

SECTION 15400 - PLUMBING

PART 1 - GENERAL

1.01 WORK INCLUDED:

- A. Cleanouts.
- B. Shock Absorbers.
- C. Floor Drains.
- D. Domestic Water Heater.
- E. Sanitary Sewer Service Connections.
- F. Water Service Connections.

1.02 RELATED WORK:

- A. Section 15010 - General Provisions - Mechanical.
- B. Section 15100 - Basic Materials and Methods - Mechanical.
- C. Section 15180 - Insulation.
- D. Section 15450 - Plumbing fixtures and trim.
- E. Division 16 - Electrical.

1.03 SUBMITTALS:

- A. See Section 01340 and Section 15010 - General Provisions - Mechanical.

PART 2 - PRODUCTS

2.01 CLEANOUTS AND CLEANOUT ACCESS COVERS:

- A. Provide caulked or threaded type extended to finished floor or wall surface. Ensure ample clearance at cleanout for rodding of drainage system.
- B. Cleanout access covers.

2.02 WATER HAMMER ARRESTORS:

- A. Water stop or equal.

2.03 FLOOR DRAINS:

- A. Lacquered cast iron body with double drainage flange, weep holes combined two piece body reversible clamping device and adjustable round-bronze strainer, and trap primers.

PART 3 - EXECUTION

SECTION 15400 - PLUMBING

3.01 REFERENCE:

- A. See Part II - Execution, Section 15100 Basic Materials and Methods - Mechanical.

3.02 EQUIPMENT INSTALLATION:

- A. Equipment shall be installed, complete with accessories, in strict accordance with manufacturer's instructions.
- B. Necessary disconnect switches, motor starters, lubrication, fittings, control devices, etc., shall be mounted/installed in proper location for servicing of equipment.
- C. Upon completion of installation, contractor shall clean system and perform all required testing as outlined in Section 15010, General Provisions - Mechanical.

END OF SECTION 15400