

***NOTE!**
SEE 9/S301 FOR THICKENED SLAB UNDER WASHER - COORDINATE W/ ARCH. AND PLUMBING DWGS.

NOTE!
GENERAL CONTRACTOR SHALL COORDINATE/VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS

NOTE!
SEE 8/S301 AND ARCH/PLUMBING DWGS. FOR SUMP PUMP PIT

NOTE!
ALL EXTERIOR WALLS ARE SHEAR WALLS SW2. SW1 INDICATES INTERIOR SHEAR WALL. SEE SHEET S002 FOR SHEAR WALL SCHEDULE.

NOTE!
SEE SOILS REPORT FOR FOOTING BEARING ELEVATION INFORMATION - SOILS ENGINEER SHALL FIELD VERIFY TOP OF FOOTING ELEVATIONS - TYPICAL

CIVIL:
James W Braswell and Associates
1005 North 4th Street
Monroe, LA 71201
Phone:
Fax:
Email: jbraswellassociates@yahoo.com


STRUCTURAL:
WGPM, Inc.
11220 Elm Lane, Suite 201
Charlotte, NC 28277
Phone: (704) 542-7199
Fax: (704) 542-7195
Email: lwright@wgpmc.com

ELECTRICAL:
Ritter Engineering
1043 Arroyo Vista Lane
Matthew, NC 28014
Phone: (704) 516-0385
Fax: (704) 644-1464
Email: shane@rittereng.com

MECHANICAL:
Shultz Engineering Group, P.C.
212 North McDowell St., Suite 204
Charlotte, NC 28204
Phone: (704) 334-7363
Fax: (704) 347-0093
Email: don@shultzeg.com

REVISIONS		
No.	Date	Description
1	11.01.13	Pool Equip., Ftgs & Rf Slope

Information contained on this drawing and in all digital files associated is authorized for use on the project named herein only and is the property of MISHRA ARCHITECTURE PLLC and may not be reproduced in any manner without express written or verbal permission from authorized individuals. Original drawing is 24"x36" and scales are as indicated. © 2011 MISHRA ARCHITECTURE PLLC



FOOTING SCHEDULE (2000 PSF)

MARK	SIZE	THICK.	REINFORCING
F35	3'-6"x3'-6"	1'-0"	4 #4 x3'-0" EACH WAY
F45	4'-6"x4'-6"	1'-0"	7 #4 x4'-0" EACH WAY
F50	5'-0"x5'-0"	1'-0"	5 #5 x4'-6" EACH WAY
F50*	5'-0"x5'-0"	1'-6"	5 #5 x4'-6" E.W.T. & B.
F55*	5'-6"x5'-6"	1'-8"	6 #5 x5'-0" E.W.T. & B.
F60	6'-0"x6'-0"	1'-0"	7 #5 x5'-6" EACH WAY
F65	6'-6"x6'-6"	1'-0"	8 #5 x6'-0" EACH WAY
F65*	6'-6"x6'-6"	1'-6"	8 #5 x6'-0" E.W.T. & B.
F75	7'-6"x7'-6"	1'-2"	8 #6 x7'-0" EACH WAY

SOILS LABORATORY SHALL VERIFY SOIL BEARING PRESSURE AT BOTTOM OF EACH FOOTING PRIOR TO PLACING CONCRETE. STRUCTURAL FILL SUPPORTING SLAB OR FOOTINGS SHALL BE PLACED IN MAXIMUM 8" LIFTS, WITH EACH 8" LIFT TESTED BY LABORATORY FOR COMPACTION LISTED IN GENERAL NOTES. E.W.T. & B. INDICATES EACH WAY TOP AND BOTTOM

WALL FOOTING SCHEDULE 4,000 PSF SOIL BEARING					
MARK	WIDTH	THICKNESS	LONGITUDINAL REINF.	TRANSVERSE REINF.	COMMENTS
WF30	3'-0"	1'-3"	3 #4 TOP 3 #5 BOTTOM	#3x2'-6" @ 24" O.C. TOP #4x2'-6" @ 24" O.C. BOTTOM	SEE 11/S301 SEE 12/S301
WF40	4'-0"	1'-4"	5 #4 TOP 5 #5 BOTTOM	#4x3'-6" @ 24" O.C. TOP #4x3'-6" @ 16" O.C. BOTTOM	SEE 11/S301 SEE 12/S301
WF55	5'-6"	1'-4"	6 #4 TOP 6 #6 BOTTOM	#4x5'-0" @ 24" O.C. TOP #5x5'-0" @ 16" O.C. BOTTOM	SEE 6/S301 SEE 4 & 6/S302

FOUNDATION AND FLOOR SLAB PLAN
1/S101
1/8" = 1'-0"


- NOTES:
- ALL ELEVATIONS REFERENCED () FROM FINISH FLOOR ELEVATION 71.50' (0-0').
 - INTERIOR TOP OF FOOTING - T.O.F. (-1'-4") TYPICAL UNLESS NOTED OTHERWISE.
 - EXTERIOR TOP OF FOOTING - T.O.F. (-1'-4") TYPICAL UNLESS NOTED OTHERWISE.
 - CONTRACT DRAWINGS SHALL NOT BE USED FOR SHOP DRAWINGS.
 - SEE SHEET S001 AND S002 FOR GENERAL NOTES, WALL STUDS AND WALL SHEATHING NOTES.
 - SEE SHEET S302 FOR COLUMN BASE PLATE AND ANCHOR ROD SCHEDULE.
 - ALL FOOTING STEPS 24" TYPICAL UNLESS NOTED OTHERWISE - SEE 2/S301.
 - SW1 INDICATES SHEAR WALL 1 - SEE SHEAR WALL SCHEDULE ON SHEET S002 TYPICAL.
 - TOP OF PIER - T.O.P. (-1'-0") TYPICAL UNLESS NOTED OTHERWISE - SEE 1/S303.

NOTE!
CONTRACT DRAWINGS SHALL NOT BE USED FOR SHOP DRAWINGS

#5 @ 24" VERTICAL ALL 8" CMU WALLS - SEE SHEET S302 - PROVIDE W1.7 (9 GA.) TRUSS TYPE HORIZONTAL JOINT REINFORCING @ 16" MAX. ALL MASONRY WALLS - TYPICAL UNLESS NOTED OTHERWISE



WGPM, Inc.
Flight - Gibbon - Patton
STRUCTURAL ENGINEERING
11220 Elm Lane, Suite 201
Charlotte, North Carolina 28277
704-542-7199 Fax: 704-542-7195
www.wgpmc.com
JOB NUMBER: 57-13



5400 I-20 & Frontage Rd.
Monroe, LA 71201
Drawing Title
Foundation and Floor Slab Plan
Phase
Construction Documents
Project No. 12-111
Sheet No. S101
Prepared by AB/LW
Checked by HLW
Date: September 16, 2013
Released for

Southern Hospitality Services

Hampton Inn and Suites

9/16/13

Hampton Inn and Suites