



FINISH NOTES

- GEN. CONTR. TO FURNISH & INSTALL CORNER GUARDS EQUAL TO AMERICAN FLOOR PRODUCTS CO. "COMET" SERIES "CG-25T 3"x3"x4" HIGH. COLOUR SELECTED BY INTERIOR DESIGNER. INSTALL AT ALL OUTSIDE GYP. BD. CORNERS IN ALL PUBLIC AREAS AND CORRIDORS.
- GEN. CONTR. TO FURNISH & INSTALL CORNER GUARDS EQUAL TO MILLER PROTECTION SYSTEMS "KODAR CORNER SAVERS", CLEAR FINISH, MODEL "CC 1142A 1 1/8"x1 1/8"x4" HIGH SELF-ADHESIVE. INSTALL AT ALL OUTSIDE GYP. BD. CORNERS IN ALL GUEST ROOM AREAS.
- PROVIDE BLOCKING BEHIND ALL WALL MOUNTED ITEMS. COORDINATE WITH OWNER FOR LOCATION OF OWNER SUPPLIED ITEMS, I.E. HAIR DRYERS, GUEST ROOM IRONING BD. SETS, ETC.

FINISH SCHEDULE

100 — Room Number

Room Name — Room Name

A1/A1

Ceiling Finish

Wall Finish

Base Finish

Floor Finish

Floors

A. Thin Set. Decorative Porcelain Tile 20"x20"

Owner Furn. Owner Installed (O.F.O.I.)

B. Thin Set. Decorative Porcelain Tile

Owner Furn. Owner Installed (O.F.O.I.)

C. Carpet and Pad

Owner Furn. Owner Installed (O.F.O.I.)

D. Not Used

E. Vinyl Composition Tile

F. Ceramic Tile 8"x8" or 12"x12" (C.F.C.I.)

G. Concrete, Sealed

H. Painted Epoxy

I. Abrasive Quarry Tile

K. EGO surface rubber flooring, or equal, with a minimum

6 mm interlocking tiles in Bedrock Color (charcoal).

Base

1. 4" Vinyl

2. Ceramic Tile (O.F.O.I.)

3. 4" Carpet w/Top Binding Edge

4. Not Used

5. Match Flooring

6. Wood Base

7. Quarry Tile

8. None Required (O.F.O.I.)

9. 6" Carpet w/Top Binding Edge

10. 6" Charcoal-colored millwork by Johnsonite or equal.

Walls

A. Painted Gyp. Bd. (Eggshell Oil Base Enamel)

B. Ceramic Tile

C. Vinyl Wallcovering

D. Painted Gyp. Bd. (Semi-gloss Oil Base Enamel)

E. Painted Concrete Masonry Units (Epoxy Paint)

F. Not Used

G. Textured -acrylic based splatter knock-down finish

to meet franchisor and/or Owner specifications.

Ceilings

1. Textured -acrylic based splatter knock-down finish

to meet franchisor and/or Owner specifications.

2. New Ceiling Panel System. Identical to

Armstrong "551 Chamfered Cirrus Pattern,

24"x24"x1/4" Regular Lay-In for Suprafine

9/16" Exposed Tee Grid, Panel 4 Grid

Colour Selected By Interior Designer From

Standard Colour Selections.

3. Painted Gyp. Bd. (Smooth Finish) Colour

Selected By Interior Designer.

Oil Base Enamel

4. New Ceiling Panel System

Identical to Armstrong

"605 Ceramaguard Nonperforated

Square Lay-In, Med. Texture 24"x24"x3/8"

for Prelude 15/16" Exposed Tee

Grid, Panel 4 Grid Colour Selected By

Owner From Standard Colour Selections.

5. New Ceiling Panel System

Identical to Armstrong

"156 Med. Floured

Square Lay-In, Med. Texture 24"x24"x3/8"

for Prelude 15/16" Exposed Tee

Grid, Panel 4 Grid Colour Selected By

Owner From Standard Colour Selections.

PROJECT NAME:

Hampton Inn

Mane Street
West Monroe, Louisiana

SHEET TITLE:

Plan @ Lobby/ Support Areas

PROJECT NO.

09017

LATEST REVISION:

△

DRAWN BY:

CJ

CHECKED BY:

RM

SHEET NUMBER:

A302

DATE:

9/13/10

