


TRANSVERSE SHEAR WALL SCHEDULE (DEMISING WALLS)				
LEVEL	SHEAR WALLS	HOLD DOWN TYP. AT EACH END OF SHEAR WALL	BOTTOM PLATE & CONNECTION	END WALL COL. AT HOLD DOWN
EL=131.25' ROOF				
3RD WALL	5/8" GYPSUM BOARD ONE SIDE OF WALL w/ ATTACH w/ 6d COOLER NAILS w/ 18" MIN. PENETRATION AT 7" SPACING	SIMPSON CS18 STRAP FASTEN w/ (22) 8d x 3" NAILS TO STUDS 12" END LENGTH REQ'D	SINGLE BOT. PLATE w/ 16d NAILS AT 6" o.c. STAGGARD TOP & BOT.	(2) 2x STUD COL.
EL=122.15' 3RD FLR.				
2ND WALL	5/8" GYPSUM BOARD BOTH SIDES OF WALL w/ ATTACH w/ 6d COOLER NAILS w/ 18" MIN. PENETRATION AT 7" SPACING	SIMPSON CS18 STRAP FASTEN w/ (22) 8d x 3" NAILS TO STUDS 12" END LENGTH REQ'D	SINGLE BOT. PLATE w/ 16d NAILS AT 6" o.c. STAGGARD TOP & BOT.	(2) 2x STUD COL.
EL=111.91' 2ND FLR.				
*GRND WALL	5/8" GYPSUM BOARD BOTH SIDES OF WALL w/ ATTACH w/ 6d COOLER NAILS w/ 18" MIN. PENETRATION AT 7" SPACING	SIMPSON HDU2-SDS2.5 FASTEN w/ (6) SDS SCREWS 1 1/2"x2 1/2" TO STUDS 5/8" SSTB w/ 11" MIN. EMBED INTO FOOTING	SINGLE BOT. PLATE w/ 5/8" BOLTS AT 24" o.c. w/ WASHERS 8" EMBED. TYP.	(2) 2x STUD COL.
EL=100.00' GRND FLR.				

SHEAR WALL SCHEDULES


SCALE: N/A

NOTES:

- ALL EXTERIOR WALLS SHALL BE SHEATHED WITH 5/8" PLYWOOD OR OSB & NAILED PER SHEAR WALL SCHEDULE.
 - ALL SHEAR WALLS WILL BE BLOCKED AT PANEL EDGES TYP.
 - REFER TO THIS SHEET FOR TYPICAL SHEAR WALL ELEVATIONS.
- * WHEN THERE IS NO GROUND FLOOR SHEAR WALL AND THE 2ND FLR. FLOOR SHEAR WALL BEARS ON A STEEL GIRDER, FOLLOW THE SHEAR WALL SCHEDULE FOR THE WALLS ABOVE AND SEE DETAIL 7/S302 FOR WALL TO GIRDER HOLD DOWN.




- NOTES:
- SEE TYPICAL PLYWOOD SHEATHING FASTENING REQUIREMENTS PER SHEARWALL SCHEDULES THIS SHEET
 - SEE FOUNDATION PLAN FOR LOCATIONS OF HOLD DOWNS. SEE NOTES & DETAILS ON THIS SHEET
 - EXTERIOR PLYWOOD TO LAP AT FLOOR LEVELS (TYP.)



2 SHEARWALL SHEATHING FASTENING DETAIL


SCALE: 3/4"=1'-0"

DET001



Richard Molenaar

ARCHITECT



PROJECT NAME: Hampton Inn
Mane Street
West Monroe, Louisiana

SHEET TITLE:
SHEAR WALLS SCHEDULES
AND DETAILS

PROJECT NO.
2010046

LATEST REVISION:

DRAWN BY: EC
CHECKED BY: GP

SHEET NUMBER:

DATE:
5-20-10

S102