

- NOTES:
- RECEPTACLE. 7. MOUNT CENTERED IN ELEVATOR MACHINE ROOM.

ENLARGED PUBLIC AREA PLAN - POWER E302 SCALE: 1/4" = 1'-0"

NOTES:

- 1. COORDINATE EXACT LAYOUT OF THIS ROOM WITH ALL OTHER TRADES PRIOR TO PROJECT START UP. ELECTRICAL CONTRACTOR TO LAY-OUT ALL ELECTRICAL EQUIPMENT LOCATIONS TO MAINTAIN NEC CODE CLEARANCES OF 36". NOTIFY G.C./OWNER IF THE REQUIRED 36" NEC CLEARANCE REQUIREMENT CAN NOT BE MET. ALL COORDINATION TO BE DONE PRIOR TO PROJECT START AND SLAB BEING POURED.
- 2. FIELD COORDINATE WITH G.C. TO PROVIDE 120V CONNECTION FOR AUTOMATIC DOORS.
- 3. COORDINATE WITH G.C./OWNER TO PROVIDE (2) CONNECTIONS FOR THE ELECTRIC STRIKE ON THE VESTIBULE DOORS. DOORS TO OPEN UPON RELEASE SWITCH ACTIVATION AT LOBBY DESK OR FIRE ALARM ACTIVATION.
- 4. PROVIDE RECESSED KNOX BOX WITH BUILDING AND ENCLOSURE KEYS PER LOCAL FIRE DEPARTMENT REQUIREMENTS.



2905-D Queen City Dr. Charlotte, NC 28208 P: (704) 399-3943 F: (704) 394-5648 www.allied-engineers.com Allied #14417

1. CONNECTION FOR 208V CIRCUIT FOR SUMP PUMP. COORDINATE WITH PLUMBING DRAWINGS. 2. COORDINATE EXACT LOCATION OF ALL DEVICES WITH THE ELEVATOR SHOP DRAWINGS. 3. MOUNT SMOKE AND HEAT DETECTORS WITHIN 2'-0" OF SPRINKLER HEADS. SMOKE DETECTORS SHALL, UPON ALARM, RECALL ELEVATOR TO THE APPROPRIATE LEVEL, AND LOCK OUT ELEVATOR VIA ELEVATOR EQUIPMENT. HEAT DETECTORS SHALL CONTROL MAIN ELEVATOR POWER. SEE ELEVATOR FIRE ALARM SHUTDOWN CONTROL SCHEMATIC. HEAT DETECTORS SHALL HAVE A LOWER RESPONSE TIME INDEX (135°F) COMPARED TO THE SPRINKLER HEADS IN THE HOISTWAY. 4. WHERE HOISTWAY IS NOT SPRINKLERED, DO NOT PROVIDE SMOKE OR HEAT DETECTORS

IN THE HOISTWAY. 5. LOCATE PIT LIGHT SWITCH AND CONVENIENCE RECEPTACLE ADJACENT TO ACCESS DOOR.

6. LIGHTS SHALL NOT BE CONNECTED TO THE LOAD SIDE TERMINALS OF THE CONVENIENCE

8. MOUNT IN ELEVATOR LOBBY AT EACH LEVEL WITHIN 15'-0" OF DOOR.

9. THE SMOKE DETECTOR(S) LOCATED IN THE DESIGNATED ELEVATOR RECALL LOBBY(S) SHALL ACTUATE THE FIRST ELEVATOR CONTROL CIRCUIT. THE SMOKE DETECTORS IN THE REMAINING ELEVATOR LOBBIES SHALL ACTUATE THE SECOND ELEVATOR CONTROL CIRCUIT. THE SMOKE DETECTORS IN THE HOISTWAY(S) AND ELEVATOR MACHINE ROOM(S) SHALL ACTUATE THE THIRD ELEVATOR CONTROL CIRCUIT, AND WHERE A MACHINE ROOM IS LOCATED AT THE DESIGNATED LEVEL. THAT ELEVATOR MACHINE ROOM SMOKE DETECTOR SHALL ALSO ACTUATE THE FIRST ELEVATOR CONTROL CIRCUIT.



ARCHITECTURE PLLC

6800 S Creek Rd, Charlotte, NC 28277 Ph: (704) 625-6554 Fax: (704) 919-5822 EMAIL:ashish@mishraarch.com WEB: www.mishraarch.com


<u>CIVIL:</u> Benchmark Engineering and Surveying 101 Highpointe Court, Suite B Brandon, MS 39042 Phone: (601) 591-1077 Fax: (601) 591-0177 Email:mikebes@bellsouth.net

STRUCTURAL: WGPM, Inc. 11220 Elm Lane, Suite 201 Charlotte, NC 28277 Phone: (704) 542-7199 Fax: (704) 542-7195 Email: lwright@wgpminc.com

<u>MEP:</u> Allied Consulting Engineers 2905-D Queen City Drive Charlotte, NC 28208 Phone: (704) 399-3943 Email: asoler@allied-engineers.com

REVISIONS				
No.	Date	Description		
1				

Information contained on this drawing and in all digital files associated is authorized for use on the project named herein only and is the property of MISHRA ARCHITECTURE PLLC and may not be reproduced in any manner without express written or verbal permission from authorized individuals. Original drawing is 24"x36" and scales are as indicated. ©2013 MISHRA ARCHITECTURE PLLC



KEY PLAN

Shiva Southaven Inc.

Holiday Inn Express & Suites

Lot 16 (Rev Lot 3) Southcrest Pkwy. Southcrest Subdivision Southaven, MS 38671

Drawing Title

ENLARGED PUBLIC AREA PLAN - POWER

Phase				
Construction Documents				
			Suites	
			ح ر	
Project No.	14-081	Sheet No.	Fxnress	
Prepared by	MAH	E302	L L L	
Checked by	EDB	ESUZ		
Date Feb	. 27, 2015		Holiday Inn	
			<u> </u>	
			Ę	