HVAC Submittal Data

SHS Development Inc.

Project: Home 2 Suites by Hilton Flowood, MS

**Architect: Richard Molenaar** 

Mech. Engineer: Innovative Engineering

**Contractor: Comfort Designs, Inc.** 

Section 1) AHU-1-7

Section 2) CU-1-7

**Section 3) thermostats** 

Section 4) MUA-1-2

**Section 5) exhaust fans** 

Section 6) electric baseboard heater

Section 7) fire dampers & access

#### **Doors**

**Section 8) grilles and registers** 


**Section 9) louvers** 

**Section 10) control dampers** 

TAG: AHU-1

## Submittal

## 3 Ton Convertible Air Handler Black Epoxy Coil - GAM5B0B36M31EA Standard Coil - GAM5B0B36M31SB



| MODEL NO. | Α    | В    | C    | D    | Е    | F   | Н    | Flow<br>Control | R-410A<br>Gas Line<br>BRAZE | R-410A<br>Liq. Line<br>BRAZE |
|-----------|------|------|------|------|------|-----|------|-----------------|-----------------------------|------------------------------|
| GAM5B0B36 | 55.7 | 21.3 | 18.4 | 45.5 | 18.4 | 9.2 | 24.8 | TXV             | 7/8                         | 3/8                          |

#### PRODUCT SPECIFICATIONS

| PRODUCT SPE                      | CIFICATIONS               |
|----------------------------------|---------------------------|
| MODEL                            | GAM5B0B36M31SB            |
|                                  | GAM5B0B36M31EA            |
| RATED VOLTS/PH/HZ.               | 208-230/1/60              |
| RATINGS ①                        | See O.D. Specifications   |
| INDOOR COIL — Type               | Plate Fin                 |
| Rows — F.P.I.                    | 3 - 14                    |
| Face Area (sq. ft.)              | 5.04                      |
| Tube Size (in.)                  | 3/8                       |
| Refrigerant Control              | TXV                       |
| Drain Conn. Size (in.) ②         | 3/4 NPT                   |
| DUCT CONNECTIONS                 | See Outline Drawing       |
| INDOOR FAN — Type                | Centrifugal               |
| Diameter-Width (In.)             | 11 X 10                   |
| No. Used                         | 1                         |
| Drive - No. Speeds               | Direct - 5                |
| CFM vs. in. w.g.                 | See Fan Performance Table |
| No. Motors — H.P.                | 1 - 1/2                   |
| Motor Speed R.P.M.               | 1050                      |
| Volts/Ph/Hz                      | 208-230/1/60              |
| F.L. Amps                        | 4.1                       |
| FILTER                           |                           |
| Filter Furnished?                | No                        |
| Type Recommended                 | Throwaway                 |
| NoSize-Thickness                 | 1 - 20 X 20 - 1 in.       |
| REFRIGERANT                      | R-410A                    |
| Ref. Line Connections            | Brazed                    |
| Coupling or Conn. Size — in. Ga  |                           |
| Coupling or Conn. Size — in. Liq |                           |
| DIMENSIONS                       | $H \times W \times D$     |
| Crated (In.)                     | 57-1/4 x 24-1/4 x 25-3/4  |
| Uncrated                         | 55-3/4 x 21-1/4 x 21-3/4  |
| WEIGHT                           |                           |
| Shipping (Lbs.)/Net (Lbs.)       | 150/142                   |

- ① These Air Handlers are A.H.R.I. certified with various Split System Air Conditioners and Heat Pumps (AHRI STANDARD 210/240). Refer to the Split System Outdoor Unit Product Data Guides for performance data.
- 2 3/4" Male Plastic Pipe (Ref.: ASTM 1785-76)







| GAM5B0B36M31SB, GAM5B0B36M31EA MINIMUM HEATER AIRFLOW CFM |  |             |  |  |  |  |  |  |  |
|---|--|-------------|--|--|--|--|--|--|--|
| Heater  | Minimum Ai   | r Speed Tap |  |  |  |  |  |  |  |
|   | Without HP   | With HP     |  |  |  |  |  |  |  |
| BAYEAAC04BK1<br>BAYEAAC04LG1                              | Tap 2  | Tap 3       |  |  |  |  |  |  |  |
| BAYEAAC05BK1<br>BAYEAAC05LG1                              | Tap 2  | Tap 3       |  |  |  |  |  |  |  |
| BAYEAAC08BK1<br>BAYEAAC08LG1                              | Tap 3  | Tap 4       |  |  |  |  |  |  |  |
| BAYEAAC10BK1<br>BAYEAAC10LG1                              | Tap 4  | Tap 5       |  |  |  |  |  |  |  |
| BAYEAAC10LG3  | Tap 4  | Tap 5       |  |  |  |  |  |  |  |
| BAYEABC15BK1  | Tap 4  | Tap 5       |  |  |  |  |  |  |  |
| BAYEABC15LG3  | Tap 4  | Tap 5       |  |  |  |  |  |  |  |
| BAYEABC20BK1  | -  | •           |  |  |  |  |  |  |  |
| BAYEACC25BK1  | and the state of t |             |  |  |  |  |  |  |  |

Note: Heating and cooling speeds are the same, factory set at Speed Tap #4.

**Note:** A "G" only signal from the comfort control will run the blower at a lower speed, factory set at Speed Tap #1. See the Sequence of Operation for additional information.

**Note:** Speed Tap 1 is NOT used for two stage systems. Two stage systems will require an airflow adjustment

|                                | AIRFLOW PERFORMANCE |               |          |       |     |      |       |            |       |     |  |  |
|--------------------------------|---------------------|---------------|----------|-------|-----|------|-------|------------|-------|-----|--|--|
| GAM5B0B36M31SB, GAM5B0B36M31EA |                     |               |          |       |     |      |       |            |       |     |  |  |
| EXTERNAL STATIC (in w.g)       |                     | AIRFLOW (CFM) |          |       |     |      |       |            |       |     |  |  |
|                                |                     | Speed Ta      | ps - 230 | VOLTS |     |      | Speed | Taps - 208 | VOLTS |     |  |  |
|                                | 5                   | 4 †           | 3        | 2     | 1   | 5    | 4†    | 3          | 2     | 1   |  |  |
| 0                              | 1438                | 1387          | 1197     | 1013  | 732 | 1435 | 1383  | 1194       | 1009  | 729 |  |  |
| 0.1                            | 1394                | 1340          | 1143     | 945   | 552 | 1388 | 1334  | 1137       | 939   | 546 |  |  |
| 0.2                            | 1350                | 1299          | 1090     | 892   | 413 | 1341 | 1291  | 1082       | 884   | 404 |  |  |
| 0.3                            | 1301                | 1245          | 1031     | 817   | 305 | 1289 | 1233  | 1019       | 806   | 293 |  |  |
| 0.4                            | 1253                | 1197          | 975      | 751   | 209 | 1239 | 1183  | 960        | 737   | 195 |  |  |
| 0.5                            | 1205                | 1151          | 917      | 651   | -   | 1188 | 1134  | 900        | 634   | -   |  |  |
| 0.6                            | 1155                | 1094          | 837      | 578   | -   | 1136 | 1075  | 817        | 559   | -   |  |  |
| 0.7                            | 1099                | 1032          | 766      | 499   | -   | 1077 | 1010  | 744        | 476   | -   |  |  |
| 0.8                            | 1039                | 972           | 691      | 453   | -   | 1014 | 946   | 666        | -     | -   |  |  |
| 0.9                            | 964                 | 889           | 633      | 409   | -   | 936  | 861   | 605        | -     | -   |  |  |

#### NOTES:

- 1. Values are with wet coil and without filters.
- 2. Contact your particular filter manufacturer for pressure drop data.
- 3. Electric heater pressure drop is negligible and is included within the airflow data.
- 4. Tap 1 is an continuous fan speed tap.
- 5. † Factory Setting

|  |                       |          |       | WIR                   | ING DATA           |                     |          |       |                       |  |  |
|--|-----------------------|----------|-------|-----------------------|--------------------|---------------------|----------|-------|-----------------------|--|--|
| GAM5B0B36M31SB, GAM5B0B36M31EA                     |                       |          |       |                       |                    |                     |          |       |                       |  |  |
|  |                       |          |       | 240 V                 | OLT                |                     |          |       | 208 \                 | OLT  |  |
| Heater<br>Model<br>No.                             | No.<br>of<br>Circuits | Сар      | acity | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload | Capacity |       | Heater<br>Amps<br>per | Minimum<br>Circuit   | Maximum<br>Overload  |
|  |                       | kW       | втин  | Circuit               | Ampacity           | Protection          | kW       | втин  | Circuit               | Ampacity   | Protection   |
| No Heater  | -                     | •        | -     | 4.1*                  | 5                  | 15                  | -        | -     | 4.1*                  | 5  | 15   |
| BAYEAAC04BK1<br>BAYEAAC04LG1                       | 1                     | 3.84     | 13100 | 16.0                  | 25                 | 25                  | 2.88     | 9800  | 13.8                  | 22   | 25   |
| BAYEAAC05BK1<br>BAYEAAC05LG1                       | 1                     | 4.80     | 16400 | 20.0                  | 30                 | 30                  | 3.60     | 12300 | 17.3                  | 27   | 30   |
| BAYEAAC08BK1<br>BAYEAAC08LG1                       | 1                     | 7.68     | 26200 | 32.0                  | 45                 | 45                  | 5.76     | 19700 | 27.7                  | 40   | 40   |
| BAYEAAC10BK1<br>BAYEAAC10LG1                       | 1                     | 9.60     | 32800 | 40.0                  | 55                 | 60                  | 7.20     | 24600 | 34.6                  | 48   | 50   |
| BAYEAAC10LG3                                       | 1-3 PH                | 9.60     | 32800 | 23.1                  | 33                 | 35                  | 7.20     | 24600 | 20.0                  | 30   | 30   |
| BAYEABC15LG3                                       | 1-3 PH                | 14.40    | 49200 | 34.6                  | 48                 | 50                  | 10.80    | 36900 | 30.0                  | 42   | 45   |
| BAYEABC15BK1 - Circuit 11                          | 2                     | 9.60     | 32800 | 40                    | 55                 | 60                  | 7.20     | 24600 | 34.6                  | 48   | 50   |
| BAYEABC15BK1 - Circuit 2                           | ۷                     | 4.80     | 16400 | 20                    | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22   | 25   |
| Note: * Motor Amps  ① MCA and MOP for circuit 1 co | ntains the            | motor ar | nns   |                       |                    |                     |          |       | ·                     | Accessed the second | Annual Control of the |

#### Notes:

- 1. See Product Data or Air Handler nameplate for approved combinations of Air Handlers and Heaters
- 2. Heater model numbers may have additional suffix digits.

## **Mechanical Specifications**

- · Unique Cabinet Design
- Double Wall Foamed and Formed Cabinet System
- Water Proof Cabinet Design
- R-4.2 Insulating Value (Avg Insulating Value R-8.2)
- Composite Foamed Cabinet Doors
- Sweat Eliminating Cabinet Design
- Loose Fiber Eliminating Cabinet Design
- Smooth Cleanable Cabinet Design
- 2% or Less air leakage
- Precision Durable Door Seals
- Modular Cabinet
- Multi-Position UP/Down Flow Horizontal Left /Right
- Phillips head door fasteners
- · Side Return Option
- Refrigerant Connections
- Condensate Connections
- Premarked Conduit Connection Locations
- Vortica® Blower with Integrated Slide Deck for Easy Removal
- Polarized Plug connections on Blower
- Aluminum Coil with Integrated Slide Deck for Easy Removal
- Slide in Electric Heaters with polarized plug connections (sold as accessory)
- · Polarized Plug connections for Electric Heater
- UVC light kit with safety switch and polarized plug connections (sold as accessory)

- Labeled Panels and connections
- 1 1/4" to 1" And 3/4" to 1/2" Conduit connection on Left, Right and Top
- Molded in 1" Standard Filter rail
- R-410A Thermal Expansion Valve
- R-22 conversion Thermal Expansion Valve available (sold as accessory)
- · Low Voltage Pigtail Connections
- Enhanced Coil Fin Patented
- · Blow Through Design
- High Efficiency ECM Motor
- Maximum Width of 23.5"
- · Compact 20.8" depth with doors removed
- Integrated Horizontal Drain pans
- Soft start fan motor operation
- Built in fan delay modes
- Single Color
- Fused 24V Power
- · Safety Door Switch
- 5 year warranty
- 10-year warranty registered
- Optional extended warranty available








Ingersoll Rand 6200 Troup Highway Tyler, TX 75707

The manufacturer has a policy of continuous product and product data improvement and it reserves the right to change design and specification without notice.

TAG: AHU-2

## **Submittal**

# 5 Ton Convertible Air Handler Black Epoxy Coil - GAM5B0C60M51EA Standard Coil - GAM5B0C60M51SB



| MODEL NO. | Α    | В    | С    | D    | E    | F    | Н    |     | R-410A<br>Gas Line<br>BRAZE |     |
|-----------|------|------|------|------|------|------|------|-----|-----------------------------|-----|
| GAM5B0C60 | 61.7 | 23.5 | 20.5 | 51.5 | 20.5 | 10.3 | 24.9 | TXV | 7/8                         | 3/8 |

#### PRODUCT SPECIFICATIONS

| PRODUCT SPE                      | CIFICATIONS               |
|----------------------------------|---------------------------|
| MODEL                            | GAM5B0C60M51SB            |
|                                  | GAM5B0C60M51EA            |
| RATED VOLTS/PH/HZ.               | 208-230/1/60              |
| RATINGS ①                        | See O.D. Specifications   |
| INDOOR COIL — Type               | Plate Fin                 |
| Rows — F.P.I.                    | 4 - 14                    |
| Face Area (sq. ft.)              | 5.96                      |
| Tube Size (in.)                  | 3/8                       |
| Refrigerant Control              | TXV                       |
| Drain Conn. Size (in.) 2         | 3/4 NPT                   |
| DUCT CONNECTIONS                 | See Outline Drawing       |
| INDOOR FAN — Type                | Centrifugal               |
| Diameter-Width (In.)             | 11 X 10                   |
| No. Used                         | 1                         |
| Drive - No. Speeds               | Direct - 5                |
| CFM vs. in. w.g.                 | See Fan Performance Table |
| No. Motors — H.P.                | 1 - 1                     |
| Motor Speed R.P.M.               | 1050                      |
| Volts/Ph/Hz                      | 208-230/1/60              |
| F.L. Amps                        | 7.6                       |
| FILTER                           |                           |
| Filter Furnished?                | No                        |
| Type Recommended                 | Throwaway                 |
| NoSize-Thickness                 | 1 - 22 X 20 - 1 in.       |
| REFRIGERANT                      | R-410A                    |
| Ref. Line Connections            | Brazed                    |
| Coupling or Conn. Size — in. Ga  | s 7/8                     |
| Coupling or Conn. Size — in. Liq | . 3/8                     |
| DIMENSIONS                       | $H \times W \times D$     |
| Crated (In.)                     | 63-1/4 x 27-1/2 x 25-3/4  |
| Uncrated                         | 61-3/4 x 23-1/2 x 21-3/4  |
| WEIGHT                           |                           |
| Shipping (Lbs.)/Net (Lbs.)       | 180/170                   |

- ① These Air Handlers are A.H.R.I. certified with various Split System Air Conditioners and Heat Pumps (AHRI STANDARD 210/240). Refer to the Split System Outdoor Unit Product Data Guides for performance data.
- 2 3/4" Male Plastic Pipe (Ref.: ASTM 1785-76)







| GAM5B0C60M51SB, GAI           | M5B0C60M51EA MINIMUM             | HEATER AIRFLOW CFM            |  |  |  |  |  |  |  |  |
|-------------------------------|----------------------------------|-------------------------------|--|--|--|--|--|--|--|--|
| Heater                        | Minimum Ai                       | r Speed Tap                   |  |  |  |  |  |  |  |  |
|                               | Without HP                       | With HP                       |  |  |  |  |  |  |  |  |
| BAYEAAC04BK1<br>BAYEAAC04LG1  | Tap 2                            | Tap 3                         |  |  |  |  |  |  |  |  |
| BAYEAAC05BK1<br>BAYEAAC05LG1  | Tap 2                            | Tap 3                         |  |  |  |  |  |  |  |  |
| BAYEAAC08BK1<br>BAYEAAC08LG1  | Tap 2                            | Tap 3                         |  |  |  |  |  |  |  |  |
| BAYEAAC10BK1<br>BAYEAAC10LG1  | Tap 2                            | Tap 3                         |  |  |  |  |  |  |  |  |
| BAYEAAC10LG3                  | Tap 2                            | Tap 3                         |  |  |  |  |  |  |  |  |
| BAYEABC15BK1                  | Tap 3                            | Tap 4                         |  |  |  |  |  |  |  |  |
| BAYEABC15LG3                  | Tap 3                            | Tap 4                         |  |  |  |  |  |  |  |  |
| BAYEABC20BK1                  | Tap 3                            | Tap 4                         |  |  |  |  |  |  |  |  |
| BAYEACC25BK1                  | Tap 4 Tap 5 ①②                   |                               |  |  |  |  |  |  |  |  |
| If the air handler is applied | in downflow or horizontal config | gurations, the airflow should |  |  |  |  |  |  |  |  |

Note: Heating and cooling speeds are the same, factory set at Speed Tap #4.

not exceed 2000 CFM. Airflow above 2000 CFM could result in water blow-off. ② Tap 5 can be used but only when the external static pressure is .6" or above.

**Note:** A "G" only signal from the comfort control will run the blower at a lower speed, factory set at Speed Tap #1. See the Sequence of Operation for additional information.

Note: Speed Tap 1 is NOT used for two stage systems. Two stage systems will require an airflow adjustment

|                                | AIRFLOW PERFORMANCE |               |          |       |      |      |       |            |       |      |  |  |
|--------------------------------|---------------------|---------------|----------|-------|------|------|-------|------------|-------|------|--|--|
| GAM5B0C60M51SB, GAM5B0C60M51EA |                     |               |          |       |      |      |       |            |       |      |  |  |
| EXTERNAL STATIC (in w.g)       |                     | AIRFLOW (CFM) |          |       |      |      |       |            |       |      |  |  |
|                                |                     | Speed Ta      | ps - 230 | VOLTS |      |      | Speed | Taps - 208 | VOLTS |      |  |  |
|                                | 5                   | 4 †           | 3        | 2     | 1    | 5    | 4 †   | 3          | 2     | 1    |  |  |
| 0                              | 2327                | 2020          | 1914     | 1819  | 1125 | 2324 | 2017  | 1910       | 1816  | 1122 |  |  |
| 0.1                            | 2285                | 1980          | 1873     | 1780  | 990  | 2279 | 1974  | 1867       | 1774  | 984  |  |  |
| 0.2                            | 2237                | 1944          | 1835     | 1740  | 831  | 2228 | 1935  | 1826       | 1731  | 822  |  |  |
| 0.3                            | 2182                | 1908          | 1800     | 1705  | 600  | 2171 | 1896  | 1789       | 1693  | 589  |  |  |
| 0.4                            | 2125                | 1869          | 1756     | 1659  | 331  | 2111 | 1854  | 1742       | 1645  | 317  |  |  |
| 0.5                            | 2062                | 1830          | 1717     | 1620  | 249  | 2045 | 1813  | 1700       | 1603  | 232  |  |  |
| 0.6                            | 1995                | 1747          | 1664     | 1575  | 187  | 1975 | 1727  | 1644       | 1555  | 168  |  |  |
| 0.7                            | 1922                | 1707          | 1629     | 1540  | -    | 1899 | 1685  | 1607       | 1518  | -    |  |  |
| 0.8                            | 1844                | 1673          | 1594     | 1502  | -    | 1819 | 1648  | 1569       | 1477  | -    |  |  |
| 0.9                            | 1761                | 1629          | 1553     | 1464  | _    | 1733 | 1601  | 1525       | 1436  | -    |  |  |

#### NOTES:

- 1. Values are with wet coil and without filters.
- 2. Contact your particular filter manufacturer for pressure drop data.
- 3. Electric heater pressure drop is negligible and is included within the airflow data.
- 4. Tap 1 is an continuous fan speed tap.
- 5. If the air handler is applied in downflow or horizontal configurations, the airflow should not exceed 2000 CFM. Airflow above 2000 CFM could result in water blow-off.
- 6. † Factory Setting

|                              |                                |       |       | WIRIN                 | IG DATA            |                     | **       |       |                       |                    |                     |  |
|------------------------------|--------------------------------|-------|-------|-----------------------|--------------------|---------------------|----------|-------|-----------------------|--------------------|---------------------|--|
|                              | GAM5B0C60M51SB, GAM5B0C60M51EA |       |       |                       |                    |                     |          |       |                       |                    |                     |  |
|                              |                                |       |       | 240                   | VOLT               |                     |          |       | 208 V                 | /OLT               | -                   |  |
| Heater<br>Model<br>No.       | No.<br>of<br>Circuits          | Сар   | acity | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload | Capacity |       | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload |  |
|                              |                                | kW    | втин  | Circuit               | Ampacity           | Protection          | kW       | втин  | Circuit               | Ampacity           | Protection          |  |
| No Heater                    | -                              | -     | -     | 7.6*                  | 10                 | 15                  | -        | -     | 7.6*                  | 10                 | 15                  |  |
| BAYEAAC04BK1<br>BAYEAAC04LG1 | 1                              | 3.84  | 13100 | 16.0                  | 30                 | 30                  | 2.88     | 9800  | 13.8                  | 27                 | 30                  |  |
| BAYEAAC05BK1<br>BAYEAAC05LG1 | 1                              | 4.80  | 16400 | 20.0                  | 35                 | 35                  | 3.60     | 12300 | 17.3                  | 31                 | 35                  |  |
| BAYEAAC08BK1<br>BAYEAAC08LG1 | 1                              | 7.68  | 26200 | 32.0                  | 50                 | 50                  | 5.76     | 19700 | 27.7                  | 44                 | 45                  |  |
| BAYEAAC10BK1<br>BAYEAAC10LG1 | 1                              | 9.60  | 32800 | 40.0                  | 60                 | 60                  | 7.20     | 24600 | 34.6                  | 53                 | 60                  |  |
| BAYEAAC10LG3                 | 1-3 PH                         | 9.60  | 32800 | 23.1                  | 37                 | 40                  | 7.20     | 24600 | 20.0                  | 34                 | 35                  |  |
| BAYEABC15LG3                 | 1-3 PH                         | 14.40 | 49200 | 34.6                  | 52                 | 60                  | 10.80    | 36900 | 30.0                  | 46                 | 50                  |  |
| BAYEABC15BK1 - Circuit 1①    | 2                              | 9.60  | 32800 | 40                    | 60                 | 60                  | 7.20     | 24600 | 34.6                  | 53                 | 60                  |  |
| BAYEABC15BK1 - Circuit 2     | 2                              | 4.80  | 16400 | 20                    | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22                 | 25                  |  |
| BAYEABC20BK1 - Circuit 1 ①   | 0                              | 9.60  | 32800 | 40                    | 60                 | 60                  | 7.20     | 24600 | 34.6                  | 53                 | 60                  |  |
| BAYEABC20BK1 - Circuit 2     | 2                              | 9.60  | 32800 | 40                    | 50                 | 50                  | 7.20     | 24600 | 34.6                  | 43                 | 45                  |  |
| BAYEACC25BK1@3- Circuit 1①   |                                | 9.60  | 32800 | 40                    | 60                 | 60                  | 7.20     | 24600 | 34.6                  | 53                 | 60                  |  |
| BAYEACC25BK1 - Circuit 2     | 3                              | 9.60  | 32800 | 40                    | 50                 | 50                  | 7.20     | 24600 | 34.6                  | 43                 | 45                  |  |
| BAYEACC25BK1 - Circuit 3     |                                | 4.80  | 16400 | 20                    | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22                 | 25                  |  |


Note: \* Motor Amps

- MCA and MOP for circuit 1 contains the motor amps
   If the air handler is applied in downflow or horizontal configurations, the airflow should not exceed 2000 CFM. Airflow above 2000 CFM could result in water blow-off.
- 3 Tap 5 can be used but only when the external static pressure is .6" or above.

TAG: AHU- 3, 7

## **Submittal**

# 4 Ton Convertible Air Handler Black Epoxy Coil - GAM5B0C48M41EA Standard Coil - GAM5B0C48M41SB



| MODEL NO. | Α    | В    | С    | D    | E    | F    | Н    | Flow<br>Control | R-410A<br>Gas Line<br>BRAZE | R-410A<br>Liq. Line<br>BRAZE |
|-----------|------|------|------|------|------|------|------|-----------------|-----------------------------|------------------------------|
| GAM5B0C48 | 61.7 | 23.5 | 20.5 | 51.5 | 20.5 | 10.3 | 24.9 | TXV             | 7/8                         | 3/8                          |

#### **PRODUCT SPECIFICATIONS**

| PRODUCT SPE                      | CIFICATIONS               |
|----------------------------------|---------------------------|
| MODEL                            | GAM5B0C48M41SB            |
|                                  | GAM5B0C48M41EA            |
| RATED VOLTS/PH/HZ.               | 208-230/1/60              |
| RATINGS ①                        | See O.D. Specifications   |
| INDOOR COIL — Type               | Plate Fin                 |
| Rows — F.P.I.                    | 4 - 14                    |
| Face Area (sq. ft.)              | 5.96                      |
| Tube Size (in.)                  | 3/8                       |
| Refrigerant Control              | TXV                       |
| Drain Conn. Size (in.) ②         | 3/4 NPT                   |
| DUCT CONNECTIONS                 | See Outline Drawing       |
| INDOOR FAN — Type                | Centrifugal               |
| Diameter-Width (In.)             | 11 X 10                   |
| No. Used                         | 1                         |
| Drive - No. Speeds               | Direct - 5                |
| CFM vs. in. w.g.                 | See Fan Performance Table |
| No. Motors — H.P.                | 1 - 3/4                   |
| Motor Speed R.P.M.               | 1050                      |
| Volts/Ph/Hz                      | 208-230/1/60              |
| F.L. Amps                        | 6.0                       |
| FILTER                           |                           |
| Filter Furnished?                | No                        |
| Type Recommended                 | Throwaway                 |
| NoSize-Thickness                 | 1 - 22 X 20 - 1 in.       |
| REFRIGERANT                      | R-410A                    |
| Ref. Line Connections            | Brazed                    |
| Coupling or Conn. Size — in. Ga  | s 7/8                     |
| Coupling or Conn. Size — in. Liq |                           |
| DIMENSIONS                       | $H \times W \times D$     |
| Crated (In.)                     | 63-1/4 x 27-1/2 x 25-3/4  |
| Uncrated                         | 61-3/4 x 23-1/2 x 21-3/4  |
| WEIGHT                           |                           |
| Shipping (Lbs.)/Net (Lbs.)       | 176/166                   |

- These Air Handlers are A.H.R.I. certified with various Split System Air Conditioners and Heat Pumps (AHRI STANDARD 210/240). Refer to the Split System Outdoor Unit Product Data Guides for performance data.
- 2 3/4" Male Plastic Pipe (Ref.: ASTM 1785-76)





| GAM5B0C48M41SB, GA           | GAM5B0C48M41SB, GAM5B0C48M41EA MINIMUM HEATER AIRFLOW CFM |             |  |  |  |  |  |  |  |  |
|------------------------------|---|-------------|--|--|--|--|--|--|--|--|
| Heater                       | Minimum Ai  | r Speed Tap |  |  |  |  |  |  |  |  |
|                              | Without HP  | With HP     |  |  |  |  |  |  |  |  |
| BAYEAAC04BK1<br>BAYEAAC04LG1 | Tap 2   | Тар 3       |  |  |  |  |  |  |  |  |
| BAYEAAC05BK1<br>BAYEAAC05LG1 | Tap 2   | Tap 3       |  |  |  |  |  |  |  |  |
| BAYEAAC08BK1<br>BAYEAAC08LG1 | Tap 2   | Tap 3       |  |  |  |  |  |  |  |  |
| BAYEAAC10BK1<br>BAYEAAC10LG1 | Tap 2   | Tap 3       |  |  |  |  |  |  |  |  |
| BAYEAAC10LG3                 | Tap 2   | Tap 3       |  |  |  |  |  |  |  |  |
| BAYEABC15BK1                 | Tap 3   | Tap 4       |  |  |  |  |  |  |  |  |
| BAYEABC15LG3                 | Tap 3   | Tap 4       |  |  |  |  |  |  |  |  |
| BAYEABC20BK1                 | Tap 3   | Tap 4       |  |  |  |  |  |  |  |  |
| BAYEACC25BK1                 | Tap 4   | Tap 5       |  |  |  |  |  |  |  |  |

Note: Heating and cooling speeds are the same, factory set at Speed Tap #4.

**Note:** A "G" only signal from the comfort control will run the blower at a lower speed, factory set at Speed Tap #1. See the Sequence of Operation for additional information.

**Note:** Speed Tap 1 is NOT used for two stage systems. Two stage systems will require an airflow adjustment

|                          |               |   | AIRFLO | W PERF   | ORMAN  | CE     |      |      |      |     |  |  |  |  |
|--------------------------|---------------|---|--------|----------|--------|--------|------|------|------|-----|--|--|--|--|
|                          |               | GAM5  | B0C48N | 141SB, G | AM5B0C | 48M41E | 4    |      |      |     |  |  |  |  |
| EXTERNAL STATIC (in w.g) | AIRFLOW (CFM) |   |        |          |        |        |      |      |      |     |  |  |  |  |
|                          |               | Speed Taps - 230 VOLTS Speed Taps - 208 VOLTS |        |          |        |        |      |      |      |     |  |  |  |  |
|                          | 5             | 4 †   | 3      | 2        | 1      | 5      | 4†   | 3    | 2    | 1   |  |  |  |  |
| 0                        | 1913          | 1770  | 1694   | 1593     | 866    | 1910   | 1767 | 1691 | 1590 | 863 |  |  |  |  |
| 0.1                      | 1874          | 1730  | 1653   | 1547     | 791    | 1868   | 1724 | 1647 | 1541 | 785 |  |  |  |  |
| 0.2                      | 1834          | 1690  | 1611   | 1505     | 699    | 1825   | 1681 | 1602 | 1496 | 690 |  |  |  |  |
| 0.3                      | 1791          | 1646  | 1567   | 1456     | 620    | 1780   | 1635 | 1556 | 1445 | 609 |  |  |  |  |
| 0.4                      | 1748          | 1600  | 1521   | 1410     | 537    | 1734   | 1586 | 1506 | 1396 | 522 |  |  |  |  |
| 0.5                      | 1708          | 1556  | 1476   | 1367     | 453    | 1691   | 1539 | 1459 | 1350 | 437 |  |  |  |  |
| 0.6                      | 1668          | 1516  | 1436   | 1326     | 370    | 1648   | 1496 | 1416 | 1306 | 351 |  |  |  |  |
| 0.7                      | 1629          | 1475  | 1394   | 1283     | -      | 1607   | 1452 | 1372 | 1260 | -   |  |  |  |  |
| 0.8                      | 1588          | 1435  | 1352   | 1236     | -      | 1563   | 1410 | 1327 | 1211 | -   |  |  |  |  |
| 0.9                      | 1541          | 1390  | 1304   | 1183     | -      | 1513   | 1362 | 1276 | 1156 |     |  |  |  |  |

#### NOTES:

- 1. Values are with wet coil and without filters.
- 2. Contact your particular filter manufacturer for pressure drop data.
- 3. Electric heater pressure drop is negligible and is included within the airflow data.
- 4. Tap 1 is an continuous fan speed tap.
- 5. † Factory Setting

|  |                       |          |       | WIR                   | ING DATA           |                     |          |       |                       |                    |                     |  |
|--|-----------------------|----------|-------|-----------------------|--------------------|---------------------|----------|-------|-----------------------|--------------------|---------------------|--|
| GAM5B0C48M41SB, GAM5B0C48M41EA                     |                       |          |       |                       |                    |                     |          |       |                       |                    |                     |  |
|  |                       |          |       | 240 V                 | OLT                |                     | 208 VOLT |       |                       |                    |                     |  |
| Heater<br>Model<br>No.                             | No.<br>of<br>Circuits | Capacity |       | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload | Capacity |       | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload |  |
|  |                       | kW       | втин  | Circuit               | Ampacity           | Protection          | kW       | втин  | Circuit               | Ampacity           | Protection          |  |
| No Heater  | -                     | -        | -     | 6.0*                  | 8                  | 15                  | -        | -     | 6.0*                  | 8                  | 15                  |  |
| BAYEAAC04BK1<br>BAYEAAC04LG1                       | 1                     | 3.84     | 13100 | 16.0                  | 28                 | 30                  | 2.88     | 9800  | 13.8                  | 25                 | 25                  |  |
| BAYEAAC05BK1<br>BAYEAAC05LG1                       | 1                     | 4.80     | 16400 | 20.0                  | 33                 | 35                  | 3.60     | 12300 | 17.3                  | 29                 | 30                  |  |
| BAYEAAC08BK1<br>BAYEAAC08LG1                       | 1                     | 7.68     | 26200 | 32.0                  | 48                 | 50                  | 5.76     | 19700 | 27.7                  | 42                 | 45                  |  |
| BAYEAAC10BK1<br>BAYEAAC10LG1                       | 1                     | 9.60     | 32800 | 40.0                  | 58                 | 60                  | 7.20     | 24600 | 34.6                  | 51                 | 60                  |  |
| BAYEAAC10LG3                                       | 1-3 PH                | 9.60     | 32800 | 23.1                  | 36                 | 40                  | 7.20     | 24600 | 20.0                  | 32                 | 35                  |  |
| BAYEABC15LG3                                       | 1-3 PH                | 14.40    | 49200 | 34.6                  | 50                 | 50                  | 10.80    | 36900 | 30.0                  | 44                 | 45                  |  |
| BAYEABC15BK1 - Circuit 1 ①                         |                       | 9.60     | 32800 | 40                    | 58                 | 60                  | 7.20     | 24600 | 34.6                  | 51                 | 60                  |  |
| BAYEABC15BK1 - Circuit 2                           | 2                     | 4.80     | 16400 | 20                    | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22                 | 25                  |  |
| BAYEABC20BK1 - Circuit 1                           |                       | 9.60     | 32800 | 40                    | 58                 | 60                  | 7.20     | 24600 | 34.6                  | 51                 | 60                  |  |
| BAYEABC20BK1 - Circuit 2                           | 2                     | 9.60     | 32800 | 40                    | 50                 | 50                  | 7.20     | 24600 | 34.6                  | 43                 | 45                  |  |
| BAYEACC25BK1 - Circuit 1①                          |                       | 9.60     | 32800 | 40                    | 58                 | 60                  | 7.20     | 24600 | 34.6                  | 51                 | 60                  |  |
| BAYEACC25BK1 - Circuit 2                           | 3                     | 9.60     | 32800 | 40                    | 50                 | 50                  | 7.20     | 24600 | 34.6                  | 43                 | 45                  |  |
| BAYEACC25BK1 - Circuit 3                           |                       | 4.80     | 16400 | 20                    | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22                 | 25                  |  |
| Note: * Motor Amps  ① MCA and MOP for circuit 1 co | ntains the i          | motor ar | nps   |                       | **                 |                     |          |       |                       |                    |                     |  |


#### Notes:

- 1. See Product Data or Air Handler nameplate for approved combinations of Air Handlers and Heaters
- 2. Heater model numbers may have additional suffix digits.

TAG: AHU-4

## **Submittal**

## 3-1/2 Ton Convertible Air Handler Black Epoxy Coil - GAM5B0C42M31EA Standard Coil - GAM5B0C42M31SB



| MODEL NO. | А    | В    | С    | D    | E    | F    | Ĥ    | Flow<br>Control | R-410A<br>Gas Line<br>BRAZE | R-410A<br>Liq. Line<br>BRAZE |
|-----------|------|------|------|------|------|------|------|-----------------|-----------------------------|------------------------------|
| GAM5B0C42 | 56.9 | 23.5 | 20.5 | 46.7 | 20.5 | 10.3 | 24.5 | TXV             | 7/8                         | 3/8                          |

#### **PRODUCT SPECIFICATIONS**

| PRODUCT SPE                       | CIFICATIONS               |
|-----------------------------------|---------------------------|
| MODEL                             | GAM5B0C42M31SB            |
|                                   | GAM5B0C42M31EA            |
| RATED VOLTS/PH/HZ.                | 208-230/1/60              |
| RATINGS ①                         | See O.D. Specifications   |
| INDOOR COIL — Type                | Plate Fin                 |
| Rows — F.P.I.                     | 4 - 14                    |
| Face Area (sq. ft.)               | 5.04                      |
| Tube Size (in.)                   | 3/8                       |
| Refrigerant Control               | TXV                       |
| Drain Conn. Size (in.) ②          | 3/4 NPT                   |
| DUCT CONNECTIONS                  | See Outline Drawing       |
| INDOOR FAN — Type                 | Centrifugal               |
| Diameter-Width (In.)              | 11 X 10                   |
| No. Used                          | 1                         |
| Drive - No. Speeds                | Direct - 5                |
| CFM vs. in. w.g.                  | See Fan Performance Table |
| No. Motors — H.P.                 | 1 - 1/2                   |
| Motor Speed R.P.M.                | 1050                      |
| Volts/Ph/Hz                       | 208-230/1/60              |
| F.L. Amps                         | 4.1                       |
| FILTER                            |                           |
| Filter Furnished?                 | No.                       |
| Type Recommended                  | Throwaway                 |
| NoSize-Thickness                  | 1 - 20 X 22 - 1 in.       |
| REFRIGERANT                       | R-410A                    |
| Ref. Line Connections             | Brazed                    |
| Coupling or Conn. Size - in. Gas  | s 7/8                     |
| Coupling or Conn. Size - in. Liq. | . 3/8                     |
| DIMENSIONS                        | HxWxD                     |
| Crated (In.)                      | 58-1/2 x 27-1/2 x 25-3/4  |
| Uncrated                          | 56-7/8 x 23-1/2 x 21-3/4  |
| WEIGHT                            |                           |
| Shipping (Lbs.)/Net (Lbs.)        | 163/153                   |

- ① These Air Handlers are A.H.R.I. certified with various Split System Air Conditioners and Heat Pumps (AHRI STANDARD 210/240). Refer to the Split System Outdoor Unit Product Data Guides for performance data.
- 2 3/4" Male Plastic Pipe (Ref.: ASTM 1785-76)







| GAM5B0C42M31SB, GA           | M5B0C42M31EA MINIMUM | HEATER AIRFLOW CFM |
|------------------------------|----------------------|--------------------|
| Heater                       | Minimum Ai           | r Speed Tap        |
|                              | Without HP           | With HP            |
| BAYEAAC04BK1<br>BAYEAAC04LG1 | Tap 2                | Tap 3              |
| BAYEAAC05BK1<br>BAYEAAC05LG1 | Tap 2                | Tap 3              |
| BAYEAAC08BK1<br>BAYEAAC08LG1 | Tap 2                | Tap 3              |
| BAYEAAC10BK1<br>BAYEAAC10LG1 | Tap 2                | Tap 3              |
| BAYEAAC10LG3                 | Tap 2                | Tap 3              |
| BAYEABC15BK1                 | Tap 3                | Tap 4              |
| BAYEABC15LG3                 | Tap 3                | Tap 4              |
| BAYEABC20BK1                 | -                    | 10                 |
| BAYEACC25BK1                 | -                    | <u> </u>           |

Note: Heating and cooling speeds are the same, factory set at Speed Tap #4.

**Note:** A "G" only signal from the comfort control will run the blower at a lower speed, factory set at Speed Tap #1. See the Sequence of Operation for additional information.

**Note:** Speed Tap 1 is NOT used for two stage systems. Two stage systems will require an airflow adjustment

|                          |                                |   | AIRFLO | W PERF | ORMAN | CE   |      | Brownian transfer der Gertre von den der verbende von den der verbende von der verbende von der verbende verbe |      | Market of Arthropology of Compa |  |  |  |  |  |
|--------------------------|--------------------------------|---|--------|--------|-------|------|------|--|------|---------------------------------|--|--|--|--|--|
|                          | GAM5B0C42M31SB, GAM5B0C42M31EA |   |        |        |       |      |      |  |      |                                 |  |  |  |  |  |
| EXTERNAL STATIC (in w.g) | AIRFLOW (CFM)                  |   |        |        |       |      |      |  |      |                                 |  |  |  |  |  |
|                          |                                | Speed Taps - 230 VOLTS Speed Taps - 208 VOLTS |        |        |       |      |      |  |      |                                 |  |  |  |  |  |
|                          | 5                              | 4†  | 3      | 2      | 1     | 5    | 4†   | 3  | 2    | 1                               |  |  |  |  |  |
| 0                        | 1644                           | 1575  | 1401   | 1266   | 752   | 1641 | 1572 | 1398   | 1263 | 749                             |  |  |  |  |  |
| 0.1                      | 1596                           | 1525  | 1346   | 1215   | 665   | 1590 | 1519 | 1340   | 1209 | 659                             |  |  |  |  |  |
| 0.2                      | 1550                           | 1480  | 1300   | 1157   | 569   | 1542 | 1471 | 1291   | 1148 | 560                             |  |  |  |  |  |
| 0.3                      | 1509                           | 1437  | 1252   | 1110   | 492   | 1497 | 1425 | 1241   | 1099 | 480                             |  |  |  |  |  |
| 0.4                      | 1463                           | 1391  | 1205   | 1058   | 384   | 1449 | 1377 | 1191   | 1043 | 370                             |  |  |  |  |  |
| 0.5                      | 1420                           | 1345  | 1151   | 980    | 327   | 1403 | 1328 | 1134   | 963  | 310                             |  |  |  |  |  |
| 0.6                      | 1376                           | 1301  | 1085   | 917    | 259   | 1356 | 1282 | 1066   | 898  | 239                             |  |  |  |  |  |
| 0.7                      | 1332                           | 1251  | 1020   | 865    | -     | 1310 | 1228 | 998  | 842  | -                               |  |  |  |  |  |
| 2 0.8                    | 1271                           | 1179  | 969    | 813    | -     | 1246 | 1154 | 944  | 788  | -                               |  |  |  |  |  |
| 0.9                      | 1199                           | 1119  | 924    | 747    | -     | 1171 | 1091 | 897  | 719  | -                               |  |  |  |  |  |

#### NOTES:

- 1. Values are with wet coil and without filters.
- 2. Contact your particular filter manufacturer for pressure drop data.
- 3. Electric heater pressure drop is negligible and is included within the airflow data.
- 4. Tap 1 is an continuous fan speed tap.
- 5. † Factory Setting

|                              |                       |          |        | WIR            | ING DATA           |                     |          |       |                       |                    |                     |
|------------------------------|-----------------------|----------|--------|----------------|--------------------|---------------------|----------|-------|-----------------------|--------------------|---------------------|
|                              |                       |          | GAM5B0 | C42M31         | SB, GAM5B          | DC42M31EA           |          |       |                       |                    |                     |
|                              | No.<br>of<br>Circuits |          |        | 240 V          | OLT                |                     | -        |       | 208 V                 | OLT                |                     |
| Heater<br>Model<br>No.       |                       | Capacity |        | Heater<br>Amps | Minimum<br>Circuit | Maximum<br>Overload | Capacity |       | Heater<br>Amps<br>per | Minimum<br>Circuit | Maximum<br>Overload |
|                              |                       | kW       | втин   | per<br>Circuit | Ampacity           | Protection          | kW       | втин  | Circuit               | Ampacity           | Protection          |
| No Heater                    | -                     | -        | -      | 4.1*           | 5                  | 15                  | -        | -     | 4.1*                  | 5                  | 15                  |
| BAYEAAC04BK1<br>BAYEAAC04LG1 | 1                     | 3.84     | 13100  | 16.0           | 25                 | 25                  | 2.88     | 9800  | 13.8                  | 22                 | 25                  |
| BAYEAAC05BK1<br>BAYEAAC05LG1 | 1                     | 4.80     | 16400  | 20.0           | 30                 | 30                  | 3.60     | 12300 | 17.3                  | 27                 | 30                  |
| BAYEAAC08BK1<br>BAYEAAC08LG1 | 1                     | 7.68     | 26200  | 32.0           | 45                 | 45                  | 5.76     | 19700 | 27.7                  | 40                 | 40                  |
| BAYEAAC10BK1<br>BAYEAAC10LG1 | 1                     | 9.60     | 32800  | 40.0           | 55                 | 60                  | 7.20     | 24600 | 34.6                  | 48                 | 50                  |
| BAYEAAC10LG3                 | 1-3 PH                | 9.60     | 32800  | 23.1           | 33                 | 35                  | 7.20     | 24600 | 20.0                  | 30                 | 30                  |
| BAYEABC15LG3                 | 1-3 PH                | 14.40    | 49200  | 34.6           | 48                 | 50                  | 10.80    | 36900 | 30.0                  | 42                 | 45                  |
| BAYEABC15BK1 - Circuit 1 ①   | 0                     | 9.60     | 32800  | 40             | 55                 | 60                  | 7.20     | 24600 | 34.6                  | 48                 | 50                  |
| BAYEABC15BK1 - Circuit 2     | 2                     | 4.80     | 16400  | 20             | 25                 | 25                  | 3.60     | 12300 | 17.3                  | 22                 | 25                  |

#### Notes:


- 1. See Product Data or Air Handler nameplate for approved combinations of Air Handlers and Heaters
- 2. Heater model numbers may have additional suffix digits.



## **Submittal**

### **Split System Cooling**

4A7A4024L1000A



Note: "Graphics in this document are for representation only. Actual model may differ in appearance."

TAG: 4-1


#### A SAFETY WARNING

Only qualified personnel should install and service the equipment. The installation, starting up, and servicing of heating, ventilating, and air-conditioning equipment can be hazardous and requires specific knowledge and training. Improperly installed, adjusted or altered equipment by an unqualified person could result in death or serious injury. When working on the equipment, observe all precautions in the literature and on the tags, stickers, and labels that are attached to the equipment.




## American Standard.

HEATING & AIR CONDITIONING



TOP DISCHARGE AREA SHOULD BE UNRESTRICTED FOR AT LEAST 1524 (5 FEET) ABOVE UNIT SHOULD BE PLACED SO ROOF RUN-OFF WATER DOES NOT POUR DIRECTLY ON UNIT, AND SHOULD BE AT LEAST 305 (12") FROM WALL AND ALL SURROUNDING SHRUBBERT ON TWO SIDES. OTHER TWO SIDES UNRESTRICTED.



| Model     | Base | А               | В               | С               | D   | E   | F          | G             | Н              | J             | К           |
|-----------|------|-----------------|-----------------|-----------------|-----|-----|------------|---------------|----------------|---------------|-------------|
| 4A7A4024L | 2    | 730<br>(28-3/4) | 724<br>(28-1/2) | 651<br>(25-5/8) | 3/4 | 3/8 | 127<br>(5) | 57<br>(2-1/4) | 194<br>(7-5/8) | 38<br>(1-1/2) | 457<br>(18) |

|                     |                  |        | S      | DUND POW | ER LEVEL   |               |         |         |    |
|---------------------|------------------|--------|--------|----------|------------|---------------|---------|---------|----|
|                     | A-Weighted Sound |        |        |          | Full Octav | e Sound Power | [dB]    |         |    |
| Power Level [dB(A)] | 63 Hz            | 125 Hz | 250 Hz | 500 Hz   | 1000 Hz    | 2000 Hz       | 4000 Hz | 8000 Hz |    |
| 4A7A4024L           | 71               | 74     | 71     | 65       | 68         | 67            | 63      | 56      | 50 |



HEATING & AIR CONDITIONING

## **Product Specifications**

| OUTDOOR UNIT (a) (b)              | 4A7A4024L1000A     |
|-----------------------------------|--------------------|
| POWER CONNS. — V/PH/HZ (c)        | 208/230/1/60       |
| MIN. BRCH. CIR. AMPACITY          | 14                 |
| BR. CIR. PROT. RTG. — MAX. (AMPS) | 25                 |
| COMPRESSOR                        | CLIMATUFF®- SCROLL |
| NO. USED — NO. STAGES             | 1-1                |
| VOLTS/PH/HZ                       | 208/230/1/60       |
| R.L. AMPS (d) — L.R. AMPS         | 10.9 - 63          |
| FACTORY INSTALLED                 |                    |
| START COMPONENTS (e)              | YES                |
| INSULATION/SOUND BLANKET          | NO                 |
| COMPRESSOR HEAT                   | NO                 |
| OUTDOOR FAN                       | PROPELLER          |
| DIA. (IN.) — NO. USED             | 18.2 - 1           |
| TYPE DRIVE — NO. SPEEDS           | DIRECT — 1         |
| CFM @ 0.0 IN. W.G. (f)            | 2450               |
| NO. MOTORS — HP                   | 1 — 1/15           |
| MOTOR SPEED R.P.M.                | 1075               |
| VOLTS/PH/HZ                       | 200/230/1/60       |
| F.L. AMPS                         | 0.60               |
| OUTDOOR COIL — TYPE               | SPINE FIN™         |
| ROWS — F.P.I.                     | 1 — 24             |
| FACE AREA (SQ. FT.)               | 13.75              |
| TUBE SIZE (IN.)                   | 3/8                |
| REFRIGERANT                       |                    |
| LBS. — R-410A (O.D. UNIT) (9)     | 4 LBS., 11 OZ      |
| FACTORY SUPPLIED                  | YES                |
| LINE SIZE — IN. O.D. GAS (h)      | 3/4                |
| LINE SIZE — IN. O.D. LIQ.         | 3/8                |
| CHARGING SPECIFICATIONS           |                    |
| SUBCOOLING                        | 10°F               |
| DIMENSIONS                        | HXWXD              |
| CRATED (IN.)                      | 30.1 x 26.7 x 30   |
| WEIGHT                            |                    |
| SHIPPING (LBS.)                   | 153                |
| NET (LBS.)                        | 133                |

- (a) Certified in accordance with the Air-Source Unitary Air-conditioner Equipment certification program, which is based on AHRI standard 210/240
- (b) Rated in accordance with AHRI standard 270.
- (c) Calculated in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses.
- (d) This value shown for compressor RLA on the unit nameplate and on this specification sheet is used to compute minimum branch circuit ampacity and max. fuse size. The value shown is the branch circuit selection current.
- (e) No means no start components. Yes means quick start kit components. PTC means positive temperature coefficient starter. Optional kit shown.
- (f) Standard Air Dry Coil Outdoor
- $\ensuremath{^{(g)}}$  This value approximate. For more precise value see unit nameplate.
- (h) Max. linear length 60 ft.; Max. lift Suction 60 ft.; Max. lift Liquid 60 ft. For greater length consult refrigerant piping software Pub. No. 32–3312–0\* (\* denotes latest revision).



## **Mechanical Specification Options**

#### General

The Outdoor Units are fully charged from the factory for up to 15 feet of piping. This unit is designed to operate at outdoor ambient temperatures as high as 115°F. Cooling capacities are matched with a wide selection of air handlers and furnace coils that are AHRI certified. The unit is certified to UL 1995. Exterior is designed for outdoor application.

#### Casing

Unit casing is constructed of heavy gauge, galvanized steel and painted with a weather-resistant powder paint finish on all louvered panels and the fan top panel. The corner panels are prepainted. All panels are subjected to our 1,000 hour salt spray test. The base is made of a CMBP-G30 weatherproof material to resist corrosion.

#### **Refrigerant Controls**

Refrigeration system controls include condenser fan, compressor contactor and high pressure switch. High and low pressure controls are inherent to the compressor. A factory supplied liquid line drier is standard. Some models may require field installation.

#### Compressor

The compressor features internal over temperature, pressure protection and total dipped hermetic motor. Other features include: Centrifugal oil pump and low vibration and noise.

#### Condenser Coil

The outdoor coil provides low airflow resistance and efficient heat transfer. The coil is protected on all four sides by louvered panels.

#### **Low Ambient Cooling**

As manufactured, this system has a cooling capacity to 55°F. The addition of an evaporator defrost control permits operation to 40°F. The addition of an evaporator defrost control with TXV permits low ambient cooling to 30°F.

Thermostats—Cooling only and heat/cooling (manual and automatic change over). Sub-base to match thermostat and locking thermostat cover.

**Evaporator Defrost Control** — See Low Ambient Cooling.







American Standard optimizes the performance of homes and buildings around the world. A business of Ingersoll Rand, the leader in creating and sustaining safe, comfortable and energy efficient environments, American Standard offers a broad portfolio of advanced controls and HVAC systems, comprehensive building services, and parts. For more information, visit www.americanstandardair.com.

American Standard has a policy of continuous product and product data improvements and reserves the right to change design and specifications without notice.


©2015 American Standard Heating & Air Conditioning 4A7A4024L-SUB-1B-EN 20 Feb 2015 Supersedes 4A7A4024L-SUB-1A-EN (September 2014)




TAG: <u>CU-2</u>

## **SPECIFICATIONS**

#### NOTE: All dimensions are in mm/inches.





From Dwg. D152898

## 5 Ton Split System Cooling — 3 Phase 4TTA3060D

**Product Specifications** 

| POWER CONNS. — V/PH/HZ  | L    |
|---|------|
| BR. CIR. PROT. RTG MAX. (AMPS)       35       15         COMPRESSOR       SCROLL       SCROLI         NO. USED - NO. SPEEDS       1 - 1       1 - 1         VOLTS/PH/HZ       200/230/3/60       460/3/60         R.L. AMPS ② - L.R. AMPS       15.6 - 110       7.8 - 52   | )    |
| COMPRESSOR         SCROLL         SCROLL           NO. USED - NO. SPEEDS         1 - 1         1 - 1           VOLTS/PH/HZ         200/230/3/60         460/3/6/6           R.L. AMPS ② - L.R. AMPS         15.6 - 110         7.8 - 52   | )    |
| NO. USED - NO. SPEEDS       1 - 1       1 - 1         VOLTS/PH/HZ       200/230/3/60       460/3/60         R.L. AMPS ② - L.R. AMPS       15.6 - 110       7.8 - 52   | )    |
| VOLTS/PH/HZ         200/230/3/60         460/3/60           R.L. AMPS ② - L.R. AMPS         15.6 - 110         7.8 - 52   | •    |
| R.L. AMPS ② - L.R. AMPS 15.6 - 110 7.8 - 52   | •    |
|   |      |
| FACTORY INSTALLED   |      |
| Name of the state |      |
| START COMPONENTS ® NO NO  |      |
| INSULATION/SOUND BLANKET NO NO  |      |
| COMPRESSOR HEAT YES YES   |      |
| OUTDOOR FAN PROPELLER PROPELL   | ER   |
| DIA. (IN.) - NO. USED 27.6 - 1 27.6 - 1   |      |
| TYPE DRIVE - NO. SPEEDS DIRECT - 1 DIRECT -   | - 1  |
| CFM @ 0.0 IN. W.G. ④ 4320 4320  |      |
| NO. MOTORS - HP 1 - 1/5 1 - 1/5   |      |
| MOTOR SPEED R.P.M. 825 825  |      |
| VOLTS/PH/HZ 200/230/1/60 460/3/60   | )    |
| F.L. AMPS 1.2 0.6   |      |
| OUTDOOR COIL — TYPE SPINE FIN™ SPINE FIN  | JTM  |
| ROWS - F.P.I. 1 - 24 1 - 24   |      |
| FACE AREA (SQ. FT.) 24.93 24.93   |      |
| TUBE SIZE (IN.) 3/8 3/8   |      |
| REFRIGERANT   |      |
| LBS. — R-410A (O.D. UNIT) (5) 8 LBS., 0 OZ. 8 LBS., 0 (   | DZ.  |
| FACTORY SUPPLIED YES YES  |      |
| LINE SIZE - IN. O.D. GAS (6) 7/8 7/8  |      |
| LINE SIZE - IN. O.D. LIQ. (6) 3/8 3/8   |      |
| CHARGING SPECIFICATION  |      |
| SUBCOOLING 10°F 10°F  |      |
| DIMENSIONS HXWXD HXWX   | D    |
| CRATED (IN.) 42.4 x 35.1 x 38.7 42.4 x 35.1 x   | 38.7 |
| WEIGHT  |      |
| SHIPPING (LBS.) 261 261   |      |
| NET (LBS.) 226 226  |      |

Certified in accordance with the Air-Source Unitary Air-conditioner Equipment certification program, which

is based on AHRI standard 210/240. Rated in accordance with AHRI standard 270.

Ratied in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses. Calculated in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses. Standard Air. — Dry Coil — Outdoor This value approximate. For more precise value see unit nameplate. Max. linear length 60 ft., Max. lift - Suction 60 ft., Max lift - Liquid 60 ft. For greater length consult refrigerant piping software Pub. No. 32-3312-01

denotes latest revision). This value shown for compressor RLA on the unit nameplate and on this specification sheet is used to compute minimum branch circuit ampacity and max, fuse size. The value shown is the branch circuit selec-

tion current. No means no start components. Yes means quick start kit components. PTC means positive temperature coefficient starter.

| MODELS B  | BASE | FIG. | Α            | В            | С            | D   | E   | F       | G          | Н           | J          | K        |
|-----------|------|------|--------------|--------------|--------------|-----|-----|---------|------------|-------------|------------|----------|
| 4TTA3060D | 4    | 1    | 943 (37-1/8) | 946 (37-1/4) | 870 (34-1/4) | 7/8 | 3/8 | 152 (6) | 98 (3-7/8) | 219 (8-5/8) | 86 (3-3/8) | 508 (20) |

|            |                              | A-W  | VEIGHTED S | OUND POW    | ER LOVEL [ | dB(A)]    |            |             |      |
|------------|------------------------------|------|------------|-------------|------------|-----------|------------|-------------|------|
| MODELS     | SOUND POWER<br>LEVEL [dB(A)] |      | A-WEIGH    | ITED FULL ( | OCTOAVE S  | OUND POWE | R LEVEL DI | o - [dB(A)] |      |
|            |                              | 63   | 125        | 250         | 500        | 1000      | 2000       | 4000        | 8000 |
| 4TTA3060D3 | 75                           | 80   | 73         | 70          | 72         | 71        | 65         | 63          | 59   |
| 4TTA3060D4 | 80                           | 47.3 | 55.7       | 69          | 72.7       | 75.8      | 69.4       | 62.2        | 53.3 |

Note: Rated in accordance with AHRI Standard 270-2008

## Mechanical Specification Options

#### General

The 4TTA3 - D model is fully charged from the factory for up to 15 feet of piping. This unit is designed to operate at outdoor ambient temperatures as high as 115°F. Cooling capacities are matched with a wide selection of air handlers and furnace coils that are AHRI certified. The unit is certified to UL 1995. Exterior is designed for outdoor application.

#### Casing

Unit casing is constructed of heavy gauge, G90 galvanized steel and painted with a weather-resistant powder paint on all louvers, panels, prepaint on all other panels. Corrosion and weather-proof CMBP-G30 DuraBase<sup>™</sup> base.

#### Refrigerant Controls

Refrigeration system controls include condenser fan, compressor contactor and high pressure switch. High and low pressure controls are inherent to the compressor. A factory installed liquid line drier is standard.

#### Compressor

The Duration™ compressor features internal over temperature and pressure protection and total dipped hermetic motor. Other features include: roto lock suction and discharge refrigerant connections, centrifugal oil pump and low vibration and noise.

#### Condenser Coil

The outdoor coil provides low airflow resistance and efficient heat transfer. The coil is protected on all four sides by louvered panels.

#### **Low Ambient Cooling**

As manufactured, this unit has a cooling capability to 55°F. The addition of an evaporator defrost control permits operation to 40° F. The addition of an evaporator defrost control with TXV permits low ambient cooling to 30° F.

#### Accessories

Thermostats — Cooling only and heat/cooling (manual and automatic change-over). Sub-base to match thermostat and locking thermostat cover.

**Evaporator Defrost Control** — See Low Ambient Cooling.







10/12


American Standard Heating & Air Conditioning www.americanstandardair.com

The Manufacturer has a policy of continuous product and product data improvement and it reserves the right to change design and specifications without notice.


## TAG: CU-3, 7

## **SPECIFICATIONS**

#### NOTE: All dimensions are in mm/inches.



TOP DISCHARGE AREA SHOULD BE UNRESTRICTED FOR AT LEAST 1524 (5 FEET) BOOVE UNIT JUNIT SHOULD BE PLACED SO ROOF-OFF WATER DOES NOT POUR DIRECTLY ON UNIT SHOULD BE ALLESS 1302 (72") FROM WALL ALL SURBOUNDER SHOUBBERT ON 10") FIRST THO SIDES. OTHER TIMO SIDES UNRESTRICTED.



From Dwg. D152898

## 4 Ton Split System Cooling — 3 Phase 4TTA3048D

| Product Spe                    | cifications        |                    |
|--------------------------------|--------------------|--------------------|
| OUTDOOR UNIT ①②                | 4TTA3048D3000C     | 4TTA3048D4000C     |
| POWER CONNS. — V/PH/HZ 3       | 208/230/3/60       | 460/3/60           |
| MIN. BRCH. CIR. AMPACITY       | 18                 | 8                  |
| BR. CIR. PROT. RTG MAX. (AMPS) | 30                 | 15                 |
| COMPRESSOR                     | SCROLL             | SCROLL             |
| NO. USED - NO. SPEEDS          | 1 - 1              | 1 - 1              |
| VOLTS/PH/HZ                    | 200/230/3/60       | 460/3/60           |
| R.L. AMPS ⑦ - L.R. AMPS        | 13.7 - 83          | 6.2 - 41           |
| FACTORY INSTALLED              |                    |                    |
| START COMPONENTS ®             | NO                 | NO                 |
| INSULATION/SOUND BLANKET       | NO                 | NO                 |
| COMPRESSOR HEAT                | YES                | YES                |
| OUTDOOR FAN                    | PROPELLER          | PROPELLER          |
| DIA. (IN.) - NO. USED          | 27.6 - 1           | 27.6 - 1           |
| TYPE DRIVE - NO. SPEEDS        | DIRECT - 1         | DIRECT - 1         |
| CFM @ 0.0 IN. W.G. ④ -         | 3950               | 3950               |
| NO. MOTORS - HP                | 1 - 1/5            | 1 - 1/5            |
| MOTOR SPEED R.P.M.             | 825                | 825                |
| VOLTS/PH/HZ                    | 200/230/1/60       | 460/3/60           |
| F.L. AMPS                      | 1.2                | 0.6                |
| OUTDOOR COIL — TYPE            | SPINE FIN™         | SPINE FIN™         |
| ROWS - F.P.I.                  | 1 - 24             | 1 - 24             |
| FACE AREA (SQ. FT.)            | 19.07              | 19.07              |
| TUBE SIZE (IN.)                | 3/8                | 3/8                |
| REFRIGERANT                    |                    |                    |
| LBS. — R-410A (O.D. UNIT) 💿    | 6 LBS., 13 OZ.     | 6 LBS., 13 OZ.     |
| FACTORY SUPPLIED               | YES                | YES                |
| LINE SIZE - IN. O.D. GAS ®     | 7/8                | 7/8                |
| LINE SIZE - IN. O.D. LIQ. (6)  | 3/8                | 3/8                |
| CHARGING SPECIFICATION         |                    |                    |
| SUBCOOLING                     | 10°F               | 10°F               |
| DIMENSIONS                     | HXWXD              | HXWXD              |
| CRATED (IN.)                   | 34.4 x 35.1 x 38.7 | 34.4 x 35.1 x 38.7 |

Certified in accordance with the Air-Source Unitary Air-conditioner Equipment certification program, which

203

235

is based on AHRI standard 210/240. Rated in accordance with AHRI standard 270.

\* denotes latest revision).

- Added in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses. Calculated in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses. Standard Air Dry Coil Outdoor This value approximate. For more precise value see unit nameplate. Max. Ilinear length 60 ft., Max. lift Suction 60 ft., Max lift Liquid 60 ft. For greater length consult refrigerant piping software Pub. No. 32-3312-0\*
- This value shown for compressor RLA on the unit nameplate and on this specification sheet is used to compute minimum branch circuit ampacity and max. fuse size. The value shown is the branch circuit selec-
- tion current.

  No means no start components. Yes means quick start kit components. PTC means positive temperature coefficient starter.

| MODELS    | BASE | FIG. | Α            | В            | С            | D   | E   | F       | G          | Н           | J          | К        |
|-----------|------|------|--------------|--------------|--------------|-----|-----|---------|------------|-------------|------------|----------|
| 4TTA3048D | 4    | 1    | 741 (29-1/8) | 946 (37-1/4) | 870 (34-1/4) | 7/8 | 3/8 | 152 (6) | 98 (3-7/8) | 219 (8-5/8) | 86 (3-3/8) | 508 (20) |

WEIGHT SHIPPING (LBS.)

NET (LBS.)

| A-WEIGHTED SOUND POWER LOVEL [dB(A)] |                              |      |         |            |            |           |           |                      |   |
|--------------------------------------|------------------------------|------|---------|------------|------------|-----------|-----------|----------------------|---|
| MODELS                               | SOUND POWER<br>LEVEL [dB(A)] |      | A-WEIGH | TED FULL O | OCTOAVE SO | DUND POWE | R LEVEL D | o - [dB( <b>A</b> )] | *************************************** |
|                                      |                              | 63   | 125     | 250        | 500        | 1000      | 2000      | 4000                 | 8000                                    |
| 4TTA3048D3                           | 75                           | 80   | 73      | 70         | 72         | 71        | 65        | 63                   | 59                                      |
| 4TTA3048D4                           | 79                           | 47.4 | 60      | 66.9       | 75.3       | 73.5      | 70.3      | 62                   | 51.4                                    |

## **Mechanical Specification Options**

#### General

The 4TTA3 - D model is fully charged from the factory for up to 15 feet of piping. This unit is designed to operate at outdoor ambient temperatures as high as 115°F. Cooling capacities are matched with a wide selection of air handlers and furnace coils that are AHRI certified. The unit is certified to UL 1995. Exterior is designed for outdoor application.

#### Casing

Unit casing is constructed of heavy gauge, G90 galvanized steel and painted with a weather-resistant powder paint on all louvers, panels, prepaint on all other panels. Corrosion and weather-proof CMBP-G30 DuraBase™ base.

#### **Refrigerant Controls**

Refrigeration system controls include condenser fan, compressor contactor and high pressure switch. High and low pressure controls are inherent to the compressor. A factory installed liquid line drier is standard.

#### Compressor

The Duration™ compressor features internal over temperature and pressure protection and total dipped hermetic motor. Other features include: roto lock suction and discharge refrigerant connections, centrifugal oil pump and low vibration and noise.

#### Condenser Coil

The outdoor coil provides low airflow resistance and efficient heat transfer. The coil is protected on all four sides by louvered panels.

#### **Low Ambient Cooling**

As manufactured, this unit has a cooling capability to 55°F. The addition of an evaporator defrost control permits operation to 40° F. The addition of an evaporator defrost control with TXV permits low ambient cooling to 30° F.

#### Accessories

Thermostats — Cooling only and heat/cooling (manual and automatic change-over). Sub-base to match thermostat and locking thermostat cover.

**Evaporator Defrost Control** — See Low Ambient Cooling.







10/12


American Standard Heating & Air Conditioning www.americanstandardair.com

The Manufacturer has a policy of continuous product and product data improvement and it reserves the right to change design and specifications without notice.


TAG: CU-4

## **SPECIFICATIONS**

#### NOTE: All dimensions are in mm/inches.



TOP DISCHARGE AREA SHOULD BE UNRESTRICTED FOR AT LEAST 1524 (5 FEET) ABOVE UNIT, UNIT SHOULD BE PLACED SO ROOF RUN-OFF WATER DOES NOT POUR DIRECTLY ON UNIT. WAS SHOULD BE AT LEAST 3005 (12") FROW MALL AN ALL SURROUNDS SHOULDERS ON TWO SIDES.



From Dwg. D152898

## 31/2 Ton Split System Cooling — 3 Phase 4TTA3042D

**Product Specifications** 

| OUTDOOR UNIT ①②                | 4TTA3042D3000C   | 4TTA3042D4000C     |
|--------------------------------|--|--------------------|
| POWER CONNS. — V/PH/HZ ③       | 208/230/3/60   | 460/3/60           |
| MIN. BRCH. CIR. AMPACITY       | 18   | 8                  |
| BR. CIR. PROT. RTG MAX. (AMPS) | 30   | 15                 |
| COMPRESSOR                     | SCROLL   | SCROLL             |
| NO. USED - NO. SPEEDS          | 1-1  | 1-1                |
| VOLTS/PH/HZ                    | 200/230/3/60   | 460/3/60           |
| R.L. AMPS ① - L.R. AMPS        | 13.6 - 83  | 6.4 - 41           |
| FACTORY INSTALLED              |  |                    |
| START COMPONENTS ®             | NO   | NO                 |
| INSULATION/SOUND BLANKET       | NO   | NO                 |
| COMPRESSOR HEAT                | YES  | YES                |
| OUTDOOR FAN                    | PROPELLER  | PROPELLER          |
| DIA. (IN.) - NO. USED          | 27.6 - 1   | 27.6 - 1           |
| TYPE DRIVE - NO. SPEEDS        | DIRECT - 1   | DIRECT - 1         |
| CFM @ 0.0 IN. W.G. ④           | 4150   | 4150               |
| NO. MOTORS - HP                | 1 - 1/5  | 1 - 1/5            |
| MOTOR SPEED R.P.M.             | 825  | 825                |
| VOLTS/PH/HZ                    | 200/230/1/60   | 460/3/60           |
| F.L. AMPS                      | 1.2  | 0.6                |
| OUTDOOR COIL — TYPE            | SPINE FIN™   | SPINE FIN™         |
| ROWS - F.P.I.                  | 1 - 24   | 1 - 24             |
| FACE AREA (SQ. FT.)            | 19.07  | 19.07              |
| TUBE SIZE (IN.)                | 3/8  | 3/8                |
| REFRIGERANT                    |  |                    |
| LBS. — R-410A (O.D. UNIT) (5)  | 6 LBS., 2 OZ.  | 6 LBS., 2 OZ.      |
| FACTORY SUPPLIED               | YES  | YES                |
| LINE SIZE - IN. O.D. GAS 📵     | 3/4  | 3/4                |
| LINE SIZE - IN. O.D. LIQ. ®    | 3/8  | 3/8                |
| CHARGING SPECIFICATION         |  |                    |
| SUBCOOLING                     | 10°F   | 10°F               |
| DIMENSIONS                     | HXWXD  | HXWXD              |
| CRATED (IN.)                   | 34,4 x 35.1 x 38.7   | 34.4 x 35.1 x 38.7 |
| WEIGHT                         |  |                    |
| SHIPPING (LBS.)                | 228  | 228                |
| NET (LBS.)                     | 196  | 196                |
|                                | The second secon |                    |

Certified in accordance with the Air-Source Unitary Air-conditioner Equipment certification program, which

is based on AHRI standard 210/240.

Rated in accordance with AHRI standard 270.

Calculated in accordance with Natl. Elec. Codes. Use only HACR circuit breakers or fuses.

- Canodated In accordance with real, it led, course, see only involve include Standard Air. Dry Coll. Outdoor
  This value approximate, For more precise value see unit nameplate.
  Max. lingar (eight 60 ft., Max. lift. Luquid 60 ft. For greater length consult refrigerant piping software Pub. No. 32-3312-01 denotes latest revision).
- This value shown for compressor RLA on the unit nameplate and on this specification sheet is used to compute minimum branch circuit ampacity and max. fuse size. The value shown is the branch circuit selec-
- No means no start components. Yes means quick start kit components. PTC means positive temperature coefficient starter.

| MODELS    | BASE | FIG. | Α            | В            | С            | D   | Е   | F       | G          | Н           | J          | К        |
|-----------|------|------|--------------|--------------|--------------|-----|-----|---------|------------|-------------|------------|----------|
| 4TTA3042D | 4    | 1    | 741 (29-1/8) | 946 (37-1/4) | 870 (34-1/4) | 3/4 | 3/8 | 152 (6) | 98 (3-7/8) | 219 (8-5/8) | 86 (3-3/8) | 508 (20) |

| *          |                              | A-WE | IGHTED SO | UND POWE    | R LOVEL [dB | (A)]      |            |                      |      |
|------------|------------------------------|------|-----------|-------------|-------------|-----------|------------|----------------------|------|
| MODELS     | SOUND POWER<br>LEVEL [dB(A)] |      | A-WEIGH   | HTED FULL O | OCTOAVE SO  | DUND POWE | R LEVEL DI | o - [dB( <b>A</b> )] |      |
|            |                              | 63   | 125       | 250         | 500         | 1000      | 2000       | 4000                 | 8000 |
| 4TTA3042D3 | 74                           | 76   | 73        | 69          | 71          | 70 -      | 64         | 58                   | 53   |
| 4TTA3042D4 | 79                           | 47.5 | 64.5      | 67          | 75.3        | 74        | 70.7       | 62.2                 | 52.8 |

Note: Rated in accordance with AHRI Standard 270-2008

## **Mechanical Specification Options**

#### General

The 4TTA3 - D model is fully charged from the factory for up to 15 feet of piping. This unit is designed to operate at outdoor ambient temperatures as high as 115°F. Cooling capacities are matched with a wide selection of air handlers and furnace coils that are AHRI certified. The unit is certified to UL 1995. Exterior is designed for outdoor application.

#### Casing

Unit casing is constructed of heavy gauge, G90 galvanized steel and painted with a weather-resistant powder paint on all louvers, panels, prepaint on all other panels. Corrosion and weather-proof CMBP-G30 DuraBase™ base.

#### Refrigerant Controls

Refrigeration system controls include condenser fan, compressor contactor and high pressure switch. High and low pressure controls are inherent to the compressor. A factory installed liquid line drier is standard.

#### Compressor

The Duration™ compressor features internal over temperature and pressure protection and total dipped hermetic motor. Other features include: roto lock suction and discharge refrigerant connections, centrifugal oil pump and low vibration and noise.

#### Condenser Coil

The outdoor coil provides low airflow resistance and efficient heat transfer. The coil is protected on all four sides by louvered panels.

#### **Low Ambient Cooling**

As manufactured, this unit has a cooling capability to 55°F. The addition of an evaporator defrost control permits operation to 40° F. The addition of an evaporator defrost control with TXV permits low ambient cooling to 30° F.

#### Accessories

Thermostats — Cooling only and heat/cooling (manual and automatic change-over). Sub-base to match thermostat and locking thermostat cover.

**Evaporator Defrost Control** — See Low Ambient Cooling.







10/12

American Standard Heating & Air Conditioning www.americanstandardair.com

The Manufacturer has a policy of continuous product and product data improvement and it reserves the right to change design and specifications without notice.

## American Standard.

### Non-Programmable **Comfort Controls**



ACONT402A

#### ACONT402AN32DA

Auto Changeover Backlit Display & Keys Comfort Information Compar™ent **Energy Savings Mode** Filter Reminder BAYSEN01ATEMPAA-Outdoor Temperature Sensor included\* Keypad Lock

Application (3-9 Wire Hookup -2 for Outdoor Sensor) Heat Pump\* or A/C 3 Heat/2 Cool

No external Dual Fuel Kit Required Do not use with TAYPLUS103A ZZSENSAL0400AA - Remote Indoor Temperature Sensor

#### ACONT401AN21MA

Auto Changeover Backlit Display & Keys Comfort Information Compar™ent **Energy Savings Mode** Filter Reminder Outdoor Temperature Sensor Keypad Lock

Application (3-9 Wire Hookup -2 for Outdoor Sensor) Heat Pump\* or A/C

- 1 Stage Heat Pump\*\*, 1 Stage Aux Heat
- 1 Stage Heat Pump\*\*, 0 Stage Aux Heat
- 1 Stage Cool, 2 Stage Heat (Gas, Electric or Oil\*)
- 1 Stage Cool, 1 Stage Heat (Gas, Electric or Oil\*)

#### Dimensions:

6.75" w x 4.52" h x 1.20" d Finish: Bright White

- \* Requires external relay for oil furnace applications.
- Installation is required for outdoor temperature sensing and display



ACONT401A

- 1 Stage Cool, 0 Stage Heat
- 0 Stage Cool, 2 Stage Heat (Gas, Electric or Oil\*)
- 0 Stage Cool, 1 Stage Heat (Gas, Electric or Oil\*)

#### **Dimensions:**

6.75" w x 4.52" h x 1.20" d Finish: Bright White

- Requires external relay for oil furnace applications.
- \*\* External TAYPLUS103A required for dual fuel applications. BAYSEN01ATEMPA required for outdoor temperature sensing and display



ACONT200A

#### ACONT200AN11AA

Auto Changeover Backlit Display & Keys Comfort Information Compar™ent **Energy Savings Mode** Filter Reminder Key Pad Lock

Application (4 wire hookup - power stealing)\*

- 1 Heat/1 Cool (Gas, Oil or electric)
- 1 Heat/0 Cool (Gas, Oil or electric)
- 0 Heat/1 Cool

Finish: Bright White

#### **Dimensions:**

4.25" w x 5.33" h x 1.20" d

① Power Stealing 4 Wire - Resistor Terminal in Box. 4 - wire system to supply power with heating mode; both resistors must be installed for proper operation.




#### COOLING & HEATING

## P-SERIES

| SUBMITTAL DATA: PKA-A1:<br>12,000 BTU/H WALL-MOUNTE | 2HA4 & PUY-A12NHA4 (<br>d air-conditioning system | -BS)                   |
|---|---|------------------------|
| Job Name: Home 2 Suites                             | Location: Flowood                                 | Date: 12/9/16          |
| Purchaser:  | Engineer: Innovative Engi                         | neering                |
| Submitted to: SHS Devlopment                        | For □Reference ■A                                 | oproval   Construction |
| System Designation: AHU ,CU -5 & 6                  | Schedule No.:                                     |                        |



Indoor Unit: PKA-A12HA4



Outdoor Unit: PHY-A12NHA4 (-RS)

#### **GENERAL FEATURES**

- Wall-mounted indoor unit for residential and commercial applications
   Shiny-white—exterior plastic; compact design
- Quiet operation—both indoor and outdoor units
   Self-check function—integrated diagnostics
- Limited warranty: five years parts and seven years compressors

#### **UNIT OPTION**

- □ Standard Model.....PUY-A12NHA4
- □ Sea Coast (BS) Model.....PUY-A12NHA4-BS

#### **ACCESSORIES**

- ☐ Mini Condensate Pump (SI3100-230, 230V)
   ☐ L-Connector Pipe (PAC-SC84PI; for left side unit piping installation)

#### **Outdoor Unit**

- Drain Pan (PAC-SG63DP)
- Drain Socket (PAC-SG61DS)
- Three-pole Disconnect Switch (TAZ-MS303)

- Wind Baffle (WB-PA1)
  Air Outlet Guide (PAC-SG58SG)
  Mounting Base (DSD-400N)
  Mounting Pad (ULTRILITE1)
  Wall-mounting Brackets (CWMB1)

#### **Controller Options**

- Wireless Wall-mounted Remote Controller Kit (MHK1)\*\*
- Portable Central Controller (MCCH1)\*
- Outdoor Air Sensor (MOS1)
- Wired Wall-mounted Controller (PAR-31MAA)\*\*
- Simple MA Remote Controller (PAC-YT53CRAU)\*\*

### \*\*See Submittal for information on each option. M-NET Adapter (PAC-SF81MA)

- M-NE I Adapter (PAC-SF81MA)
   CN51 Connector for Multiple Remote Controller Adapters/Duct Fan Controller (PAC-725AD)
   CN32 Connector for Remote On/Off (PAC-715AD)
   Remote Temperature Sensor (PAC-SE41TS)
   Remote Operation Adapter Display and On/Off (PAC-SF40RM)
   Hand-held Wireless Remote Controller (PAR-FL32MA; req. PAR-FA32MA-E)
   Wireless Signal Receiver Module (PAR-FA32MA-E)
   Lockdown Bracket for Hand-held Controller (RCMKP1CB)
   Control/Service Tool (PAC-SK52ST)

- □ Control/Service Tool (PAC-SK52ST)

#### SEACOAST PROTECTION

- External Outer Panel: Phosphate coating + Acrylic-Enamel coating
- Fan Motor Support: Epoxy resin coating (at edge face)
- Separator Assembly; Valve Bed: Epoxy resin coating (at edge face)
   Screws (used outer side): Zinc nickel coating 5µm + Polyvinylidene chloride coating

"Blue Fin" treatment is an anti-corrosion treatment that is applied to the condenser coil to protect it against airborne contaminants.



## SPECIFICATIONS: PKA-A12HA4 & PUY-A12NHA4 (-BS)

| Cooling*                   |
|----------------------------|
| Rated Capacity12,000 Btu/h |
| Minimum Capacity           |
| SEER                       |
| EER 10.1 Btu/h/W           |
| Total Input                |

\* Rating Conditions per AHRI Standard Cooling | Indoor: 80° F (27° C) DB / 67° F (19° C) WB Cooling | Outdoor: 95° F (35° C) DB / 75° F (24° C) WB

Electrical Requirements

#### **OPERATING CONDITIONS**

| -       |         | Indoor Intake Air<br>Temp.           | Outdoor Intake Air<br>Temp. |
|---------|---------|--------------------------------------|-----------------------------|
| Cooling | Maximum | 95° F (35° C) DB<br>71° F (22° C) WB | 115° F (46° C) DB           |
| Cooling | Minimum | 67° F (19° C) DB<br>57° F (14° C) WB | 0° F** (-18° C) DB          |

 $<sup>^{**}</sup>$  With optional wind baffle accessory installed. If not installed, the minimum temperature will be 23° F (-5° C) DB.

| Indoor Unit                          |
|--------------------------------------|
| MCA                                  |
| Blower Motor (ECM)                   |
| Blower Motor Output                  |
| Airflow (Lo - Mid - Hi)              |
| 290 - 335 - 380 Wet CFM              |
| Air Filter Polypropylene Honeycomb   |
| Sound Pressure Level (Lo - Mid - Hi) |
| SHF 0.81                             |
| Moisture Removal                     |

| DIMENSIONS | UNIT INCHES / MM |
|------------|------------------|
| W          | 35-3/8 / 898     |
| D          | 9-13/16 / 249    |
| H          | 11-5/8 / 295     |

| Weight                                     |
|--|
| External Finish Munsell No. 1.0Y 9.2 / 0.2 |
| Field Drainpipe Size O.D                   |

#### **Outdoor Unit**


| Odtago: Oilit        |         |    |                             |
|----------------------|---------|----|-----------------------------|
| Compressor           |         | DC | Inverter-driven Twin Rotary |
| MCA                  | 141 413 |    |                             |
| MOCP                 |         |    | 15 A                        |
| Fan Motor (ECM)      |         |    |                             |
| Sound Pressure Level |         |    |                             |
| Cooling , . ,        |         |    | 46 dB(A)                    |

| DIMENSIONS | INCHES / MM               |
|------------|---------------------------|
| W          | 31-1/2 / 800              |
| D          | 11-13/16 + 7/8 / 300 + 23 |
| H          | 23-5/8 / 600              |

| Weight  |
|---|
| Refrigerant Type                                    |
| Refrigerant Pipe Size O.D.                          |
| Gas Side  |
| Liquid Side   |
| Max. Refrigerant Pipe Length 100' / 30 m            |
| Max. Refrigerant Pipe Height Difference 100' / 30 m |
| Connection Method Flared                            |


Notes:

### **DIMENSIONS: PKA-A12HA4**




Specifications are subject to change without notice. © 2013 Mitsubishi Electric US. Inc.

## **DIMENSIONS: PUY-A12NHA4 (-BS)**



#### Clearance space around the outdoor unit




2 sides should be open in the right, left and rear side.

Min.100mm<3-15/16>

#### **FOUNDATION BOLTS**

Please secure the unit firmly with 4 foundation M10<W3/8> bolts. (Bolts, washers and nut must be purchased locally.)



#### PIPING-WIRING DIRECTION

Piping and wiring connection can be made from the rear direction only.

#### Minimum installation space for outdoor unit

- \*1 In the place where short cycle tends to occur, cooling and heating capacity and power consumption might get lowered 10%. Air outlet guide (optional) will help them improve.
- \*2 If air discharges to the wall, the surface might get stained.









COOLING & HEATING

- Live Better

1340 Satellite Boulevard Suwanee, GA 30024 Tele: 678-376-2900 • Fax: 800-889-9904 Toll Free: 800-433-4822 www.mehvac.com



## SUBMITTAL

Job Title:

**Home2 Suites by Hilton** 

Location:

Flowood, MS

Contractor:

Comfort Designs

Date:

December 9, 2016

Submitted By: Rob Thomas

GORHAM/SCHAFFLER, INC.

115A Lone Wolf Drive Madison, MS 39110

Phone: (601) 405-9775

www.gorhamschaffler.com



Estimated lead time for curbs is 3 weeks, and 8 weeks for equipment, from receipt of approved submittals.





#### Equipment selection based on 208/3 electrical service and natural gas heating source

#### **100% OSA HEATING & COOLING UNITS**

Manufacturer:

AAON, INC.

Model:

Series RN

Tag:

MAU-1 & 2

Description:

Unit is designed specifically for 100% outside air rooftop applications with weatherproof cabinet, dual circuit refrigeration system, modulating natural gas heating system, total operating and safety controls. Unit is completely factory assembled, piped, tested, internally wired and shipped as a single package. Unit is certified in accordance with UL Standard UL465, and ANSI Standard Z21.47. Units are ETL labeled.

The hinged access panels have 1/4 turn latches. All airside roof and wall casing shall include 2-inch thick rigid, closed cell polyurethane foam double wall construction with an R-value of 13. Finish of corrosion resistant, two par polyurethane, heat dried paint.

Supply fan shall be direct drive, single width inlet, un-housed airfoil centrifugal plenum fan. Motor bearings shall be rated for 200,000 hours service and shall have external lubrication lines. Fan(s) and motor(s) shall be dynamically balanced, and the entire fan assembly mounted on rubber isolators.

Unit has two independent refrigeration circuits. Compressors are fully hermetic type equipped with internal overload protection, mounted with suitable vibration isolators and carry a 5 year parts warranty. Condenser fans shall be high efficiency electronically commutated motor driven with factory installed head pressure control module. Condenser airflow shall continuously modulate based on head pressure. Propeller fans are top discharge, aluminum blades with zinc plated steel hubs. Refrigeration piping includes thermostatic expansion valve, liquid line filter drier, service ports, manual reset high-pressure switch and low-pressure switch.

Hot gas bypass is provided on all circuits. In addition, heat reclaim coil is provided with a modulating refrigerant control valve for leaving air humidity control.

Coils are aluminum plate rippled fin, mechanically bonded to heavy wall seamless copper rifled tubes. Evaporator coil is interlaced to assure all air is conditioned when only one circuit in operation.

The unit filters are 4" pleated type with 2" pleated pre-filters and easily accessible through removable panels.

Heat exchanger is indirect fired, tubular type with .120 wall stainless steel construction. Combustion system includes induced draft combustion blower with electric pressure switch. Control system is 100% safe with electronic spark ignition with pilot relight and





flame sensor. Controls include main gas solenoid with manual shutoff valve and integral pressure regulator, combination fan and limit control, and proven airflow switch. Gas furnace system is modulating control and approved for outdoor application. Heat exchanger has 25-year non-prorated warranty.

Outside air hood is bottom inlet with mesh grille eliminating the possibility of rain or large foreign objects from being drawn into the outside air opening.

The unit manufacturer supplies all controls for the complete operation of the rooftop unit.

#### **OPTIONAL ACCESSORIES INCLUDE:**

- 1. 100% OSA hood with birdscreen
- 2. Programmable controller
- 3. Stainless steel heat exchanger
- 4. 10:1 turndown furnace control
- 5. Hot gas bypass all circuits
- 6. Heat reclaim coil with modulating valve
- 7. Stainless steel drain pan
- 8. Sight glass
- 9. Double wall construction
- 10. ECM condenser fans for head pressure control
- 11. Non-fused disconnect
- 12. MERV 8 pre-filters
- 13. MERV 12 unit filters
- 14. Phase protection

#### SHIPPED LOOSE

- 1. OE212 room sensors
- 2. Plenum roof curbs with vibration isolation rails
- 3. Programming tool

#### **IMPORTANT NOTES:**

- Required roof curb height is dependent upon actual roofing insulation thickness and minimum clearance requirements. Supply openings in side of plenum curb to be field cut. Factory openings are available with contractor provided detail of opening locations and sizes. Curb drawings are for dimensional reference only. Curb height will be coordinated with contractor and a formal curb/isolation rails submittal will be provided for approval prior to curb release.
- 2. Cut roof curb discharge opening in field as required matching discharge duct. Locate unit so that outside air intake is 10' from nearest exhaust fan. <a href="Exterior of curb at base">Exterior of curb at base</a> flange must be mopped in with roofing compound or sealant to form airtight seal.
- 3. Check blower RPM and adjust as required to RPM shown in submittal schedule. Additional balancing may be required depending on actual external static pressure.
- 4. Supply air temperature sensor (located in RTU controls cabinet) must be field installed in supply ductwork a minimum of 12 feet downstream of unit discharge. Wire must be run in watertight conduit external to the unit/duct.





- 5. Field install space temperature sensors on top floor using 18 AWG plenum rated, 3 insulated conductor wire with a shield and drain, for each sensor, to the location specified by others. All sensor wires run from the RTU should be installed properly. Please keep all control wires at least 18 inches from Light Ballasts, High Voltage wires and conduit to prevent interference.
- 6. Contractor to confirm equipment heating source and voltage prior to ordering or submittal is assumed correct.



2672 / 2672 lbs. (±5%) 3200 / 1.5 in. wg.

°F WB

153.60 fpm / 6

153.60 fpm / 6

2.17 in. wg.

3200



2425 South Yukon Ave - Tulsa, Oklahoma74107-2728- Ph. (918) 583-2266 Fax (918) 583-6094AAONEcat32 Ver. 4.247 (SN: 7126944-6D3F6439)

RN-020-8-0-BA02-349:M000-U00-DQQ-AF0-0JKBHBF-00-000000AX Tag: MUA-1,2

(Values do not account for changes described in SPA) Job Information

| Job Name:      | Flowood MS Home2 Suites |
|----------------|-------------------------|
| Job Number:    | Flowood MS Home2 Suites |
| Site Altitude: | 0 ft                    |
| Refrigerant    | R-410 $A$               |

#### Static Pressure

| External:      | 1.50 in. wg. |
|----------------|--------------|
| Evaporator:    | 0.12 in. wg. |
| Filters Clean: | 0.10 in. wg. |
| Dirt Allowance | 0.35 in. wg  |

#### Cooling Section

|                           | Gross               | Net         |
|---------------------------|---------------------|-------------|
| Total Capacity:           | 255.82              | 250.61 MBH  |
| Sensible Capacity:        | 95.66               | 90.45~MBH   |
| Latent Capacity:          | 160.16 MBH          |             |
| Mixed Air Temp:           | 83.50 °F DB         | 78.70 °F WB |
| Entering Air Temp:        | 83.50 °F DB         | 78.70 °F WB |
| Lv Air Temp (Coil):       | 55.11 °F DB         | 54.91 °F WB |
| Lv Air Temp (Unit)        | 56.58 °F DB         | 55.50 °F WB |
| Supply Air Fan:           | 1 x 270D60 @ 1.81   | BHP         |
| SA Fan RPM / Width:       | 1009 / 3.091"       |             |
| Evaporator Coil:          | 19.9 ft² / 4 Rows / | 14 FPI      |
| Evaporator Face Velocity: | 161.1  fpm          |             |

#### Rating Information

| Cooling Capacity (MBH):               | 230.0 |
|---------------------------------------|-------|
| Cooling EER:                          | 12    |
| Cooling IEER:                         | 13.8  |
| Rated in accordance with AHRI 240/260 |       |

| Application EER @ Op. Conditions: 1 | 4. |
|-------------------------------------|----|
|-------------------------------------|----|

#### Electrical Data

| Rating:<br>Unit FLA: | 208/3/60<br>85 |      |     | Minimum Circuit Amp: 92 Maximum Overcurrent: 110 |      |      |      |      |
|----------------------|----------------|------|-----|--|------|------|------|------|
|                      | Qty            | HP   | VAC | Phase  | RPM  | FLA  | RLA  |      |
| Compressor 1:        | 2              |      | 208 | 3  |      |      | 30.1 |      |
| Condenser Fans:      | 2              | 1.00 | 208 | 1  | 1110 | 7.0  |      |      |
| Supply Fan:          | 1              | 3.00 | 208 | 3  | 1170 | 10.6 |      |      |
| Combustion:          | 1              | 0.25 | 208 | 1  | 3210 | 1.7  |      |      |
| Cabinet Sound Powe   | er Levels*     |      |     |  |      |      |      |      |
| Octave Bands:        | 63             | 125  | 250 | 500  | 1000 | 2000 | 4000 | 8000 |
| Discharge LW(dB):    | 84             | 84   | 84  | 81   | 77   | 82   | 79   | 75   |
| Return LW(dB):       | 74             | 70   | 67  | 62   | 63   | 59   | 47   | 41   |

<sup>\*</sup>Sound power levels are given for informational purposes only. The sound levels are not guaranteed.

#### Unit Information \*\*WEIGHT AND PERFORMANCE DO NOT INCLUDE SPA

| Ambient Temperature: | 83.5 °F DB / 78.7 |  |  |  |
|----------------------|-------------------|--|--|--|
| Economizer:          | 0.00 in. wg.      |  |  |  |
| Heating:             | 0.07 in. wg.      |  |  |  |
| Cabinet:             | 0.01 in. wg.      |  |  |  |
| Re-Heat Coil:        | 0.01 in. wg.      |  |  |  |

| Loual.  |         |  |
|---------|---------|--|
| Heating | Section |  |

Approx. Op./Ship Weights:

Supply CFM/ESP: Pre-Filter FV / Qty:

Outside CFM:

Total.

Final Filter FV / Qty:

| PreHeat Type:      | Std (No Preheat)        |
|--------------------|-------------------------|
| Heating Type:      | Nat. Gas Heat           |
| Heating CFM:       | 3200                    |
| Total Capacity:    | 218.7MBH                |
| OA Temp:           | 17.1 °F DB / 16.0 °F WB |
| RA Temp:           | 75.0 °F DB / 62.0 °F WB |
| Entering Air Temp: | 17.1 °F DB / 16.0 °F WB |
| Leaving Air Temp:  | 80.3 °F DB / 51.4 °F WB |
| Input:             | 270.0~MBH               |
| Heater Qty:        | 1                       |
| Consumption:       | 270.0~MBH               |
|                    |                         |

#### Re-Heat Coil:

| Capacity:   | 58 MBH              |
|-------------|---------------------|
| LA DB / WB: | 72.00 °F / 61.30 °F |
| RH:         | 55%                 |



### **Unit Submittal**

2425 South Yukon Ave - Tulsa, Oklahoma 74107-2728 - Ph. (918) 583-2266 Fax (918) 583-6094
AAONEcat32 Ver. 4.247 (SN: 7126944-6D3F6439)

RN-020-8-0-BA02-349: M000-U00-DQQ-AF0-0JKBHBF-00-000000AX
Tag: MUA-1,2

Job Name: Job Number: Flowood MS Home2 Suites Flowood MS Home2 Suites Unit Submittal For: Unit Submittal Date:


 $February\ 16,\ 2016$ 


|     | Base Option               | Description                          |
|-----|---------------------------|--------------------------------------|
| R   | Series                    | Roof Top Unit                        |
| N   | Generation                | Ninth Generation                     |
| 020 | Unit Size                 | Twenty                               |
| 8   | Voltage                   | 208V/3Ø/60Hz                         |
| 0   | Interior Protection       | Standard                             |
| В   | Refrigerant Style         | R-410A                               |
| A   | Unit Configuration        | Air-Cooled Cond. + Std Evap. Coil    |
| 0   | Coil Coating              | Standard                             |
| 2   | Cooling/Heat Pump Staging | 2 Stage                              |
| 3   | Heating Type              | Natural Gas Stainless Steel          |
| 4   | Heating Designation       | Heat 4 - 270 MBtuh                   |
| 9   | Heating Staging           | Modulating Gas - Temperature Control |

|   | Feature Option                 | Description   |
|---|--------------------------------|---|
| M | 1A. RA/OA Section              | Motorized 100% Outside Air Dampers - No RA Opening                        |
| 0 | 1B. RA/EA Blower Configuration | Standard - None   |
| 0 | 1C. RA/EA Blower               | Standard - None   |
| 0 | 1D. RA/EA Blower Motor         | Standard - None   |
| U | 2. OA Control                  | 2 Position Actuator   |
| 0 | 3. Heat Options                | Standard  |
| 0 | 4. Maintenance Options         | Standard  |
| D | 5A. SA Blower Configuration    | 1 Blower + Premium Efficiency Motor + 1 VFD                               |
| Q | 5B. SA Blower                  | 27" Direct Drive Backward Curved Plenum - 60% Width                       |
| Q | 5C. SA Motor                   | 3.0 hp - 1170 rpm   |
| A | 6A. Pre Filter Type            | 2" Pleated Pre Filter - MERV 8  |
| F | 6B. Unit Filter Type           | 4" Pleated - MERV 12  |
| 0 | 6C. Filter Options             | Standard  |
| 0 | 7. Refrigeration Control       | Standard - Fixed 55°F Comp. Cooling Lock Out                              |
| J | 8. Refrigeration Options       | HGB Lead + HGB Lag + MHGR   |
| K | 9. Refrigeration Accessories   | ECM Condenser Fan - Head Pressure Control + Sight Glass                   |
| В | 10. Power Options              | Non-fused Disconnect Power Switch - 150 Amps                              |
| Н | 11. Safety Options             | Remote Safety Shutdown Terminals  |
| В | 12. Controls                   | Phase & Brown Out Protection  |
| F | 13. Special Controls           | Make Up Air Unit Controller - CV Cool + CV Heat                           |
| 0 | 14A. Preheat Configuration     | Standard - None   |
| 0 | 14B. Preheat Sizing            | Standard - None   |
| 0 | 15. Glycol Percent             | Water or No WSHP  |
| 0 | 16. Interior Cabinet Options   | Standard - Double Wall + R-13 Foam Insulation + Stainless Steel Drain Pan |
| 0 | 17. Exterior Cabinet Options   | Standard  |
| 0 | 18. Customer Code              | Standard  |
| 0 | 19. Code Options               | Standard - ETL U.S.A. Listing   |
| 0 | 20. Crating                    | Standard  |
| 0 | 21. Water-Cooled Cond.         | Standard - None   |
| A | 22. Control Vendors            | WattMaster VCM-X Controls   |
| X | 23. Type                       | Special Price Authorization + AAON Gray Paint                             |

## RN SERIES C - CABINET STANDARD ~ 16-30 TON

| CLEARANCES                   |  |  |
|------------------------------|--|--|
| • UNIT SIZE •<br>16 - 30 TON |  |  |
| 48                           |  |  |
| 48                           |  |  |
| 6                            |  |  |
| 60                           |  |  |
| UNOBSTRUCTED                 |  |  |
|                              |  |  |






#### NUMBER OF CONDENSER FANS

16,18 & 20 TON -

2 FANS

25 & 30 TON


3 FANS




**DETAIL C** 

## 


#### FRONT VIEW





BY MANUFACTURER FOR DRAIN

CONNECTION.



# **Duct Temperature Sensors** OE230 (6" Probe) & OE231 (12" Probe)


### Caution!

The Duct Sensor Is Used For Sensing Supply Or Return Air Temperatures. Location Of The Sensors Is Very Important In Order To Obtain Accurate Temperature Readings. The Following Recommendations Should Be Followed:

Supply Air When Used As A Supply Air Sensor The Sensor Should Be Mounted In The Supply Air Duct As Close To The HVAC Unit As Possible And Upstream Of The Bypass Damper (If Used) For Best Results. For Best Accuracy, Apply Insulation On The Outside Of The Ductwork Over The Sensor. This Will Help Thermal Gradients From Affecting The Sensor.

Return Air When Used As A Return Air Sensor The Sensor Should Be Mounted In The Return Air Duct As Close To The HVAC Unit As Possible And Upstream Of The Bypass Damper (If Used) For Best Results. For Best Accuracy, Apply Insulation On The Outside Of The Ductwork Over The Sensor, This Will Help Thermal Gradients From Affecting The Sensor.

See The Systems Installation And Operation Manual For Other Design Considerations And Recommendations Regarding Duct Temperature Sensor Location.



|      | Temperature Sensor Resistance/Voltage Chart |      |             |          |      |             |          |      |             |          |
|------|---|------|-------------|----------|------|-------------|----------|------|-------------|----------|
| Temp | Resistance* Voltage                         | Temp | Resistance* | Voltage  | Temp | Resistance* | Voltage  | Temp | Resistance* | Voltage  |
| o F  | Ohms @ Input*                               | ۰F   |             | @ Input* | ۰F   | Ohms        | @ Input* | e F  | Ohms        | @ Input* |
| -10  | 933334.620                                  | 45   | 21094       | 3.470    | 69   | 11906       | 2.780    | 84   | 8514        | 2.352    |
|      | 4.550                                       | 50   | 18655       | 3.330    | 70   | 11652       | 2.752    | 86   | 8153        | 2.297    |
| 0    | 698224.474                                  | 52   | 17799       | 3.275    | 71   | 11379       | 2.722    | 88   | 7805        | 2.242    |
| 5    | 605524,390                                  | 54   | 16956       | 3.217    | 72   | 11136       | 2.695    | 90   | 7472        | 2.187    |
| 10   | 525004.297                                  | 56   | 16164       | 3.160    | 73   | 10878       | 2.665    | 95   | 6716        | 2.055    |
|      | 459024.200                                  | 58   | 15385       | 3.100    | 74   | 10625       | 2.635    | 100  | 6047        | 1.927    |
| 20   | 401474.095                                  | 60   | 14681       | 3.042    | 75   | 10398       | 2.607    | 105  | 5453        | 1.805    |
| 25   | 351653.982                                  | 62   | 14014       | 2.985    | 76   | 10158       | 2.570    | 110  | 4923        | 1.687    |
| 30   | 308053.862                                  | 64   | 13382       | 2.927    | 78   | 9711        | 2.520    | 115  | 4449        | 1.575    |
| 35   | 271403.737                                  | 66   | 12758       | 2.867    | 80   | 9302        | 2.465    | 120  | 4030        | 1.469    |
| 40   | 3.605                                       | 68   | 12191       | 2.810    | 82   | 8893        | 2.407    | 125  | 3656        | 1.369    |
|      |   |      |             |          |      |             |          |      |             |          |

- 1. Use the resistance column to check the thermistor sensor while disconnected from the controllers (not powered).
- 2. Use the voltage column to check sensors while connected to powered controllers. Read voltage with meter set on DC volts. Place the "-"(minus) lead on GND terminal and the "+"(plus) lead on the sensor input terminal being investigated. If the voltage is above 5.08 VDC, the sensor or wiring is "open." If the voltage is less than 0.05 VDC, the sensor or wiring is shorted.

#### Notes:

1.)All Wiring To Be In Accordance With Local And National Electrical Codes And Specifications.

| r    | I/D MANAC         |                    |  |  |  |  |  |  |  |  |
|------|-------------------|--------------------|--|--|--|--|--|--|--|--|
|      | JOB NAME          |                    |  |  |  |  |  |  |  |  |
|      |                   |                    |  |  |  |  |  |  |  |  |
|      | FILENAME          |                    |  |  |  |  |  |  |  |  |
| G-DU | ICSENS1.CDR       |                    |  |  |  |  |  |  |  |  |
| DA   | TE: 04/25/02      | DRAWN BY: B. CREWS |  |  |  |  |  |  |  |  |
| PAGE | PAGE DESCRIPTION: |                    |  |  |  |  |  |  |  |  |
|      | OE230 & OE231     |                    |  |  |  |  |  |  |  |  |
|      | Duct Te           | mperature Sensor   |  |  |  |  |  |  |  |  |



# OE210, 211, 212 & 213 Standard Room Sensors

## **Description**

The patented design, OE21x series Standard Room Sensor provides accurate sensing of the room temperature. Its design allows for flush wall mounting yet rejects the influence of surface and internal wall temperatures. The Standard Room Sensor is used in conjunction with the Orion VAV/CAV controller or the MUA II controller. Wire terminals are provided on the sensor for connection to the controllers. The Standard Room Sensor cannot be used for connection to the VAV/Zone controller. For this application the Modular Room Sensor must be used. Please see the Orion Modular Room Sensor submittal sheet for information.

Sensors provided with the setpoint adjustment option can be programmed to allow a temperature range adjustment of  $\pm$  6° F from their standard setpoint. Sensors provided with the pushbutton override option can be programmed to provide a timed override duration of up to 8.0 hours.

The Room Sensor's attractive styling and off white casing color make it suitable for most building decors. If interior decoration requires, the Room Sensor casing can also be painted or wall papered without affecting the sensor's performance. Room Sensors are available in 4 different configurations:

- OE210 Sensor Plain
- OE211 Sensor with Override
- OE212 Sensor with Setpoint Adjustment
- OE213 Sensor with Setpoint Adjustment and Override

2.75°

0.88°


2.00°


Wall Cut-Out Dimensions When Sensor Is To Be Mounted Without Handy Box (By Others)

Modular cable from the VAV/Zone Controller to the Modular Room Sensor should not be run in conduit with other AC line voltage wiring, or with any conductors carrying highly inductive loads.

## Mounting

The Room Sensors are designed to be mounted on a vertical, 2" x 4" electrical box recessed in the wall. If the wall cannot be penetrated, a plastic surface mount box such as those made by Wiremold<sup>TM</sup>, may be used to mount the sensor to the wall surface.







OE212

Room Sensor


With Setpoint Adjust

Room Sensor With Setpoint Adjust & Overide

| Technical Data  |  | OE210, OE211, OE212, OE213 Standard Room Senso                        |   |  |  |
|-----------------|--|---|---|--|--|
| Sensor Element  | Type III Thermistor<br>10k ohm @ 77° F | Mounting  | Designed to be Flush Mounted to Wall using Vertical 2" x 4" Handy Box (by others) |  |  |
| Accuracy        | ±0.4° F between 40° F to 95° F         | Line Loss   | 0.25° F max. error, using 22 AWG wire at 1000 ft                                  |  |  |
| Range           | -30° F to 150° F                       | Weight  | 4 oz.   |  |  |
| 3 Year Warranty |  | WattMaster reserves the right to change specifications without notice |   |  |  |



Either The Slide Offset Option For The Space Temperature Sensor Or The Remote Supply Others) May Be Connected To An AI7 On The VCM-X Controller. Only One Option Is Air Temperature Reset Signal Option (By Allowed, Not Both.



VCM-X Controller




# OE391-12 Modular Service Tool SD

# Description

The OE391-12 Modular Service Tool SD is a system interface that provides a direct link to enable the system operator to view the status, configure, and adjust the setpoints of the following Orion controllers:

- VCM-X Series Controller
- VCM-X E-BUS Series Controller
- RNE Controller
- VCB-X Controller
- SA E-BUS Controller
- VCM Controller
- VAV/CAV Controller
- MUA II Controller
- VAV/Zone Controller
- MiniLink PD

The OE391-12 Modular Service Tool SD is housed in a black plastic enclosure. The display area is covered with a clear plastic bezel for protection of the display screen. The Modular Service Tool SD has a four line by 20 character display panel with adjustable contrast control and a 27 key membrane keypad for data selection and entry. All keypad operations are simple and straight forward, utilizing non-cryptic plain English language messages. Menudriven programming allows for easy setup and operation without the need for specialized training. The OE391-12 Modular Service Tool SD is supplied with a programmable 4 Gigabyte SD memory card, with (4) AA 1.5 V batteries, a wall



mount a DC power supply, a mini-Din communication cable, and an E-BUS communication cable. The mini-Din cable allows you to connect the Modular Service Tool to any Orion controller which has a mini-Din connector socket for programming, monitoring, and troubleshooting purposes.

The Modular Service Tool is also equipped with an EBC E-BUS port and an RS-485 three conductor terminal block port. The E-BUS port and included E-BUS cable are used for updating E-BUS Module software. The RS-485 port is used for hard-wiring to older controllers that do not have a mini-DIN connector socket.

The Modular Service Tool SD is designed to be carried by the system installer or service technician. Its rugged plastic housing provides superior protection for the electronic components housed inside. The Modular Service Tool SD is a top quality service tool that will stand up to the demands of the typical job site for many years.

| Technical Data        |                                     |                    | OE391-12 Modular Service Tool SD                         |
|-----------------------|-------------------------------------|--------------------|--|
| Power                 | (4) AA (1.5V) Batteries<br>Supplied | Display            | 4 Line by 20 Character                                   |
| Power Switch          | Membrane Switch                     | Network Connection | RS-485   |
| Operating Temp        | 10°F to 149°F                       | Protocol           | HSI Open Protocol Token Passing                          |
| Operating<br>Humidity | 90% RH Non-Condensing               | Color              | Black  |
| Keypad                | 27 Key Membrane Style               | Communications     | RS-485 9600 or 57,600 Baud                               |
| SD Memory Card        | Programmable 4 Gigabyte             | Connections        | RS-485 and EBC E-BUS Ports                               |
| 3 Year Warranty       |                                     | WattMaster res     | serves the right to change specifications without notice |



December 2, 2016

# Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Loren Cook Exhaust Fans and Roof Hoods with Flat Curbs

Approved By:

Date of Approval:









PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016

# **GEMINI**

# Ceiling Fans 100 Series

STANDARD CONSTRUCTION FEATURES:

Forward curved injection molded polypropylene fan wheel - Injection molded flame resistant fan housing with round outlet duct - 22 ga. galvanized steel inlet box - Isolation mounted motor, mounted to one piece galvanized stamped steel integral motor mount/inlet - Permanently lubricated 2-speed motor with built-in thermal overload protection and disconnect plug - Field wiring compartment with receptacle - Adjustable prepunched mounting bracket - White, high impact styrene injection molded grille - Shipped in ISTA certified transit tested packaging.

| Performance |
|-------------|
|-------------|

|     | Catalog<br>Number |    |      | Nominal<br>RPM |    | Speed<br>Control |
|-----|-------------------|----|------|----------------|----|------------------|
| 106 | GC-128            | 50 | .250 | 673            | 25 | FSC              |

Altitude (ft): 331 Temperature (F): 70

## **Motor Information**


| Volts/Ph/Hz | Nameplate Amps |  |  |  |  |
|-------------|----------------|--|--|--|--|
| 115/1/60    | .252           |  |  |  |  |

## Sound Data Inlet Sound Power by Octave Band

| 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | LwA | dBA | Sones |
|----|----|----|----|----|----|----|----|-----|-----|-------|
| 45 | 45 | 50 | 45 | 38 | 30 | 22 | 13 | 46  | 31  | .8    |

#### Accessories:

CEILING RAD. DAMPER INTEGRAL BD DAMPER FAN SPEED CONTROLLER 5 AMP 120 VOLT WHITE STEEL GRILLE GEMINI ISOLATOR KIT - ISOLATORS




Dimensions (inches)


| Dillielisio | ins (inch | CS | 1 |       |
|-------------|-----------|----|---|-------|
| A Steel     | 13-1/2    |    | M | 3-1/4 |
| B Steel     | 15-1/2    |    | N | 14    |
| D           | 4         |    | N | 14    |
| Е           | 4         | '  |   |       |
| F           | 12        |    |   |       |
| G           | 5/8       |    |   |       |
| Н           | 8-3/8     |    |   |       |
| J O.D.      | 5-15/16   |    |   |       |
| K           | 12-3/4    |    |   |       |
| L           | 6-11/16   |    |   |       |

NOTE: Accessories may affect dimensions shown.

Weight(lbs)\*\*\* Shipping 24 Unit 21

\*\*Includes fan, motor & accessories.





CFM vs SP
CFM vs Watts
Point of Operation
System Curve







PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016

# **GEMINI**

# Ceiling Fans 100 Series

STANDARD CONSTRUCTION FEATURES:

Forward curved injection molded polypropylene fan wheel - Injection molded flame resistant fan housing with round outlet duct - 22 ga. galvanized steel inlet box - Isolation mounted motor, mounted to one piece galvanized stamped steel integral motor mount/inlet - Permanently lubricated 2-speed motor with built-in thermal overload protection and disconnect plug - Field wiring compartment with receptacle - Adjustable prepunched mounting bracket - White, high impact styrene injection molded grille - Shipped in ISTA certified transit tested packaging.

| - |   |    |   |    |   |   |   |   |   |
|---|---|----|---|----|---|---|---|---|---|
| Р | e | rf | O | rı | m | a | n | C | e |

|   | Catalog<br>Number |    |      | Nominal<br>RPM |    | Speed<br>Control |
|---|-------------------|----|------|----------------|----|------------------|
| 6 | GC-146            | 75 | .250 | 810            | 31 | FSC              |

Altitude (ft): 331 Temperature (F): 70

**Motor Information** 


| Volts/Ph/Hz | Nameplate Amps |
|-------------|----------------|
| 115/1/60    | .313           |

Sound Data Inlet Sound Power by Octave Band

| 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | LwA | dBA | Sones |
|----|----|----|----|----|----|----|----|-----|-----|-------|
| 46 | 48 | 50 | 48 | 41 | 34 | 28 | 19 | 48  | 33  | 1.1   |

## Accessories:

INTEGRAL BD DAMPER FAN SPEED CONTROLLER 5 AMP 120 VOLT WHITE PLASTIC GRILLE GEMINI ISOLATOR KIT - ISOLATORS




3-1/4


| Dimensions  | (inches) |
|---|----------|
| Name and Address of the Owner, where the Owner, where |          |

| - IIII OII OI OII | 0 (111011100 |
|-------------------|--------------|
| A Plastic         | 13-1/4       |
| B Plastic         | 15-1/2       |
| D                 | 4            |
| Е                 | 4            |
| F                 | 12           |
| G                 | 5/8          |
| Н                 | 8-3/8        |
| J O.D.            | 5-15/16      |
| K                 | 12-3/4       |
| L                 | 6-11/16      |

| NOTE: Accessories ma | y affect dimensi | ions s | shown. |    |
|----------------------|------------------|--------|--------|----|
| Weight(lbs)***       | Shipping         | 18     | Unit   | 15 |

<sup>\*\*</sup>Includes fan, motor & accessories.





CFM vs Watts —
Point of Operation 
System Curve ——








PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016

# **GEMINI**

# Ceiling and Wall Blowers 200-700 Series

STANDARD CONSTRUCTION FEATURES:
Forward curved galvanized steel fan wheels Corrosion resistant galvanized steel fan housing Acoustically insulated housing - Aluminum
backdraft damper with solid aluminum hinge rod
mounted in brass bushings - Permanently
lubricated motor with built-in thermal overload
protection and disconnect plug - Interchangeable
panels with removable fasteners allows the
discharge to be easily changed - Internal wiring box
with disconnect receptacle - Powder-painted white
steel grille. Plastic grill standard on sizes 220,
240,320 and 340...



#### Performance

|   | Catalog<br>Number |     |      | Nominal<br>RPM | Input<br>Watts |
|---|-------------------|-----|------|----------------|----------------|
| 2 | GC-542            | 361 | .250 | 1600           | 124            |

Altitude (ft): 331 Temperature (F): 70

## **Motor Information**

| Volts/Ph/Hz | Nameplate Amps |
|-------------|----------------|
| 115/1/60    | 1.2            |

| <b>Sound Data</b> | Inlet Sound Power by Octave I | 3and |
|-------------------|-------------------------------|------|
|                   |                               |      |

| 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | LwA | dBA | Sones |
|----|----|----|----|----|----|----|----|-----|-----|-------|
| 62 | 69 | 72 | 60 | 52 | 48 | 46 | 43 | 65  | 51  | 5.5   |

## Accessories:


WHITE ALUM GRILLE
GEMINI ISOLATORS

| Dimensions (i | nches) |
|---------------|--------|
| L-HSG         | 17     |
| W-HSG         | 11-7/8 |
| H-HSG         | 11-7/8 |
| A-Outlet      | 8      |
| B-Outlet      | 6      |
| С             | 1      |
| Alum Grille J | 18-3/4 |
| Alum Grille K | 13-3/4 |

NOTE: Accessories may affect dimensions shown.

Weight(lbs)\*\*\* Shipping 34 Unit 30

\*\*\*Includes fan, motor & accessories.



Fan Curve Legend

CFM vs SP

CFM vs Watts

Point of Operation

System Curve







MARK: EF-3A

PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016

# **GEMINI**

# Ceiling Fans 100 Series

STANDARD CONSTRUCTION FEATURES:

Forward curved injection molded polypropylene fan wheel - Injection molded flame resistant fan housing with round outlet duct - 22 ga. galvanized steel inlet box - Isolation mounted motor, mounted to one piece galvanized stamped steel integral motor mount/inlet - Permanently lubricated 2-speed motor with built-in thermal overload protection and disconnect plug - Field wiring compartment with receptacle - Adjustable prepunched mounting bracket - White, high impact styrene injection molded grille - Shipped in ISTA certified transit tested packaging.

| Pe | rfo | rm | an | ce |
|----|-----|----|----|----|
|----|-----|----|----|----|

|   | Catalog<br>Number |     | SP<br>(inwc) | Nominal<br>RPM | Input<br>Watts |
|---|-------------------|-----|--------------|----------------|----------------|
| 4 | GC-186            | 218 | .250         | 1100           | 91             |

Altitude (ft): 331 Temperature (F): 70

**Motor Information** 


| Volts/Ph/Hz | Nameplate Amps |
|-------------|----------------|
| 115/1/60    | .817           |

Sound Data Inlet Sound Power by Octave Band

| 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | LwA | dBA | Sones |
|----|----|----|----|----|----|----|----|-----|-----|-------|
| 58 | 60 | 66 | 66 | 60 | 54 | 53 | 48 | 66  | 51  | 5.5   |

## Accessories:

INTEGRAL BD DAMPER WHITE PLASTIC GRILLE GEMINI ISOLATOR KIT - ISOLATORS



3-1/4

14

M


| Dim | ension | e line | hac |
|-----|--------|--------|-----|


| A Plastic | 13-1/4  |  |  |
|-----------|---------|--|--|
| B Plastic | 15-1/2  |  |  |
| D         | 4       |  |  |
| Е         | 4       |  |  |
| F         | 12      |  |  |
| G         | 5/8     |  |  |
| Н         | 8-3/8   |  |  |
| J O.D.    | 5-15/16 |  |  |
| K         | 12-3/4  |  |  |
| ı         | 6-11/16 |  |  |

| L     | 6-11/16 |                       |
|-------|---------|-----------------------|
| FF. A |         | altare and the second |

Weight(Ibs)\*\*\* Shipping 18 Unit 15

\*\*\*Includes fan, motor & accessories.












PROJECT: HOME2SUITES FLOWOOD


DATE: 12/1/2016

# **GEMINI**

# Ceiling and Wall Blowers 200-700 Series

STANDARD CONSTRUCTION FEATURES:
Forward curved galvanized steel fan wheels Corrosion resistant galvanized steel fan housing Acoustically insulated housing - Aluminum
backdraft damper with solid aluminum hinge rod
mounted in brass bushings - Permanently
lubricated motor with built-in thermal overload
protection and disconnect plug - Interchangeable
panels with removable fasteners allows the
discharge to be easily changed - Internal wiring box
with disconnect receptacle - Powder-painted white
steel grille. Plastic grill standard on sizes 220,





## Performance

240,320 and 340..

| Qty | Catalog<br>Number | Flow<br>(CFM) | SP<br>(inwc) | Nominal<br>RPM |     | Speed<br>Control |
|-----|-------------------|---------------|--------------|----------------|-----|------------------|
| 1   | GC-720            | 600           | .250         | 1283           | 237 | FSC              |

Altitude (ft): 331 Temperature (F): 70

## Motor Information

| Volts/Ph/Hz | Nameplate Amps |
|-------------|----------------|
| 115/1/60    | 3.9            |

| Sou | ınd | Da | ta | Inle | et S | oun | d P | ower | by Oc | tave Ba | nd |
|-----|-----|----|----|------|------|-----|-----|------|-------|---------|----|
| 1   | 2   | 3  | 4  | 5    | 6    | 7   | 8   | LwA  | dBA   | Sones   |    |
| 68  | 67  | 64 | 59 | 53   | 48   | 49  | 49  | 61   | 47    | 4.5     |    |

#### Accessories:

FAN SPEED CONTROLLER 5 AMP 120 VOLT WHITE ALUM GRILLE GEMINI ISOLATOR KIT - ISOLATORS

| Difficiliations ( | 1101103/ |
|-------------------|----------|
| L-HSG             | 17       |
| W-HSG             | 11-7/8   |
| H-HSG             | 11-7/8   |
| A-Outlet          | 10-1/2   |
| B-Outlet          | 4-3/4    |
| С                 | 1        |
| Alum Grille J     | 18-3/4   |


Dimensions (inches)

NOTE: Accessories may affect dimensions shown.

Weight(lbs)\*\*\* Shipping 38 Unit 34

\*\*\*Includes fan, motor & accessories

Alum Grille K 13-3/4



CFM vs SP - CFM vs Watts -

Point of Operation System Curve







MARK: EF-5 & 6

PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016

# **GEMINI**

# Ceiling Fans 100 Series

STANDARD CONSTRUCTION FEATURES:

Forward curved injection molded polypropylene fan wheel - Injection molded flame resistant fan housing with round outlet duct - 22 ga. galvanized steel inlet box - Isolation mounted motor, mounted to one piece galvanized stamped steel integral motor mount/inlet - Permanently lubricated 2-speed motor with built-in thermal overload protection and disconnect plug - Field wiring compartment with receptacle - Adjustable prepunched mounting bracket - White, high impact styrene injection molded grille - Shipped in ISTA certified transit tested packaging.

| Pei | for | ma | nce |
|-----|-----|----|-----|

|   |   | Catalog<br>Number |     |      |      |     |  |  |
|---|---|-------------------|-----|------|------|-----|--|--|
| ľ | 2 | GC-188            | 234 | .375 | 1450 | 108 |  |  |

Altitude (ft): 331 Temperature (F): 70

**Motor Information** 


| Volts/Ph/Hz | Nameplate Amps |
|-------------|----------------|
| 115/1/60    | 1              |

Sound Data Inlet Sound Power by Octave Band

| 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | LwA | dBA | Sones |
|----|----|----|----|----|----|----|----|-----|-----|-------|
| 59 | 63 | 69 | 66 | 62 | 57 | 55 | 50 | 68  | 53  | 6.0   |

#### Accessories:

INTEGRAL BD DAMPER WHITE PLASTIC GRILLE GEMINI ISOLATOR KIT - ISOLATORS



3-1/4


| Dir | nanc  | ione    | (inc | hae  |
|-----|-------|---------|------|------|
| ווע | Hells | SILOIIS |      | 1162 |


|           |         | / - |   |   |
|-----------|---------|-----|---|---|
| A Plastic | 13-1/4  |     | M | Ī |
| B Plastic | 15-1/2  |     | N |   |
| D         | 4       |     |   |   |
| Е         | 4       |     |   |   |
| F         | 12      |     |   |   |
| G         | 5/8     |     |   |   |
| Н         | 8-3/8   |     |   |   |
| J O.D.    | 5-15/16 |     |   |   |
| K         | 12-3/4  |     |   |   |
| L         | 6-11/16 |     |   |   |

NOTE: Accessories may affect dimensions shown.

Weight(Ibs)\*\*\* Shipping 18 Unit 15

\*\*Includes fan, motor & accessories.





CFM vs SP — CFM vs Watts — Point of Operation Osystem Curve




PR

Spun Aluminum Intake/Relief Ventilator

STANDARD CONSTRUCTION FEATURES:

All aluminum construction - Anti-backdraft flange - Five year warranty.



MARK: RHOOD8

DATE: 12/1/2016

PROJECT: HOME2SUITES FLOWOOD

Performance

| C |   | Catalog<br>Number |     | SP<br>(inwc) |
|---|---|-------------------|-----|--------------|
|   | 1 | 8 PR              | 209 | .050         |

Altitude (ft): 331 Temperature (F): 70

## Accessories:

ROOF CURB RCG 16-13.5H BIRDSCREEN

| D          | /! ! \     |
|------------|------------|
| Dimensions | (inches    |
|            | (11101100) |

| A Dia.     | 8-5/8  |
|------------|--------|
| B Dia.     | 18-3/4 |
| С          | 4-5/8  |
| D          | 3-1/2  |
| G          | 2      |
| T Sq.      | 18     |
| Roof Open. | 13-1/2 |

NOTE: Accessories may affect dimensions shown.

| Weight(lbs)*** | Shipping | 36 | Unit | 32 |
|----------------|----------|----|------|----|
|                |          |    |      |    |



PR

PROJECT: HOME2SUITES FLOWOOD


DATE: 12/1/2016

MARK: RHOOD16

Spun Aluminum Intake/Relief Ventilator

**STANDARD CONSTRUCTION FEATURES:** 

All aluminum construction - Anti-backdraft flange - Five year warranty.



**Performance** 

| Qty | Catalog<br>Number | Flow<br>(CFM) | SP<br>(inwc) |
|-----|-------------------|---------------|--------------|
| 12  | 16 PR             | 927           | .050         |

Altitude (ft): 331 Temperature (F): 70

Accessories:

ROOF CURB RCG 26-13.5H BIRDSCREEN

| Dimensions | (inches |
|------------|---------|
| A Dia.     | 16-1/2  |
| B Dia.     | 27-3/4  |
| С          | 5-1/16  |
| D          | 5-1/2   |
| G          | 2       |
| T Sq.      | 28      |
| Roof Open. | 23-1/2  |

NOTE: Accessories may affect dimensions shown.

Weight(lbs)\*\*\* Shipping 66 Unit 60

\*\*\*Includes accessories.



MARK: RHOOD18

PROJECT: HOME2SUITES FLOWOOD


DATE: 12/1/2016

Spun Aluminum Intake/Relief Ventilator

STANDARD CONSTRUCTION FEATURES:

All aluminum construction - Anti-backdraft flange - Five

year warranty.



Performance

| C | <b>Q</b> ty | Catalog<br>Number | Flow<br>(CFM) | SP<br>(inwc) |
|---|-------------|-------------------|---------------|--------------|
|   | 4           | 20 PR             | 1438          | .050         |

Altitude (ft): 331 Temperature (F): 70

Accessories:

ROOF CURB RCG 30-13.5H **BIRDSCREEN** 

| Dimensions | (inches) |
|------------|----------|
|            |          |

| A Dia.     | 20-1/2 |
|------------|--------|
| B Dia.     | 36-5/8 |
| С          | 6-3/4  |
| D          | 4-7/8  |
| G          | 2      |
| T Sq.      | 32     |
| Roof Open. | 27-1/2 |

NOTE: Accessories may affect dimensions shown.

Weight(Ibs)\*\*\* | Shipping | 88 | Unit | 78

\*\*Includes accessories.



**GR** 

# **Gravity Relief Ventilator**


STANDARD CONSTRUCTION FEATURES: Heavy gauge aluminum construction -Birdscreen - Radius throat - Rain gutter to prevent rain infiltration - Welded curb cap corners - Integral lifting lugs/tie down points


- Hinged hood standard on throat lengths less than 73" - Five year warranty.


MARK: RHOOD36X36

PROJECT: HOME2SUITES FLOWOOD

DATE: 12/1/2016







#### Performance

| Qty | Catalog<br>Number | Flow<br>(CFM) | SP<br>(inwc) | Face Velocity<br>(fpm) | Installation |
|-----|-------------------|---------------|--------------|------------------------|--------------|
| 2   | 36X36GR           | 2700          | .011         | 386                    | Ducted       |

Altitude (ft): 331 Temperature (F): 70

## Accessories:

ROOF CURB RCG 40X 40-13.5H W/TRAY ALUM BIRDSCREEN

## **Dimensions** (inches)

| Α | 36    |
|---|-------|
| В | 36    |
| С | 57    |
| D | 51    |
| E | 18.26 |
| F | 2     |
| G | 41.5  |
| Н | 41.5  |
| J | 9     |

NOTE: Accessories may affect dimensions shown

Weight(lbs)\*\*\* Shipping 253 Unit 116

<sup>\*\*\*</sup>Includes accessories





DATE: 12/1/2016


# **GEMINI**

# **CEILING RADIATION DAMPERS**

## NOTE:

Loren Cook Company's curtain style ceiling radiation dampers are classified by UL to function as heat barriers in air handling penetrations through fire resistive membrane ceiling assemblies.

Meets NFPA 90A requirements.
Meets BOCA, SBCCA, UBC requirements.
The City of New York 460-88-5A
California State Fire Marshall 3225-0935:102



| Mark | Qty | Description         | Α      | В      | С      | D      |
|------|-----|---------------------|--------|--------|--------|--------|
| EF-1 | 106 | CEILING RAD. DAMPER | 14-1/2 | 12-3/8 | 6-3/16 | 4-3/16 |



DATE: 12/1/2016


# **FSC**

# **Fan Speed Controls**

## STANDARD CONSTRUCTION FEATURES:

PRODUCT DESCRIPTION - Through the "Quadrac" integrated semi-conductor device it is now possible to offer this system with many advantages. Fewer semi-conductor parts mean greater reliability and the passivation process used in the manufacture of the semi-conductor insures long life. Printed circuit construction eliminates wiring difficulties and guarantees workmanship. All of these factors serve to offer the most important of all features - quality. SPEED CONTROL - Positive Off/On action in the control dial. Speed range set to the customer's requirements. CONTROL RATING - 120 volts, 60 cycles, 1 phase. Maximum ambient temperature -120 degree F (5 AMP, 10 AMP, 15 AMP). 220/240 volt, 50/60 cycles, 1 phase. Maximum ambient temperature - 120 degree F (5 AMP, 10 AMP). 220/240 volt model not UL listed. Fan cannot have UL listing if furnished with prewired 220/240 volt FSC. 277 volt, 60 cycles, 1 phase. Maximum ambient temperature - 120 degree F (5 AMP). WARNING - Power must be turned off before installing this unit. STANDARD INSTALLATION - Fits any standard single gang box. Turn off power and connect the two wires on the control to the two switch wires in the usual manner. The connection box is not supplied. SPECIAL FEATURES - Complete range control, solid state "Quadrac" integrated circuitry, solid state construction for long reliable operating life, saves on electric bills.


| Mark | Qty | Description        |  |  |  |  |  |  |
|------|-----|--------------------|--|--|--|--|--|--|
| EF-1 | 106 | FSC 5 AMP 120 VOLT |  |  |  |  |  |  |
| EF-2 | 6   | FSC 5 AMP 120 VOLT |  |  |  |  |  |  |
| EF-4 | 1   | FSC 5 AMP 120 VOLT |  |  |  |  |  |  |





DATE: 12/1/2016

# **GEMINI**STEEL GRILLE



| Mark | Qty | Description        | Α      | В      | С  | D   |
|------|-----|--------------------|--------|--------|----|-----|
| EF-1 | 106 | WHITE STEEL GRILLE | 13-1/2 | 15-1/2 | 13 | 1/4 |



# **GEMINI**


Gemini Isolator Kit GIK Rubber In Shear

**Dimensions** (inches)

| Mark     | Qty | Description    | Part # | Α |
|----------|-----|----------------|--------|---|
| EF-1     | 106 | GEMINI ISOLATO | GIK    | 4 |
| EF-2     | 6   | GEMINI ISOLATO | GIK    | 4 |
| EF-3     | 2   | GEMINI ISOLATO | GIK    | 4 |
| EF-3A    | 4   | GEMINI ISOLATO | GIK    | 4 |
| EF-4     | 1   | GEMINI ISOLATO | GIK    | 4 |
| EF-5 & 6 | 2   | GEMINI ISOLATO | GIK    | 4 |

PROJECT: HOME2SUITES FLOWOOD


DATE: 12/1/2016





DATE: 12/1/2016

# **GEMINI**PLASTIC GRILLE




| Mark     | Qty | Description          | Α      | В      | С  | D   | E Diam | F Places |
|----------|-----|----------------------|--------|--------|----|-----|--------|----------|
| EF-2     | 6   | WHITE PLASTIC GRILLE | 13-1/4 | 15-1/2 | 13 |     |        | 4        |
| EF-3A    | 4   | WHITE PLASTIC GRILLE | 13-1/4 | 15-1/2 | 13 | 1/4 | 1/4    | 4        |
| EF-5 & 6 | 2   | WHITE PLASTIC GRILLE | 13-1/4 | 15-1/2 | 13 | 1/4 | 1/4    | 4        |



DATE: 12/1/2016

# GEMINI ALUMINUM GRILLE



| Mark | Qty | Description       | Α      | В      | С      | D   | E      |
|------|-----|-------------------|--------|--------|--------|-----|--------|
| EF-3 | 2   | WHITE ALUM GRILLE | 12-3/4 | 17-3/4 | 16-3/8 | 1/4 | 1-1/16 |
| EF-4 | 1   | WHITE ALUM GRILLE | 12-3/4 | 17-3/4 | 16-3/8 | 1/4 | 1-1/16 |



DATE: 12/1/2016


# **RCG**

# Galvanized Steel Roof Curb

# STANDARD CONSTRUCTION FEATURES:

18 gauge galvanized steel - 1-1/2", 3 lbs. density thermal and acoustical insulation - Continuously welded corners -Wood nailer.

Options:(As noted below\*)
1) No wood nailer (deduct 1-1/2" for actual height).
2) Damper tray.



| Dillionor | 2110 | (IIICIIC3)  | Similarions (menes) |          |       |        |        |        |                 |  |  |  |  |  |
|-----------|------|-------------|---------------------|----------|-------|--------|--------|--------|-----------------|--|--|--|--|--|
| Mark      | Qty  | Description | Ht                  | Options* | Α     | F Sq.  | V Sq.  | W Sq.  | Roof<br>Opening |  |  |  |  |  |
| RHOOD8    | 1    | RCG 16      | 13.5                | -        | 1-1/2 | 16-1/2 | 20-1/2 | 9-3/4  | 13-1/2          |  |  |  |  |  |
| RHOOD16   | 12   | RCG 26      | 13.5                | -        | 1-1/2 | 26-1/2 | 30-1/2 | 19-3/4 | 23-1/2          |  |  |  |  |  |
| RHOOD18   | 4    | RCG 30      | 13.5                | -        | 1-1/2 | 30-1/2 | 34-1/2 | 23-3/4 | 27-1/2          |  |  |  |  |  |



DATE: 12/1/2016

# **RCG**

# **Galvanized Steel**

STANDARD CONSTRUCTION FEATURES:


18 ga. galvanized steel - 1-1/2"(3.81 cm), 3 lbs./cu.ft.(1.36 kg/cu. meter) density thermal and accoustical insulation -Continuously welded corners - Wood nailer.

Options:(As noted below\*)

- 1) No wood nailer
- 2) Damper tray

Note:

Roof Opening is (E - 3) X (F - 3)



| Mark       | Qty | Description | Ht   | Options* | A | В   | С     | E  | F  | Roof<br>Opening |
|------------|-----|-------------|------|----------|---|-----|-------|----|----|-----------------|
| RHOOD36X36 | 2   | RCG 40X 40  | 13.5 | 2;       | 2 | 1.5 | 1.875 | 40 | 40 | 37 X 37         |



December 2, 2016

# Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Fantech Dryer Booster Fans

Approved By:


Date of Approval:


# **DBF 4XL**

Dryer Exhaust Booster

# STANDARD FEATURES

- · Airtight galvanized steel housing
- Permanently lubricated sealed ball bearings
- · Self-cleaning backward curved impeller
- Automatic reset thermal overload protection
- 5 1/2 foot 120Vac power cord
- · Five-year factory warranty







| Model   | Metal Gauge | Weight |  |
|---------|-------------|--------|--|
| DBF 4XL | 22          | 8      |  |

All dimensions in inches. Weights in pounds.

|      |     |           | Fan Specif | ications |     |         | THE SHARE THE | Moto  | r Specificati | ons   |      |
|------|-----|-----------|------------|----------|-----|---------|---------------|-------|---------------|-------|------|
| _ine | Qty | Model No. | Tag        | CFM      | SP  | Fan RPM | Watts         | Volts | Phase         | Hertz | Encl |
| 1    | 3   | DBF 4XL   | DBF        | 188      | .25 | 2175    | .54A          | 120   | 1             | 60    |      |
| 2    |     |           |            |          |     |         |               |       |               |       |      |
| 3    |     |           |            |          |     |         |               |       |               |       |      |

| Accessory Items 1 2                  | 3 4 | Accessory Items | 1 2 3 4           |
|--------------------------------------|-----|-----------------|-------------------|
|                                      |     |                 |                   |
|                                      |     |                 |                   |
| Project: HOME 2 SUITES - FLOWOOD, MS |     | Submitted:      | AIRFLO SALES, INC |
| Customer: COMFORT DESIGNS            |     | Approved:       |                   |
| Location: FLOWOOD, MS                |     |                 |                   |

United States 10048 Industrial Blvd. • Lenexa, KS 66215 • 1.800,747.1762 • www.fantech.net Canada 50 Kanalflakt Way • Bouctouche, NB E4S 3M5 • 1.800,565,3548 • www.fantech.net





December 2, 2016

# Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Q mark Electric Wall Heaters

Approved By:

Date of Approval:

# PRODUCT SUBMITTAL SHEET



## **Capacities**

500, 562, 750, 900, 1000, 1125, 1500, 1800 or 2000 Watts 120, 208, 240 or 277V @ 1Ø Only

Thermostat Range: 40° - 85° F Air Movement: 65 CFM

# CWH1000 SERIES FAN-FORCED WALL HEATERS

| Job Name: HOME 2 SUITES     | Submitted By: | Date: |
|-----------------------------|---------------|-------|
| Location: FLOWOOD, MS       |               |       |
| Architect: RICHARD MOLENAAR |               |       |
| Engineer: IES               | -2            |       |
| Contractor: COMFORT DESIGNS | Approved By:  | Date: |
| Submitted By: AIRFLO SALES  |               |       |
| Date: 12-2-20016            | ,             |       |
|                             |               |       |


| Item | QTY | Catalog<br>Number | Tag         | Watts | Volts | PH | AMPS | Weight |
|------|-----|-------------------|-------------|-------|-------|----|------|--------|
|      | 4   | CWH1208DSF        | WALL HEATER | 1000  | 208   | 1  | 4.8  |        |
|      |     |                   |             |       |       |    |      |        |
|      |     |                   |             | à s   |       |    |      |        |
|      |     |                   |             | (4/2  | 4     |    |      |        |
|      |     |                   |             |       | =     |    |      |        |
|      |     |                   |             |       |       |    |      |        |
|      |     |                   |             |       |       |    |      |        |
|      | 1   |                   |             |       |       |    |      |        |
|      |     |                   |             |       |       |    |      |        |
|      |     |                   |             |       |       |    |      |        |
|      |     |                   |             |       |       |    |      |        |

|      |     | ACCESSORIE     | S            |
|------|-----|----------------|--------------|
| Item | QTY | Part<br>Number | Tag          |
|      | 4   | CWHSM          | WALL HEATERS |
|      |     |                |              |
|      |     |                | *            |



470 Beauty Spot Road East Bennettsville, South Carolina 29512 www.marleymep.com





| Catalog Number | Volts | Amps     | Watts                 | BTU/HR    | Wire Size |
|----------------|-------|----------|-----------------------|-----------|-----------|
| CWH1101DSF     | 120   | 8.4/4.2  | 1000/500              | 3413/1706 | 14AWG     |
| CWH1151DSF     | 120   | 12.5/6.3 | 1500/750              | 5120/2560 | 12AWG     |
| CWH1201DSF     | 120   | 15.0/7.5 | 1800/900              | 6143/3072 | 12AWG     |
| CWH1202DSF     | 240   | 8.4/4.2  | 2000/1000             | 6826/3413 | 14AWG     |
| CVVH1202D3F    | 208   | 7.3/3.6  | 1500/750              | 5120/2560 | 14AWG     |
| CWH1207DSF     | 277   | 7.3/3.6  | 2000/1000             | 6826/3413 | 14AWG     |
| CVVIIIZO7D3I   | 240   | 6.3/3.2  | 1500/750              | 5120/2560 | 14AWG     |
| CIAUI1157DCF   | 277   | 5.5/2.75 | 1500/750              | 5120/2560 | 14AWG     |
| CWH1157DSF     | 240   | 4.7/2.4  | 1125/562              | 3840/1920 | 14AWG     |
| CWH1208DSF     | 208   | 9.6/4.8  | <del>2000</del> /1000 | 6826/3413 | 14AWG     |

|  |                   | a                  | I T        |
|--|-------------------|--------------------|------------|
| Joseph Land Land Land Land Land Land Land Land |                   | 12-13°<br>207-mi   | 11 con 279 |
| subsections: 1                                 |                   |                    |            |
|  |                   | 3                  | Line L     |
| 10   | 9-1/4"<br>(2050m) |                    |            |
|  | 12<br>23<br>23    | )I 7/8°<br>)I_22mn |            |

10-5.8

12-1/2" (318mm)H X 10-3/8" (264mm)W X 4" (102mm)

CWHS1 1" (25mm) Recess Mounting Frame (Accessory) Order Separately - Northern White

CWHS2 2" (50mm) Recess Mounting Frame (Accessory) Order Separately - Northern White

SRAFCTP F Tamper-resistant front cover - Northern White

Surface Mounting Frame (Accessory) Order Separately - Northern White

Standard color is Northern White.

**CWHSM** 

#### ARCHITECT'S AND ENGINEER'S SPECIFICATIONS\*

The heating equipment shall include an electric automatic fan forced air heater suitable for small area heating, as manufactured by QMark®, a Marley Engineered Products® Brand, Bennettsville, SC. The heater shall be designed for wall mounting, recess or surface. Heaters shall be cETLus listed.

**BACK BOX:** The back box shall be designed as a recessed ough-in box in either masonry or frame installations and is also used when surface mounting frames are used in surface mounting installations. The back box shall be heavy gauge galvanized steel and shall contain knockouts through which power leads enter.

**INNER FRAME ASSEMBLY:** The heater assembly, which fits into the back box, shall consist of a heavy gauge steel fan panel to which all of the operational parts of the heater are mounted. The inner frame assembly shall be completely prewired.

**HEATING ELEMENT:** The heating element shall be of the non-glowing design consisting of an 80/20 nickel-chromium resistance wire enclosed in a steel sheath to which plate fins are copper brazed. The element shall cover the entire air discharge area to ensure uniform heating of all discharged air. It shall be warrantied for 5 years.

**ON/OFF SWITCH:** A double-pole, single throw on/off switch shall be mounted on the back box for positive disconnect of power supply. It will be completely concealed behind the front cover.

MOTOR AND CONTROLS: The fan motor shall be impedance protected, permanently lubricated. Fan control shall be of the bi-metallic, snap-action type and shall activate fan after heating element reaches operating temperature, and continue to operate the fan after the thermostat is satisfied and until all heated air has been discharged. The thermostat shall be single-pole type on all models. Thermal cutout shall be self-hold (manual-reset) type designed to shut off heat in the event of overheating. The fan shall be four-bladed aluminum. A back-up (End of Life) thermal fuse shall be provided for additional safety.

**SURFACE MOUNTING FRAME:** The surface mounting frame shall be of heavy gauge steel designed to mount around the back box for a finished surface installation. Slot knock outs shall be provided for power supply conduit.

**FRONT COVER:** The louvered front cover shall be of heavy gauge steel with a powder paint finish. A plug button will be provided to replace the thermostat knob and render the unit tamper-resistant.

**FINISH:** All sheet metal parts, except the galvanized steel back box, shall be phosphatized, then completely painted by a powder paint process.

\*In the interest of continual improvements in product and performance, Marley Engineered Products reserves the right to change specifications without notice.



December 2, 2016

# Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Ruskin Fire Dampers and Access Doors

Approved By:

Date of Approval:

# Schedule



Job: Home2Suites Flowood

| Model   | Quantity | Tag     | WIDTH | HEIGHT | SIZE           | FRAME      | MOUNTING | FUSELINK<br>TEMP | VELOCITY | STATIC<br>PRESSURE | SLEEVE/TRANS | MOUNTING<br>ANGLES | SLV.<br>ACCESS. | SEALED<br>SLEEVE | Comments |
|---------|----------|---------|-------|--------|----------------|------------|----------|------------------|----------|--------------------|--------------|--------------------|-----------------|------------------|----------|
| DIBD20G | 1        | FD<br>G | 24    | 12     | Actual<br>Size | G<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | FAST 1.5 1<br>SIDE | NONE            | NO               |          |
| DIBD20G | Ĭ        | FD<br>G | 30    | 24     | Actual<br>Size | G<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | FAST 1.5 1<br>SIDE | NONE            | NO               |          |



3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

# IBD20G and DIBD20G CURTAIN TYPE FIRE DAMPERS FOR GRILLES

11/2 HOUR UL555 RATED

FOR USE IN STATIC OR DYNAMIC SYSTEMS

### **APPLICATION**

IBD20G (Static) and DIBD20G (Dynamic) curtain type fire dampers for grille installation may be installed vertically in walls or horizontally in floors with fire resistance ratings of less than 3 hours. Model 'G' curtain fire dampers are offset in a sleeve to fit within the wall/floor plane behind the customer's supplied grille. The damper/sleeve assembly is installed with angle one side (FAST) to allow the use of all types of grilles.

Model 'G' dampers require access to both sides of the wall/floor for the proper installation; however, access through the grille for inspection or maintenance is permissible.

For application where the damper would be installed outside the plane of the wall or floor refer to model GA (Grille Access) or OW (Out of Wall).

#### STANDARD CONSTRUCTION

#### FRAME AND BLADES

Galvanized (in gauges required by UL listing R-5531).

#### **CLOSURE SPRINGS**

Stainless steel (when required by UL listing R-5531).

#### **FUSIBLE LINK**

 $165^{\circ}F~(74^{\circ}C)$  is standard.  $212^{\circ}F~(100^{\circ}C)$  and  $285^{\circ}F~(141^{\circ}C)$  are optional.

#### SLEEVE

20 gauge (1.0) galvanized steel.

## MOUNTING ANGLE (FAST)

20 gauge (1.0) galvanized steel (one piece wrap around angle).

## **OPTIONS**

- · FM Approved as Specification Tested Product.
- SP100 Switch Package to remotely indicate damper blade position.
- Factory sealed sleeve

## **NOTES**

- 1. Dimensions shown in parentheses ( ) indicate millimeters.
- 2. Damper/sleeve assembly furnished actual size to inside of sleeve.

- National Fire Protection Association NFPA Standards 90A and 101
- ICC International Building Codes
- CSFM California State Fire Marshal Fire Damper Listing (#3225-245:005)
- New York City (BSA Listing #297-71-SA)

## **UL CLASSIFIED**

UL555 Listing R5531





#### **DAMPER SIZES**

#### IBD20G

Not for use in Dynamic (fans on) System

## MINIMUM SIZE

Vertical Installation -4"w x 4"h (102 x 102) Horizontal Installation -6"w x 6"h (152 x 152)

#### MAXIMUM SIZE

Vertical Installation - 48"w x 30"h (1219 x 762) or 33"w x 54"h (838 x 1372) or 36"w x 36"h (914 x 914) Horizontal Installation - 30"w x  $45^1/_2$ "h (762 x 1156) or 33"w x 38"h (838 x 965)

#### DIBD20G


For use in Dynamic (fans on) or Static (fans off) System

#### MINIMUM SIZE

Vertical – 4"w x 4"h (102 x 102) Horizontal Installation – 6"w x 6"h (152 x 152)

#### MAXIMUM SIZE

Vertical Installation – 33"w x 36"h (762 x 914) Horizontal Installation – 24"w x 24"h (610 x 610)



# **HOW TO APPLY IBD20G AND DIBD20G**


- 1. Size the damper  $A \times B$  (width  $\times$  height)
- 2. 'S' dimension =  $2^{3}/4$ " (70).
- 3. Determine the orientation (wall, floor or ceiling)
- 4. Determine the wall, floor, or ceiling depth.

## DUCTED


- 'G' models have a standard 'S' set back dimension of 2<sup>3</sup>/<sub>4</sub>" (70).
- Sleeve lengths (L) are calculated as: Minimum wall, floor, or ceiling depth = 4" (102)
- The minimum wall, floor or ceiling depth is calculated by adding the 'S' dimension + 11/4" (31) (See note 1).


## NOTES:

 If the wall, floor, or ceiling depth is less than the minimum depth, refer to Models 'GA' or 'OW' for the proper UL installation. Also, consider changing to a grille with a shallower overall depth.




**ORIENTATION** 







**FLOOR** 



**DAMPER DETAIL** 









3900 Dr. Greaves Rd. Kansas City, MO 64030 (816) 761-7476 FAX (816) 765-8955 www.ruskin.com

# Schedule



Job: Home2Suites Flowood

| Model  | Quantity | Tag     | WIDTH | HEIGHT | SIZE          | FRAME      | MOUNTING | FUSELINK<br>TEMP | VELOCITY | STATIC<br>PRESSURE | SLEEVE/TRANS | MOUNTING<br>ANGLES  | SLV.<br>ACCESS | SEALED<br>SLEEVE | Comments |
|--------|----------|---------|-------|--------|---------------|------------|----------|------------------|----------|--------------------|--------------|---------------------|----------------|------------------|----------|
| DIBD20 | 2        | FD<br>B | 22    | 14     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 12    | 12     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | Ī        | FD<br>B | 24    | 10     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 24    | 9      | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | I        | FD<br>B | 20    | 15     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 17    | 10     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 10    | 6      | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 16       | FD<br>B | 24    | 6      | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 22    | 12     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | Į.       | FD<br>B | 18    | 10     | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 1        | FD<br>B | 14    | 8      | Deduct<br>1/4 | B<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |
| DIBD20 | 3        | FD<br>R | 7     | 7      | Deduct<br>1/4 | R<br>STYLE | VERTICAL | 165<br>DEGREES   | 2000 FPM | 4 INCHES           | SLEEVE       | PFMA 1.5 2<br>SIDES | NONE           | NO               |          |

## Job Name: Home2Suites Flowood

| DIBD20 | 7   | FD<br>R  | 6  | 6  | Deduct<br>1/4 | R<br>STYLE | VERTICAL   | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
|--------|-----|----------|----|----|---------------|------------|------------|----------------|----------|----------|--------|---------------------|------|----|
| DIBD20 | 5   | FD<br>R  | 8  | 8  | Deduct<br>1/4 | R<br>STYLE | VERTICAL   | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 3 - | FD<br>R  | 10 | 10 | Deduct<br>1/4 | R<br>STYLE | VERTICAL   | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 2   | FD<br>R  | 9  | 9  | Deduct<br>1/4 | R<br>STYLE | VERTICAL   | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 8   | FDH<br>R | 6  | 6  | Deduct<br>1/4 | R<br>STYLE | HORIZONTAL | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 1   | FDH<br>B | 20 | 15 | Deduct<br>1/4 | B<br>STYLE | HORIZONTAL | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 1   | FDH<br>B | 26 | 12 | Deduct<br>1/4 | B<br>STYLE | HORIZONTAL | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 1   | FDH<br>B | 25 | 10 | Deduct<br>1/4 | B<br>STYLE | HORIZONTAL | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |
| DIBD20 | 1   | FDH<br>B | 24 | 9  | Deduct<br>1/4 | B<br>STYLE | HORIZONTAL | 165<br>DEGREES | 2000 FPM | 4 INCHES | SLEEVE | PFMA 1.5 2<br>SIDES | NONE | NO |



3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

# DIBD20, 40 and 60 CURTAIN TYPE STATIC FIRE DAMPERS 11/2 HOUR UL555 RATED FOR USE IN DYNAMIC AND STATIC SYSTEMS

#### **APPLICATION**

Ruskin Model DIBD20, 40, & 60 are  $1^{1/2}$  hour UL classified dynamic (fans on) or static (fans off) curtain style fire dampers for use in HVAC systems that remain in operation during a fire. Fire dampers are used for the protection of openings in walls, partitions, or masonry floors with fire resistance ratings of less than 3 hours and shall have a  $1^{1/2}$  hour fire protection rating. The DIBD20,40 & 60 can be installed vertically in walls or horizontally in masonry floors and is rated for airflow in either direction.

#### DYNAMIC CLOSURE RATINGS

4000 fpm (20.3 m/s) vertical mount only, up to 24" x 24" (610 x 610). 3000 fpm (15.2 m/s) vertical and horizontal mount, up to 24" x 24" (610 x 610).

2000 fpm (10.2 m/s) vertical or horizontal mount on all sizes. 4 in. w.g. (1 kPa) maximum pressure on all sizes.

#### STANDARD CONSTRUCTION

#### Frame and Blades Material

Galvanized steel or stainless steel (in gauges required by UL listing R-5531).

#### **Closure Springs**

301 stainless steel constant force or spring clip type. Note: Vertical units 24" x 24" (610 x 610) and smaller utilize spring clips only and do not have constant force springs.

#### **Fusible Link**


 $165^{\circ}F~(74^{\circ}C)$  is standard. 212°F (100°C) and 285°F (141°C) are available option.

#### **DAMPER SIZES**

See pages 2 - 5 for minimum and maximum UL sizes. See pages 6 - 9 for construction details on multiple section assemblies.

#### **OPTIONS**

- True Round Fire Damper See model FDR25
- Stainless Steel Construction See model (D)IBD20SS
- FM Approvals as Specification Tested Product
- SP200 Switch Package to allow remote indication of damper blade position
- FAST Angles factory supplied one-side installation. Other angles of various sizes and gauges also available for one-side or twoside installation
- · Factory sealed sleeves and transitions
- · MCP Control panels for monitoring purpose
- · Grille Mounting See (D)IBD20G model



Models DIBD20, 40, and 60 series meet the requirements for fire dampers established by:

- National Fire Protection Association NFPA Standards 80, 90A, 92A, 92B, and 101
- ICC International Building Codes
- CSFM California State Fire Marshal IBD2 #3225-0245:0005
- New York City MEA 450-06-M

UL CLASSIFIED UL555 Listing R5531




FM Approvals
Specification Tested Product
(Option)

#### Notes:

- 1. Dimensions shown in parentheses ( ) indicate millimeters.
- Dampers may require sealing of seams in the field to meet local code leakage requirements.

#### DAMPER STYLES AND SIZES



### B Style - Blades out of the Airstream for Greater Free Area

### **B** Style

Blades out of air stream Sleeve optional

80 - 90% free area

#### MINIMUM SIZE 2000 fpm (10.2 m/s)

Vertical Installation – 4"w x 4"h (102 x 102)

Horizontal Installation – 6"w x 4"h (152 x 102)

#### MAXIMUM SIZE 2000 fpm (10.2 m/s)

#### Single Section

Vertical Installation - 33"w x 32"h (838 x 813)

Horizontal Installation – 24"w x 21"h (610 x 533)

#### **Multiple Section Assembly**

Vertical Installation - 54"w x 45"h (1372 x 1143) or

48"w x 51"h (1219 x 1295) or 54"w x 21"h (1372 x 533)

Horizontal Installation - 36"w x 42"h (914 x 1067) or

48"w x 30"h (1219 x 813).

The minimum width or height becomes 9"w x 8"h

(229 x 203) when damper's width or height is over 21" (533).


### DIBD2 MINIMUM SIZE UNITS ABOVE 2000 fpm (10.2 m/s)

Vertical or Horizontal Installation – 9"w x 7"h (229 x 178)

### DIBD2 MAXIMUM SIZE UNITS ABOVE 2000 fpm (10.2 m/s)

Single Section only

Vertical or Horizontal Installation - 24"w x 21"h (610 x 533)




A = Duct Width

B = Duct Height

H = Overall Damper Height

### **DAMPER STYLES AND SIZES**



#### R Style - Round Transition

Round enclosure. Blades partially in the air stream Non-sealed sleeve standard Sealed sleeve optional

85 - 95% free area

### MINIMUM SIZE

Vertical Installation – 3" diameter (76)

Horizontal Installation - 4" diameter (102)

#### MAXIMUM SIZE

### Single Section


Vertical Installation – 31" diameter (787) Horizontal Installation – 22" diameter (559)


D = Diameter

H = Overall Damper Height

### NOTE:

- 1. Style R the duct connection extends  $1^{1/2}$ " (38) beyond the damper.
- 2. See page 10 for overall dimensional information







#### ASSEMBLY AND DIMENSIONAL INFORMATION

Dampers normally fabricated approximately 1/4" (6) less than given duct dimensions. A (width) and B (height) dimensions shown describe maximum UL Classified sizes. Multiple section damper assemblies ordered without sleeves are shipped in individual sections, for field assembly. Multiple section dampers ordered with factory furnished sleeves are normally shipped in complete assemblies,

### DIBD20, 40, & 60 A STYLE DAMPERS



### HORIZONTAL INSTALLATION




### **ASSEMBLY AND DIMENSIONAL INFORMATION**


### B STYLE DAMPERS VERTICAL INSTALLATION

'X' dim. + 'B' dim. = 'H' dim.


| Single Section Units<br>24" (610) wide and<br>20" (508) high and under |            |
|--|------------|
| 'B' Damper Height  | 'x' Dim.   |
| 4" (102) thru 8" (203)   | 13/4" (44) |
| 8.01" (204) thru 16" (406)   | 23/4" (70) |
| 16.01" (407) thru 20" (508)  | 33/4" (95) |




| Above 24" (610) wide or :   | ngle Section Units<br>(610) wide or 20" (508) high<br>' (838) wide by 32" (813) high |  |
|-----------------------------|--|--|
| 'B' Damper Height           | 'x' Dim.   |  |
| 4" (102) thru 12" (305)     | 13/4" (44)   |  |
| 12.01" (306) thru 23" (584) | 23/4" (70)   |  |
| 23.01" (585) thru 32" (813) | 33/4" (95)   |  |




| Multiple Section Wide and High<br>Above 21" (533) thru 69" (1153) high |            |
|--|------------|
| 'B' Damper Height  | 'x' Dim.   |
| 22" (559) thru 26" (660)   | 13/4" (44) |
| 26.01" (661) thru 51" (1295)   | 23/4" (70) |





| Multiple Section<br>Single Section High 21" |              |  |
|---|--------------|--|
| 'B' Damper Height                           | 'x' Dim.     |  |
| 4" (102) thru 12" (305)                     | 13/4" (44)   |  |
| 12.01" (306) thru 21" (533)                 | 23/4" (70) . |  |




### HORIZONTAL INSTALLATION


'X' dim. + 'B' dim. = 'H' dim.


| Single Section Units<br>24" (610) wide and<br>20" (508) high and under |            |
|--|------------|
| 'B' Damper Height  | 'x' Dim.   |
| 4" (102) thru 10" (254)  | 13/4" (44) |
| 10.01" (255) thru 21" (533)  | 23/4" (70) |

| Multiple Section High and<br>36" (914) wide and under |             |
|---|-------------|
| 'B' Damper Height                                     | 'x' Dim.    |
| 8" (203) thru 12" (305)                               | 13/4" (44)  |
| 12.01" (306) thru 21" (533)                           | 23/4" (70)  |
| 21.01" (534) thru 24" (610)                           | 31/2" (89)  |
| 24.01" (611) thru 42" (1067)                          | 51/2" (140) |

| Multiple Section I<br>Over 36" (914) |             |
|--------------------------------------|-------------|
| 'B' Damper Height                    | 'x' Dim.    |
| 8" (203) thru 12" (305)              | 13/4" (44)  |
| 12.01" (306) thru 15" (381)          | 23/4" (70)  |
| 15.01" (382) thru 22" (559)          | 31/2" (89)  |
| 22.01" (560) thru 30" (762)          | 51/2" (140) |








### ASSEMBLY AND DIMENSIONAL INFORMATION For 2000 fpm (10.2 m/s) and 4 in. wg. (1 kPa) MAX.

## CR and LR STYLE DAMPERS VERTICAL INSTALLATION

'X' dim. + 'Dia' dim. = 'H' dim.


| SINGLE SECTION HIGH         |             |
|-----------------------------|-------------|
|                             |             |
| 3" (76) thru 7" (178)       | 23/4" (70)  |
| 7.01" (179) thru 15" (533)  | 33/4" (95)  |
| 15.01" (534) thru 19" (483) | 43/4" (121) |
| 19.01" (484) thru 22" (559) | 3 (95)      |
| 22.01" (560) thru 31" (787) | 43/4" (121) |




### HORIZONTAL INSTALLATION


"X' dim. + 'Dia' dim. = 'H dim.

| SINGLE SECTION            | HIGH       |
|---------------------------|------------|
| 'H' DIMENSION             |            |
| 'Dia' Damper Height       | 'x' Dim.   |
| 4" (102) thru 9" (228)    | 23/4" (70) |
| 9.01" (229) hru 20" (508) | 33/4" (95) |



### R STYLE DAMPERS VERTICAL AND HORIZONTAL INSTALLATION





### ASSEMBLY AND DIMENSIONAL INFORMATION

For 4000 fpm (20.3 m/s) and 4 in. wg. (1 kPa) MAX. Vertical Mount Only


For 3000 fpm (15.2 m/s) and 4 in. wg. (1 kPa) MAX. Vertical or Horizontal Mount



#### **B DAMPERS**

'X' dim. + 'B' dim. = 'H' dim.


| Single Section Units        |            |
|-----------------------------|------------|
| 'B' Damper Height           | 'x' Dim.   |
| 8" (203) thru 12" (305)     | 13/4" (44) |
| 12.01" (306) thru 21" (533) | 23/4" (70) |




### C and CO DAMPERS

'X' dim. + 'B' dim. = 'H' dim.

| Single Section Units        |            |
|-----------------------------|------------|
| 'B' Damper Height           | 'x' Dim.   |
| 7" (178) thru 11" (280)     | 23/4" (44) |
| 11.01" (281) thru 20" (508) | 33/4" (95) |






#### **CR Dampers**

'X' dim. + 'Dia' dim. = 'H'

| Single Section Units        |            |
|-----------------------------|------------|
| 'Dia' Damper Height         | 'x' Dim.   |
| 7" (178) thru 11" (280)     | 23/4" (44) |
| 11.10" (281) thru 20" (508) | 33/4" (95) |



### **DIBD20, 40 & 60 SUGGESTED SPECIFICATION**

Furnish and install at locations shown on the plans, or as described in schedules for curtain type fire dampers suitable for vertical wall or horizontal masonry floor or ceiling. Dynamic fire dampers tested, constructed and labeled in accordance with the latest edition of UL Standard 555. Dampers shall have a fire rating of 1½ hours and shall meet the requirements of the latest edition of NFPA90A. Fire dampers shall be produced in an ISO 9001 certified factory.

Damper frame and blades shall be galvanized steel in gauges required by UL listing R-5531 installed in a factory mounted sleeve and shipped loose mounting angle. Damper blades shall be steel interlock to provide fire shield in gauges required by UL listing R-5531. Closure spring dampers shall be of 301 stainless steel and shall be constant force type.

Each dynamic fire damper shall include a steel sleeve and mounting angles furnished by the damper manufacturer to ensure appropriate installation. Submittal information shall include the fire protection rating, maximum velocity/pressure ratings and the manufac-

turer's UL installation instructions. The dampers shall be installed in accordance with the manufacturer's UL installation instructions. Dynamic fire dampers shall be in all respects equivalent to Ruskin model DIBD20, 40 & 60.

Each damper shall include a 165°F (74°C), 212°F (100°C) or 285°F (141°C) fusible link and shall be labeled for use in dynamic systems. Dampers labeled for use in static systems only are not permitted. The damper shall be rated for dynamic closure at 2000 fpm (10.16 m/s) and 4 inches w.g. (1 kPa) static pressure and shall be rated to close with airflow in either direction.

### Optional FM Approvals Specification

Each fire damper shall be listed in Factory Mutual (FM) Approvals Specification Tested Product and labeled accordingly.

Dynamic fire dampers shall be Ruskin model DIBD20, 40 & 60. (Consult www.ruskin.com for electronic version of this "Quick" spec as well as for complete 3-part CSI MasterFormat Specifications)



3900 Dr. Greaves Rd. Kansas City, MO 64030 (816) 761-7476 FAX (816) 765-8955 www.ruskin.com



| Model | Quantity | Tag | WIDTH | HEIGHT | SIZE           | CAM<br>MATERIAL | CONSTRUCTION | DOOR<br>GAUGE | EXTRA<br>CAMS | LATCHES      | SECURITY<br>CHAIN | DOOR SEAL    | Comments |
|-------|----------|-----|-------|--------|----------------|-----------------|--------------|---------------|---------------|--------------|-------------------|--------------|----------|
| ADC24 | 2        | AD  | 6     | 6      | Actual<br>Size | STANDARD        | GALVANIZED   | 24<br>GAUGE   | NONE          | CAM<br>LATCH | NO                | POLYURETHANE |          |
| ADC24 | 29       | AD  | 12    | 12     | Actual<br>Size | STANDARD        | GALVANIZED   | 24<br>GAUGE   | NONE          | CAM<br>LATCH | NO                | POLYURETHANE |          |



3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

#### STANDARD ACCESS DOORS

#### **APPLICATION**

Ruskin access doors offer quick, easy and economical installation wherever duct access is needed. Manual locks assure tight door closure and the continuous piano-type hinge models give smooth operation. The ADCW and ADHW models feature a "see through" panel that permits visual duct inspection without door removal.

#### STANDARD CONSTRUCTION

#### FRAME

22 gage (.8) galvanized steel with seal.

#### DOOR

24 gage (.7) galvanized steel.

ADC14 - Removable, single skin.

ADH14 - Hinged, single skin.

ADC24 – Removable, double skin.

ADH24 - Hinged, double skin.

ADCW24 – Removable, double skin with round transparent plexiglass window.

ADHW24 - Hinged, double skin with round transparent plexiglass window.

#### HINGE (ADH Models Only)

Continuous piano type.

#### LOCKS

ADH Models – Doors 16" (406) and under have one lock, doors over 16" (406) have two locks.

ADC Models  $^-$  Doors 16" (406) and under have two locks, doors over 16" (406) have four locks.

### MAXIMUM STATIC PRESSURE

Double skin access doors have been tested to 6" w.g. Leakage increases as system pressure increases. Refer to chart on page 2.

#### SEALS

Foam gasket.

#### INSULATION

1" (25) fiberglass.

#### MINIMUM SIZE

6"w x 6"h (152 x 152).

#### MAXIMUM SIZE

24"w x 24"h (610 x 610).

#### INSTALLATION

Cut hole 11/8" (28) smaller than door size.


#### **VARIATIONS**


- · Additional cam locks
- · Wire reinforced glass window
- 20 gage (.9) door panels
- Ventlock 100 latches
- · Stainless steel construction
- · Bronze hinge pins

- Brass cams
- · Security chain
- Intermediate sizes between 6" x 6" (152 x 152) and 24" x 24" (610 x 610)


#### 7, 01


- NOTES
- 1. Dimensions shown in parenthesis ( ) indicate millimeters.
- 2. Access doors furnished actual size.
- 3. For doors larger than 24" x 24" (610 x 610) see GPAD.





### 12" x 12" ACCESS DOOR









| Model | Quantity | Tag | SIZE        | DUCT DIAMETER | DOOR SIZE        | CONSTRUCTION | Comments |
|-------|----------|-----|-------------|---------------|------------------|--------------|----------|
| ADR1  | 15       | ADR | Actual Size | 6 Inch DIA.   | 10 Inch X 6 Inch | GALVANIZED   |          |
| ADR1  | 8        | ADR | Actual Size | 8 Inch DIA.   | 10 Inch X 6 Inch | GALVANIZED   |          |
| ADR1  | 5        | ADR | Actual Size | 10 Inch DIA.  | 10 Inch X 6 Inch | GALVANIZED   |          |



3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

### ADR and ADF ACCESS DOORS

Ruskin ADR and ADF access doors are an inexpensive and trouble-free way to gain access into sheet metal ductwork systems for resetting dampers, cleaning filters, or access for general maintenance. The oval shaped opening permits the back plate or "inner plate" to be easily passed through the duct openings, and the neoprene gasket on the inner plate provides for an absolutely air-tight

seal. The large hand knobs insure a quick method to remove and reinstall the door without the use of special tools. The ADR (for round duct work) and ADF (for flat duct work) are available in three sizes, 16" x 12", 10" x 6" and 8" x 4" to accommodate the many different sizes of duct work that are available.



#### **METAL THICKNESSES**

20 (.9) gauge steel - 10" x 6" (254 x 152) door size.

20 (.9) gauge steel - 16" x 12" (406 x 305) door size.

20 (.9) gauge steel - 8" x 4" (203 x 102) door size.

### **CELLULAR SPONGE GASKET**

Fixed to the inner plate keeps the doors free of leaks at pressures to 20" w.g.

### ACCESS DOOR MODELS AND SIZES

Ruskin ADF is available in 8" x 4" (203 x 102), 10" x 6" (254 x 152) and 16" x 12" (406 x 305) sizes for rectangular (flat) ductwork. Ruskin ADR is available as the ADR1 size 10" x 6" (254 x 152), the ADR2 size 16" x 12" (406 x 305), and the ADR3 size 8" x 4" (203 x 102) for round duct work in the following sizes:

#### **AVAILABLE OPTIONS**

Aluminum Construction: ADR1 and ADR2 Only.


304SS Construction: ADR1 and ADR2 Only.

### ADR1, 10" x 6" (254 x 152) DUCT SIZES


6", 8", 9" 10", 12", 14", 16", 18", 20", 22", 24", 26", 28", 30" (152, 203, 229, 254, 305, 356, 406, 457, 508, 559, 610, 660, 711,

ADR2, 16" x 12" (406 x 305) DUCT SIZES
12", 14", 16", 18", 20", 22", 24", 26", 28", 30", 32", 34", 36", 38", 40", 42", 44", 46", 48" (305, 356, 406, 457, 508, 559, 610, 660, 711, 762, 813, 864, 914, 965, 1067, 1118, 1168, 1219).

ADR3, 8" x 4" (203 x 102) DUCT SIZES 4", 6", 8", 9" 10", 12", 14", 16", 18", 20", 22", 24", 26", 28", (102, 152, 203, 229, 254, 305, 356, 406, 457, 508, 559, 610, 660, 711).



### **INSTALLATION INSTRUCTIONS**



**SELF-ADHESIVE TEMPLATES** are also provided so that the duct opening can be cut without expensive lay-out.



**EASY INSTALLATION** after door opening has been cut, unscrew handles or door in insert in the opening, align then tighten knobs.



3900 Dr. Greaves Rd. Kansas City, MO 64030 (816) 761-7476 FAX (816) 765-8955 www.ruskin.com



December 2, 2016

### Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Titus Grilles and Diffusers

Approved By:

Date of Approval:



| Model       | Quantity | Tag      | DIM 1           | DIM<br>2 | Module | Border            | Finish        | Pattern | Damper                                  | Accessory 1                   | Accessory<br>2 | Accessory<br>3 | Comments |
|-------------|----------|----------|-----------------|----------|--------|-------------------|---------------|---------|---|-------------------------------|----------------|----------------|----------|
| TMSA-<br>AA | 23       | CD<br>LI | 10"<br>DIAMETER |          | 24X24  | 3 -<br>LAY-<br>IN | 26 -<br>WHITE |         | D-75 - ROUND<br>NECK-<br>MOUNTED<br>OBD | IB -<br>INSULATION<br>BLANKET | NONE           | NONE           |          |
| TMSA-<br>AA | 22       | CD<br>LI | 8"<br>DIAMETER  |          | 24X24  | 3 -<br>LAY-<br>IN | 26 -<br>WHITE |         | D-75 - ROUND<br>NECK-<br>MOUNTED<br>OBD | IB -<br>INSULATION<br>BLANKET | NONE           | NONE           |          |
| TMSA-<br>AA | 5        | CD<br>LI | 6"<br>DIAMETER  |          | 24X24  | 3 -<br>LAY-<br>IN | 26 -<br>WHITE |         | D-75 - ROUND<br>NECK-<br>MOUNTED<br>OBD | IB -<br>INSULATION<br>BLANKET | NONE           | NONE           |          |




# Submittal

TMSA-AA 1.0


4-6-15

# Square Ceiling Diffusers Aluminum • Adjustable • High Performance


### Model: TMSA-AA • Round Neck • Vertical-to-Horizontal Discharge Pattern




### Other Available Border Types




### Adjusting Optional Damper • Removing Center Cone





### TMSA-AA Discharge Patterns





### Accessories (Optional) Check of if provided.












Dimension "A" in Inches, for Dampers Shown as Above

| Accessories |          |       | Nominal | Round D | uct Sizes |       |     |
|-------------|----------|-------|---------|---------|-----------|-------|-----|
| Accessories | 6        | 7     | 8       | 10      | 12        | 14    | 15  |
| AG-100      |          |       |         | _       |           | _     | N/A |
| D-100       | <u> </u> |       |         | _       | -         | _     | N/A |
| D-75        | 2 3/8    | 2 7/8 | 3 1/4   | 4 1/8   | 4 7/8     | N/A   | N/A |
| AG-85       | 2 1/2    | 3     | 3 1/2   | 4 1/2   | 5 1/2     | 6 1/2 | 7   |
| AG-65       | 3 3/8    | 4     | 4 1/2   | 5 1/2   | 7 1/8     | 8 5/8 | 9   |
| AG-75       | 2 3/4    | 3 1/4 | 3 5/8   | 4 1/2   | 5 3/8     | 2 3/4 | 3   |

#### Note: D-100 and AG-100 dampers have radial blades that slide in a horizontal plane. For that reason, no opening clearance "A" is dimensioned.

### Other Accessories (Optional)

☐ Model SB Sectorizing Baffles



### Standard Finish: #26 White

### General Description

- Model TMSA-AA includes adjustable vanes which vary the discharge pattern between horizontal and vertical.
- Delivers supply air in a true 360° pattern. Designed to protect ceiling from streaking and smudging.
- Excellent for variable volume systems. The uniform, nearly horizontal jet maintains effective room air distribution even when air volume varies over a considerable range.
- The TMSA-AA consists of 3 concentric cones in all sizes. This uniformity of design enhances appearance in installations where more than one size is involved.
- Screwdriver adjustment of the optional damper is achieved without removing the inner cone. (See Note 2, page 2.)
- Quick removal of inner cone with a hex key speeds installation. (See Note 3, page 2.)
- All cones are die-stamped onepiece construction with smooth, clean surfaces and no corner joints.
- Material is heavy gauge aluminum with steel bar webbing.



| Model      | Quantity | Tag | DIM 1        | DIM 2        | Module | Border         | Finish        | Pattern | Damper      | Accessory<br>1 | Accessory<br>2 | Accessory<br>3 | Comments |
|------------|----------|-----|--------------|--------------|--------|----------------|---------------|---------|-------------|----------------|----------------|----------------|----------|
| PAR-<br>AA | 3        | RAG | 6 INCHES     | 6 INCHES     | 24X24  | 3 - LAY-<br>IN | 26 -<br>WHITE |         | 0 -<br>NONE | NONE           | NONE           | NONE           |          |
| PAR-<br>AA | 4        | RAG | 8 INCHES     | 8 INCHES     | 24X24  | 3 - LAY-<br>IN | 26 -<br>WHITE |         | 0 -<br>NONE | NONE           | NONE           | NONE           |          |
| PAR-<br>AA | 2        | RAG | 12<br>INCHES | 12<br>INCHES | 24X24  | 3 - LAY-<br>IN | 26 -<br>WHITE |         | 0 -<br>NONE | NONE           | NONE           | NONE           |          |
| PAR-<br>AA | 2        | RAG | 22<br>INCHES | 22<br>INCHES | 24X24  | 3 - LAY-<br>IN | 26 -<br>WHITE |         | 0 -<br>NONE | NONE           | NONE           | NONE           |          |




PAR-AA


8-13-15


### **Perforated Ceiling Diffusers** Aluminum • Flush Face


Model:


PAR-AA • Return
















|                   |       |   |   |   | Available | Sizes fo | or Border | Types 1 | , 2, 3, 4, | 4SL |   |   |   | * |
|-------------------|-------|---|---|---|-----------|----------|-----------|---------|------------|-----|---|---|---|---|
| Face or           |       | Nominal Duct Size D   |   |   |           |          |           |         |            |     |   |   |   |   |
| Ceiling<br>Module | 6 x 6 | 8 x 8 10 x 10 12 x 12 15 x 15 18 x 18 22 x 22 22 x 10 6" Dia. 8" Dia. 10" Dia. 12" Dia. 14" Dia. 16" Dia. |   |   |           |          |           |         |            |     |   |   |   |   |
| 12 x 12           | •     |   | • |   |           |          |           |         |            |     |   |   |   |   |
| 24 x 12           |       |   |   |   |           |          |           | •       |            |     |   |   |   |   |
| 24 x 24           | •     | •   | • | • | •         | •        | •         | •       | •          | •   | • | • | • | • |

<sup>·</sup> Indicates available combination.

### Removing Perforated Face





### Standard Finish: #26 White

### General Description -

- Model PAR-AA flush face perforated ceiling diffusers are designed for use as returns to match the Model PAS supply diffusers.
- Can be mounted in a plenum or connected to a return duct.
- Optional damper is easily adjusted by dropping the perforated face (see above).
- Perforated face has 3/16" diameter holes on 1/4" staggered centers.
- Material is heavy gauge aluminum face, steel backpan and pattern controllers.



| Model | Quantity | Tag       | Width | Height | Module | Border               | Fastening          | Finish        | Damper      | Accessory | Accessory<br>- 2 | Accessory | Comments |
|-------|----------|-----------|-------|--------|--------|----------------------|--------------------|---------------|-------------|-----------|------------------|-----------|----------|
| 355FL | 1        | RAG<br>SW | 24    | 12     | NONE   | 1 - SURFACE<br>MOUNT | A - SCREW<br>HOLES | 26 -<br>WHITE | 0 -<br>NONE | NONE      | NONE             | NONE      |          |
| 355FL | I        | RAG<br>SW | 30    | 24     | NONE   | 1 - SURFACE<br>MOUNT | A - SCREW<br>HOLES | 26 -<br>WHITE | 0 -<br>NONE | NONE      | NONE             | NONE      |          |



### Submittal

G-355F


1-1-01

### Louvered Return Grilles and Registers • Aluminum

Models: 

35° Deflection • Long Blades • 1/2" Blade Spacing

□ 355FS • 35° Deflection • Short Blades • 1/2" Blade Spacing




additional cost. Sizes larger than 48" x 48" are shipped in multiple sections with joining strips for field assembly.

Note: Wall or duct opening should be duct size ± 1/8". All dimensions are in inches.

### **Fastenings**



### **Mounting Frames**



### Accessories (Optional) Check ☐ if provided

- Neck mounted opposed blade damper (galvanized steel)
- IS Insect Screen (¹/₁₀" square mesh galvanized steel)
- galvanized steel) EQT • Earthquake tabs

DS • Debris Screen (1/4" square mesh -

### Standard Finish: #26 White

Optional finish


### General Description


- · Available with louvers vertical or horizontal.
- · Optional opposed blade damper has screwdriver adjustment accessible through face of register.
- · Insect and debris screens are not available when dampers are fitted.
- Material: Aluminum.


- #8 x 11/4" Ig. Phillips flat head sheet metal screws painted white.
- All dimensions are ± 1/16".


G-17.0-S

### **Optional Border Types Available**









### Border Type 2, 3, 4

### • Accessories & Options Check ☐ if provided

AG-15 • Neck mounted opposed blade damper (galvanized steel)

IS • Insect Screen (1/16" square mesh – galvanized steel)

DS • Debris Screen (1/4" square mesh – galvanized steel)

☐ EQT • Earthquake tabs

Other \_

### **Border Type 7**

· Accessories & Options

Check if provided

☐ EQT • Earthquake tabs

Other \_\_\_\_

### Standard Finish: #26 White

Optional finish \_\_\_\_\_

### Standard Finish: #26 White

Optional finish \_\_\_\_\_





| Model     | Quantity | Tag       | Length | Slots/Width | End<br>Border/Module<br>Width/Angle | Border                     | Finish        | Fastening/Throw | Damper/Miter<br>Type | Accessory<br>1 | Accessory<br>2 | Accessory<br>3 | Comments |
|-----------|----------|-----------|--------|-------------|-------------------------------------|----------------------------|---------------|-----------------|----------------------|----------------|----------------|----------------|----------|
| ML-<br>39 | 4        | LSD-<br>1 | 96     | 2 SLOTS     | XX - TWO<br>END<br>BORDERS          | 2A -<br>CONCEALED<br>MOUNT | 26 -<br>WHITE |                 |                      | NONE           | NONE           | NONE           |          |



# Submittal

D-ML-1.0 6-08-12

- ☐ ML-37
- 1/2" Slot
- Supply

- □ ML-38
- Supply

- Supply

- □ ML-40

- ☐ MLR-37 ☐ MLR-38
- 1/2" Slot
- Return

- 3/4" Slot

- 3/4" Slot
- Return


- **⊠ ML-39**
- 1" Slot


- ☐ MLR-39
- 1" Slot
- Return


- 1-1/2" Slot
  - Supply


- ☐ MLR-40
- 1-1/2" Slot
- Return

### Linear Slot Ceiling Diffusers Aluminum • Modulinear












☑ Border Type 2A




Dimensions are in inches.


### Frame & Border Types, Dimensions (cont'd) Check 🗹 if provided.








- Frame & Border Type 7A
  Frame & Border Type 7B
  both with
  - · Plaster & Tile Mounting Frame
  - Flange Border
  - · Concealed Mounting




| Туре | А     | 0'       |
|------|-------|----------|
| 7A   | 1 1/8 | D' + 3/4 |
| 7B   | 7/8   | D' + 1/4 |


- Border Type 9A
  Border Type 9B
  both with
  - Flange BorderCeiling Hangers




| 1 |          |                                      |                        |
|---|----------|--------------------------------------|------------------------|
|   | Туре     | Α                                    | 0'                     |
|   | 9A<br>9B | <sup>3</sup> / <sub>4</sub><br>1 1/8 | D' + 5/8<br>D' + 1 3/8 |


- Border Type 11 with
  - Perimeter Plaster & Tile Mounting Frame
  - Flush Border
  - Concealed Mounting







- Border Type 15 with
  - Flush Border
  - Ceiling Hangers







### **End Fabrication**










Overall Length for Various End Fabrications Frame and/or Border Type X-Z X-X X-Y Z-Z C 0 1A, 1B, 9B D -1 3/8 D +3/4 D -11/16 D +3/8 D +7/16 D-5/8 D+1/16 D+1/16 D +1/8 D +1/8 D -5/8 2A, 4, 7A, 16 D -1 3/8 D +3/4 D -11/16 D +3/8 D +7/16 D D+1/16 D+1/16 D +1/8 D +1/8 3, 6, 11 D -1 3/8 D-11/16 D -5/8 D +1/16 D D D D+1/16 D +1/16 D+1/8 D + 1/82B, 7B D -1 3/8 D + 1/4D-11/16 D +1/8 D 518 D +3/16 D D D+1/16 D 71/16 D +1/8 D +1/8 9A D-13/8 D D-11/16 D-5/8 D +1/16 D D D +1/16 D +1/8 D +1/16 B ±1/8 12, 15 D D -5/16 D -11/16 D D-1/4 D +1/16 D D D +1/16 D +1/16 D +1/8 D +1/8 D -1 3/16 D +1 1/16 D 19/32 D +17/32 N/A N/A

**Duct Dimensions D' (Width) for Various Frame & Border Types** 

| •      |         | Types   | 1A, 1B |           | Types 2A, 2B, 4, 7A, 7B, 16 |         |        |           |  |
|--------|---------|---------|--------|-----------|-----------------------------|---------|--------|-----------|--|
| No. of | ML/MLR  | ML/MLR  | ML/MLR | ML/MLR    | ML/MLR                      | ML/MLR  | ML/MLR | ML/MLR    |  |
| Slots  | 37      | 38      | 39     | 40        | 37                          | 38      | 39     | 40        |  |
|        | S = 1/2 | S = 3/4 | S = 1  | S = 1 1/2 | S = 1/2                     | S = 3/4 | S = 1  | S = 1 1/2 |  |
| 1      | 1 7/8   | 2 1/8   | 2 3/8  | 2 7/8     | 2                           | 2 1/4   | 2 1/2  | 1         |  |
| . 2    | 3 1/8   | 3 5/8   | 4 178  | 5 1/8     | 3 1/4                       | 3 3/4   | 4 1/4  | 5 1/4     |  |
| 3      | 4 3/8   | 5 1/8   | 5 7/8  | 7 3/8     | 4 1/2                       | 5 1/4   | 6      | 7 1/2     |  |
| 4      | 5 5/8   | 6 5/8   | 7 5/8  | 9 578     | 5 3/4                       | 6 3/4   | 7 3/4  | 9/3/4     |  |
| 5      | 6 7/8   | 8 1/8   | 9 3/8  | N/A       | X                           | 8 1/4   | 9 1/2  | N/A       |  |
| 6      | 8 1/8   | 9 5/8   | 11 1/8 | N/A       | 8 174                       | 9 3/4   | 11 1/4 | N/A       |  |
| 7      | 9 3/9   | 11 1/8  | 12 7/8 | N/A       | 9 1/2                       | 1/4     | 13     | N/A       |  |
| 8      | 10 5/8  | 12 5/8  | 14 5/8 | N/A       | 10 3/4                      | 12 3/4  | 14 3/4 | N/A       |  |

|        |         | Types   | 3, 6, 11 |           | Types 9A, 9B, 12, 15, 22 |         |        |           |  |  |
|--------|---------|---------|----------|-----------|--------------------------|---------|--------|-----------|--|--|
| No. of | MEMBER  | ML/MLR  | ML/MLR   | ML/MLR    | ML/MLR                   | ML/MLR  | MLANER | ML/MLR    |  |  |
| Slots  | 37      | 38      | 39       | 40        | 37                       | 38      | 39     | 40        |  |  |
|        | S = 1/2 | S = 3/4 | S = 1    | S = 1 1/2 | S = 1/2                  | 8 = 3/4 | S = 1  | S = 1 1/2 |  |  |
| 1      | 2 1/8   | 2 3/8   | 2 5/8    | 3 1/8     | 1 3/8                    | 1 5/8   | 1 7/8  | 2 3/8     |  |  |
| 2      | 3 3/8   | 3 7/8   | 4 3/8    | 5 3/8     | 2 5/8                    | 3 1/8   | 3 5/8  | 4 5/8     |  |  |
| 3      | 4 5/8   | 5 3/8   | 6 1/8    | 7 5/8     | 3 7/8                    | 4 5/8   | 5 3/8  | 6 7/8     |  |  |
| 4      | 5 7/8   | 6 7/8   | 7/8      | 9 7/8     | 5 1/8                    | 6 1/8   | 7 1/8  | 9 1/8     |  |  |
| 5      | 7 1/8   | 8 318   | 9 5/8    | N/A       | 6 3/8                    | 7 5/8   | 8 7/8  | N/A       |  |  |
| 6      | 8 3/8   | 9 7/8   | 11 3/8   | N/A       | 7 5/8                    | 9 1/8   | 10 5/8 | N/A       |  |  |
| 7      | 9 5/8   | 11 3/8  | 13 1/8   | N/A       | 8 7/8                    | 10 5/8  | 12 3/8 | N/A       |  |  |
| 8      | 10 7/8  | 12 7/8  | 14 7/8   | N/A       | 10 1/8                   | 12 1/8  | 14 1/8 | MA        |  |  |

= Not Available in Type 22



This submittal is meant to demonstrate general dimensions of this product. The drawings are not meant to detail every aspect of the product. Drawings are not to scale. Titus reserves the right to make changes without written notice.

longer than 36".

size determined by the factory.



| Model      | Quantity | Tag          | Length       | Slots                             | Width/Throw | Plenum<br>Inlet | Module | Border                     | Finish | Damper      | Accessory 1 /<br>Configuration | Accessory<br>2 | Accessory<br>3 | Comments |
|------------|----------|--------------|--------------|-----------------------------------|-------------|-----------------|--------|----------------------------|--------|-------------|--------------------------------|----------------|----------------|----------|
| MPI-<br>39 | 8        | LSD-<br>1 PL | 48<br>INCHES | 2LP - 2<br>SLOT<br>LOW<br>PROFILE |             | 8<br>INCH       |        | 2A -<br>CONCEALED<br>MOUNT |        | 0 -<br>NONE | XX - TWO<br>END<br>BORDERS     | STRAIGHT       |                |          |
| MPI-<br>39 | 8        | LRD-<br>1 PL | 48<br>INCHES | 2LP - 2<br>SLOT<br>LOW<br>PROFILE |             | 8<br>INCH       |        | 2A -<br>CONCEALED<br>MOUNT |        | 0 -<br>NONE | XX - TWO<br>END<br>BORDERS     | STRAIGHT       |                |          |

MPI-40



# Submittal

MP 1.0


8-30-13


### Modulinear Plenum Adapters for ML Modulinear Diffusers

Models: MP-37 • 1/2" Slot

MP-38 • 3/4" Slot • 1" Slot MP-39 MP-40 • 11/2" Slot MPI-37 • 1/2" Slot • Insulated

**MPI-38** • 3/4" Slot • Insulated **→**MPI-39 • 1" Slot • Insulated • 11/2" Slot • Insulated







| 1 | ML/MLR |                 |         |         | V       | Vidth   |         |         |          |
|---|--------|-----------------|---------|---------|---------|---------|---------|---------|----------|
|   | Туре   | Number of Slots |         |         |         |         |         |         |          |
|   | Type   | 1               | 2       | 3       | 4       | 5       | 6       | 7       | 8        |
|   | MP-37  | 2 3/16          | 3 7/16  | 4 11/16 | 5 15/16 | 7 3/16  | 8 7/16  | 9 11/16 | 10 15/16 |
|   | MP-38  | 2 7/16          | 3 15/16 | 5 7/16  | 6 15/16 | 8 7/16  | 9 15/16 | 11 7/16 | 12 15/16 |
|   | MP-39  | 2 11/16         | 4 7/16  | 6 3/16  | 7 15/16 | 9 11/16 | 11 7/16 | 13 3/16 | 14 15/16 |
|   | MP-40  | 3 3/16          | 5 7/16  | 7 11/16 | 9 15/16 | N/A     | N/A     | N/A     | N/A      |


| ML/MLR<br>End<br>Fabrication | L     |
|------------------------------|-------|
| XX                           | N-7/8 |
| XY                           | N-7/8 |
| YY                           | N-1/4 |
| ZZ                           | N-1/4 |


| Н     | LP | HP |
|-------|----|----|
| (in.) | 8  | 11 |



### **Installation Details**








### Accessories (optional)

# Internal Insulation MPI-37 • For ML/MLR-37 • ½" Slot MPI-38 • For ML/MLR-38 • ¾" Slot MPI-39 • For ML/MLR-39 • 1" Slot MPI-40 • For ML/MLR-40 • 1½" Slot



### **General Description**

- Model MP modulinear plenums are tailored for field attachment to ML or MLR modulinear diffusers.
- Can be selected to integrate with all ML or MLR frame and border types.
- Standard lengths are 2', 3', 4', 5' and 6'.
- End caps can be turned up to allow installing the MP on continuous runs of ML diffuser.
- Available with optional internal insulation, Model MPI.
- Model MP can be used as supply or return.
- Available to fit ML or MLR 1-8 slot units.
- Material is steel.



| Model      | Quantity | Tag       | Length | Slots/Width | End<br>Border/Module<br>Width/Angle | Border                     | Finish        | Fastening/Throw | Damper/Miter<br>Type | Accessory<br>1 | Accessory<br>2 | Accessory<br>3 | Comments |
|------------|----------|-----------|--------|-------------|-------------------------------------|----------------------------|---------------|-----------------|----------------------|----------------|----------------|----------------|----------|
| MLR-<br>39 | 4        | LRD-<br>1 | 96     | 2 SLOTS     | XX - TWO<br>END<br>BORDERS          | 2A -<br>CONCEALED<br>MOUNT | 26 -<br>WHITE |                 |                      | NONE           | NONE           | NONE           |          |



# Submittal

D-ML-1.0 6-08-12

- ☐ ML-37
- 1/2" Slot
- Supply

- □ ML-38
- 3/4" Slot

- □ ML-39
- 1" Slot
- Supply

- □ ML-40
- 1-1/2" Slot
- Supply

- ☐ MLR-37
- 1/2" Slot
- Return


- Supply


- ☐ MLR-38
- 3/4" Slot
- Return


- **⊠ MLR-39**
- 1" Slot
- Return


- ☐ MLR-40
  - 1-1/2" Slot
- Return

### Linear Slot Ceiling Diffusers Aluminum • Modulinear












□ Border Type 2A





Dimensions are in inches.


### Frame & Border Types, Dimensions (cont'd) Check 🗹 if provided.



























### **End Fabrication**










Overall Length for Various End Fabrications Z Frame and/or Border Type X-X X-Y X-Z Z-Z 0 C 0 1A, 1B, 9B D -1 3/8 D +3/4 D -11/16 D +7/16 D +3/8 D-5/8 D+1/16 D+1/16 D +1/8 D +1/8 2A, 4, 7A, 10 D -1 3/8 D +3/4 D -11/16 D + 3/8D -5/8 D +7/16 D D+1/16 D+1/16 D + 1/8D + 1/83, 6, 11 D -1 3/8 D D-11/16 D D-5/8 D +1/16 D D D+1716 D +1/16 D +1/8 D +1/8 2B, 7B D -1 3/8 D +1/4 D-11/16 D+1/8 D 5/8 D +3/16 D D +1/16 D D +1/16 D +1/8 D +1/8 9A D -1 3/8 D-11/16 D-5/8 D+1/16 D D D +1/16 D+1/16 D+1/8 D +1/8 12, 15 D-11/16 D D -5/16 D-1/4 D +1/16 D D D D +1/16 D +1/16 D +1/8 D +1/8 D -1 3/16 D +1 1/16 D 19/32 D +17/32 N/A N/A N/A N/A NA

Duct Dimensions D' (Width) for Various Frame & Border Types

|   |        |         |     |                |       |        | _   |                     |  |         |     |         |     |       |     |       |      |      |
|---|--------|---------|-----|----------------|-------|--------|-----|---------------------|--|---------|-----|---------|-----|-------|-----|-------|------|------|
| - |        |         |     | Ī              | Гуреѕ | 1A, 1E | 3   |                     | Types 2A, <del>2B, 4, 7A, 7B, 18</del> |         |     |         |     |       |     |       |      |      |
|   | No. of | MU      | MLR | R ML/MLR<br>38 |       | ML/MLR |     | ML/I                | MLR                                    | ML/MLR  | ML/ | MLR     | ML/ | MLR   | ML/ | MLR   | ML/I | MLR/ |
|   | Slots  | 3       | 7   |                |       | 39     |     | 40                  | 3                                      | 37      |     | 38      |     | 39    |     | 0     |      |      |
|   |        | S = 1/2 |     | 5 = 3/4        |       | S = 1  |     | $S = 1 \frac{1}{2}$ | S=                                     | S = 1/2 |     | S = 3/4 |     | S = 1 |     | 1 1/2 |      |      |
|   | 1      | 1       | 7/8 | 2              | 1/8   | 2      | 3/8 | 2 7/8               | 2                                      |         | 2   | 1/4     | 2   | 1/2   | 8   |       |      |      |
| > | 2      | 3       | 1/8 | 3              | 5/8   | 4      | 1/8 | 5 1/8               | 3                                      | 1/4     | 3   | 3/4     | 4   | 1/4   | 5   | 1/4   |      |      |
|   | 3      | 4       | 3/8 | 5              | 1/8   | 5      | 7/8 | 7 3/8               | 4                                      | 1/2     | 5   | 1/4     | 6   |       | 7   | 1/2   |      |      |
|   | 4      | 5       | 5/8 | 6              | 5/8   | 7      | 5/8 | 9 5/8               | 5                                      | 3/4     | 6   | 3/4     | 7   | 3/4   | 9   | 8/4   |      |      |
|   | 5      | 6       | 7/8 | 8              | 1/8   | 9      | 3/8 | N/A                 | 7                                      |         | 8   | 1/4     | 9   | 1/2   | N   | /A    |      |      |
|   | 6      | 8       | 1/8 | 9              | 5/8   | 11     | 1/8 | N/A                 | 8                                      | 14      | 9   | 3/4     | 11  | 1/4   | / N | /A    |      |      |
|   | 7      | 9       | 3/8 | 11             | 1/8   | 12     | 7/8 | N/A                 | 9                                      | 1/2     | 41  | 1/4     | 13  |       | N   | /A    |      |      |
|   | 8      | 10      | 5/8 | 12             | 5/8   | 14     | 5/8 | N/A                 | 10                                     | 3/4     | 12  | 3/4     | 14  | 3/4   | / N | /A    |      |      |

|        |         | 1 100 100 10000 |          |           |                          |         |        |           |  |  |  |
|--------|---------|-----------------|----------|-----------|--------------------------|---------|--------|-----------|--|--|--|
|        |         | Types           | 3, 6, 11 |           | Types 9A, 9B, 12, 15, 22 |         |        |           |  |  |  |
| No. of | MEMALR  | ML/MLR          | ML/MLR   | ML/MLR    | ML/MLR                   | ML/MLR  | ML/MLR | ML/MLR    |  |  |  |
| Slots  | 37      | 38              | 39       | 40        | 37                       | 38      | 39     | 40        |  |  |  |
|        | S = 1/2 | S = 3/4         | S = 1    | S = 1 1/2 | S = 1/2                  | 8 = 3/4 | S = 1  | S = 1 1/2 |  |  |  |
| 1      | 2 1/8   | 2 3/8           | 2 5/8    | 3 1/8     | 1 378                    | 1 5/8   | 1 7/8  | 2 3/8     |  |  |  |
| 2      | 3 3/8   | 3 7/8           | 4 3/8    | 5 3/8     | 2 5/8                    | 3 1/8   | 3 5/8  | 4 5/8     |  |  |  |
| 3      | 4 5/8   | 5 3/8           | 6 1/8    | 5/8       | 3 7/8                    | 4 5/8   | 5 3/8  | 6 7/8     |  |  |  |
| 4      | 5 7/8   | 6 7/8           | 7 118    | 9 7/8     | 5 1/8                    | 6 1/8   | 7 1/8  | 9 1/8     |  |  |  |
| 5      | 7 1/8   | 8 3/8           | 9 5/8    | N/A       | 6 3/8                    | 7 5/8   | 8 7/8  | N/A       |  |  |  |
| 6      | 8 3/8   | 9 7/8           | 11 3/8   | N/A       | 7 5/8                    | 9 1/8   | 10 5/8 | N/A       |  |  |  |
| 7      | 9 5/8   | 11 3/8          | 13 1/8   | N/A       | 8 7/8                    | 10 5/8  | 12 3/8 | N/A       |  |  |  |
| 8      | 10 7/8  | 12 =7/8         | 14 7/8   | N/A       | 10 1/8                   | 12 1/8  | 14 1/8 | N         |  |  |  |

= Not Available in Type 22



This submittal is meant to demonstrate general dimensions of this product. The drawings are not meant to detail every aspect of the product. Drawings are not to scale. Titus reserves the right to make changes without written notice.

longer than 36".

size determined by the factory.



December 2, 2016

# Submittal Data

Project Name:

Home 2 Suites – Flowood, MS

Contractor:

Comfort Designs

Submitted By:

Trent Dismuke

Airflo Sales Inc.

103 First Choice Drive Madison, MS 39110 601-898-1017 Phone 601-898-1018 Fax

Items Submitted: Ruskin Wind Driven Rain Louvers

Approved By:

Date of Approval:

# Schedule



Job: Home2Suites Flowood

| Model    | Quantity | Tag | WIDTH | HEIGHT | SIZE          | FRAME | SCREEN1                  | SCREEN1<br>MTG | INSTALL.<br>ANGL | FINISH<br>TYPE      | FINISH<br>COLOR     | CONSTRUCTION | WINDLOAD | Comments |
|----------|----------|-----|-------|--------|---------------|-------|--------------------------|----------------|------------------|---------------------|---------------------|--------------|----------|----------|
| EME220DD | 4        | L   | 20    | 12     | Deduct<br>1/4 | ВОХ   | 5/8<br>Inch .040<br>ALUM | REAR           | NONE             | 50%<br>PVDF<br>(B1) | TO<br>MATCH<br>(98) | STANDARD     | 20       |          |
| EME220DD | 1        | L   | 20    | 14     | Deduct<br>1/4 | BOX   | 5/8<br>Inch .040<br>ALUM | REAR           | NONE             | 50%<br>PVDF<br>(B1) | TO<br>MATCH<br>(98) | STANDARD     | 20       |          |
| EME220DD | 2        | L   | 48    | 48     | Deduct<br>1/4 | BOX   | 5/8<br>Inch .040<br>ALUM | REAR           | NONE             | 50%<br>PVDF<br>(B1) | TO<br>MATCH<br>(98) | STANDARD     | 20       |          |
| EME220DD | 1        | L   | 18    | 14     | Deduct<br>1/4 | вох   | 5/8<br>Inch .040<br>ALUM | REAR           | NONE             | 50%<br>PVDF<br>(B1) | TO<br>MATCH<br>(98) | STANDARD     | 20       |          |
| EME220DD | 3        | L   | 14    | 14     | Deduct<br>1/4 | BOX   | 5/8<br>Inch .040<br>ALUM | REAR           | NONE             | 50%<br>PVDF<br>(B1) | TO<br>MATCH<br>(98) | STANDARD     | 20       |          |

3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

# EME220DD WIND-DRIVEN RAIN RESISTANT STATIONARY LOUVER

### **EXTRUDED ALUMINUM**

### STANDARD CONSTRUCTION

### FRAME

2" (51) deep, 6063T6 extruded aluminum with .060" (1.5) nominal wall thickness.

6063T6 extruded aluminum .045" (1.1) nominal wall thickness. Double drainable blades are sightproof.

### **SCREEN**

5/8" x .040" (16 x 1) expanded flattened aluminum bird screen in removable frame. Screen adds approximately 1/2" (13) to louver depth.

### FINISH

Mill.

### MINIMUM SIZE

6"w x 6"h (152 x 152).

## APPROXIMATE SHIPPING WEIGHT

4 lbs. per sq. ft. (19.4 kg/m²)

### MAXIMUM FACTORY ASSEMBLY SIZE

Single sections shall not exceed 120" x 90"h (3048 x 2286) or 90"w x 120"h (2286 x

Louvers larger than the maximum single section size will require field assembly of smaller sections.

### SUPPORTS


Louvers may be provided with rear mounted blade supports that increase overall louver depth depending on louver size, assembly configuration or windload.

Consult Ruskin for additional information.

Please reference our website www.ruskin.com for up to date LEED® information

### NOTES:

- 1. Dimensions in inches, parenthesis ( indicate millimeters.
- 2. Units furnished 1/4" (6) smaller than given opening dimensions.



# "B"

### **FEATURES**

- · Closely spaced horizontal blades minimize the penetration of wind-driven rain, reducing damage and additional operating expenses.
- Tested in the AMCA 500-L Wind-Driven Rain Penetration Test.
- Published performance ratings based on testing in accordance with AMCA Publication 511.
- · 43% Free Area.
- · Excellent pressure drop performance.
- · Aluminum construction for low maintenance and high resistance to corrosion.


### **VARIATIONS**

- · Extended sill.
- · Hinged frame.
- · Front or rear security bars.
- · Filter racks.
- · Installation angles.
- · A variety of bird and insect screens.

### Finishes:

- · Prime coat.
- · Baked enamel (modified fluoropolymer).
- Epoxy
- · Pearledize 50 & 70.
- · Kynar.
- · Clear and color anodize.
- · Triangular and round shapes available.

Consult Ruskin for other special requirements.



| TAG | QTY. | SIZ     | E.      | FRAME | VARIATIONS |
|-----|------|---------|---------|-------|------------|
|     |      | A*-WIDE | B*-HIGH |       |            |
|     | 4    | 20      | 12      | вох   |            |
|     | 1    | 20      | 14      | вох   |            |
|     | 2    | 48      | 48      | BOX   |            |
|     | 1    | 18      | 14      | вох   |            |
|     | 3    | 14      | 14      | вох   |            |
|     |      |         |         |       |            |

PROJECT HOME 2 SUITES

ARCH./ENGR. RICHARD MOLENAAR ARCHITECT/IES


REPRESENTATIVE

LOCATION FLOWOOD, MS

**CONTRACTOR** COMFORT DESIGNS

DATE 12/1/2016

Test size 48" x 48" (1219 x 1219)
Beginning point of water penetration at .01 oz./sq. ft. is 680 fpm (208 m/min.)






Ruskin Company certifies that the louver shown herein is licensed to bear the AMCA Seal. The ratings shown are based on tests and procedures performed in accordance with AMCA Publication 511 and comply with the requirements of the AMCA Certified Ratings Program. The AMCA Certified Ratings Seal applies to air performance ratings, water penetration ratings and wind driven rain ratings only.

### PRESSURE DROP

Pressure Drop testing performed on 48" x 48" (1219 x 1219) unit.



Ratings do not include the effect of a bird screen.

Air Velocity in feet (meters) per minute through Free Area

# **FREE AREA GUIDE**

### Free Area Guide shows free area in ft2 and m2 for various sizes of EME220DD. Width - Inches and Meters

| - 1     |                   | 6    | 12   | 18           | 24           | 30           | 36           | 42           | 48            | 54    | 60    | 66    | 72            | 78            | 84            | 90    | 96    | 102   | 108           | 114   | 120   |
|---------|-------------------|------|------|--------------|--------------|--------------|--------------|--------------|---------------|-------|-------|-------|---------------|---------------|---------------|-------|-------|-------|---------------|-------|-------|
|         |                   | 0.15 | 0.30 | 0.46         | 0.61         | 0.76         | 0.91         | 1.07         | 1.22          | 1.37  | 1.52  | 1.68  | 1.83          | 1.98          | 2.13          | 2.29  | 2.44  | 2.59  | 2.74          | 2.90  | 3.05  |
| Γ       | 6                 | 0.04 | 0.11 | 0.18         | 0.25         | 0.32         | 0.39         | 0.46         | 0.53          | 0.60  | 0.67  | 0.74  | 0.82          | 0.89          | 0.96          | 1.03  | 1.10  | 1.17  | 1.24          | 1.31  | 1.38  |
|         | 0.15              | 0.00 | 0.01 | 0.02         | 0.02         | 0.03         | 0.04         | 0.04         | 0.05          | 0.06  | 0.06  | 0.07  | 0.08          | 0.08          | 0.09          | 0.10  | 0.10  | 0.11  | 0.12          | 0.12  | 0.13  |
|         | 12                | 0.10 | 0.28 | 0.46         | 0.64         | 0.82         | 1.00         | 1.18         | 1.36          | 1.54  | 1.72  | 1.90  | 2.08          | 2.26          | 2.44          | 2.62  | 2.80  | 2.98  | 3.16          | 3.34  | 3.52  |
| L       | 0.30              | 0.01 | 0.03 | 0.04         | 0.06         | 0.08         | 0.09         | 0.11         | 0.13          | 0.14  | 0.16  | 0.18  | 0.19          | 0.21          | 0.23          | 0.24  | 0.26  | 0.28  | 0.29          | 0.31  | 0.33  |
|         | 18                | 0.17 | 0.48 | 0.78         | 1.09         | 1.40         | 1.71         | 2.01         | 2.32          | 2.63  | 2.94  | 3.24  | 3.55          | 3.86          | 4.17          | 4.47  | 4.78  | 5.09  | 5.40          | 5.70  | 6.01  |
| L       | 0.46              | 0.02 | 0.04 | 0.07         | 0.10         | 0.13         | 0.16         | 0.19         | 0.22          | 0.24  | 0.27  | 0.30  | 0.33          | 0.36          | 0.39          | 0.42  | 0.44  | 0.47  | 0.50          | 0.53  | 0.56  |
|         | 24                | 0.24 | 0.67 | 1.11         | 1.54         | 1.98         | 2.41         | 2.85         | 3.28          | 3.72  | 4.15  | 4.59  | 5.02          | 5.45          | 5.89          | 6.32  | 6.76  | 7.19  | 7.63          | 8.06  | 8.50  |
| L       | 0.61              | 0.02 | 0.06 | 0.10         | 0.14         | 0.18         | 0.22         | 0.26         | 0.31          | 0.35  | 0.39  | 0.43  | 0.47          | 0.51          | 0.55          | 0.59  | 0.63  | 0.67  | 0.71          | 0.75  | 0.79  |
|         | 30                | 0.30 | 0.84 | 1.39         | 1.93         | 2.48         | 3.02         | 3.56         | 4.11          | 4.65  | 5.20  | 5.74  | 6.29          | 6.83          | 7.37          | 7.92  | 8.46  | 9.01  | 9.55          | 10.10 | 10.64 |
| L       | 0.76              | 0.03 | 0.08 | 0.13         | 0.18         | 0.23         | 0.28         | 0.33         | 0.38          | 0.43  | 0.48  | 0.53  | 0.58          | 0.64          | 0.69          | 0.74  | 0.79  | 0.84  | 0.89          | 0.94  | 0.99  |
| )       | 36                | 0.37 | 1.04 | 1.71         | 2.38         | 3.05         | 3.73         | 4.40         | 5.07          | 5.74  | 6.41  | 7.08  | 7.76          | 8.43          | 9.10          | 9.77  | 10.44 | 11.11 | 11.78         | 12.46 | 13.13 |
| 5 -     | 0.91              | 0.03 | 0.10 | 0.16         | 0.22         | 0.28         | 0.35         | 0.41         | 0.47          | 0.53  | 0.60  | 0.66  | 0.72          | 0.78          | 0.85          | 0.91  | 0.97  | 1.03  | 1.10          | 1.16  | 1.22  |
| 3       | 42                | 0.43 | 1.21 | 1.99         | 2.77         | 3.55         | 4.33         | 5.12         | 5.90          | 6.68  | 7.46  | 8.24  | 9.02          | 9.80          | 10.58         | 11.37 | 12.15 | 12.93 | 13.71         | 14.49 | 15.27 |
| MICICIS | 1.07              | 0.02 | 0.05 | 0.08         | 0.11         | 0.14         | 0.17         | 0.20         | 0.23          | 0.26  | 0.29  | 0.32  | 0.36          | 0.39          | 0.42          | 0.45  | 0.48  | 0.51  | 0.54          | 0.57  | 0.60  |
|         | 48                | 0.50 | 1.41 | 2.31         | 3.22         | 4.13         | 5.04         | 5.95         | 6.86          | 7.77  | 8.67  | 9.58  | 10.49         | 11.40         | 12.31         | 13.22 | 14.12 | 15.03 | 15.94         | 16.85 | 17.76 |
| 2       | 1.22              | 0.05 | 0.13 | 0.22         | 0.30         | 0.38         | 0.47         | 0.55         | 0.64          | 0.72  | 0.81  | 0.89  | 0.98          | 1.06          | 1.14          | 1.23  | 1.31  | 1.40  | 1.48          | 1.57  | 1.65  |
| 3       | 54                | 0.57 | 1.60 | 2.64         | 3.67         | 4.71         | 5.75         | 6.78         | 7.82          | 8.85  | 9.89  | 10.92 | 11.96         | 13.00         | 14.03         | 15.07 | 16.10 | 17.14 | 18.17         | 19.21 | 20.24 |
| 0       | 1.37              | 0.05 | 0.15 | 0.25         | 0.34         | 0.44         | 0.53         | 0.63         | 0.73          | 0.82  | 0.92  | 1.02  | 1.11          | 1.21          | 1.30          | 1.40  | 1.50  | 1.59  | 1.69          | 1.79  | 1.88  |
| )       | 60                | 0.63 | 1.77 | 2.92         | 4.06         | 5.21         | 6.35         | 7.50         | 8.65          | 9.79  | 10.94 | 12.08 | 13.23         | 14.37         | 15.52         | 16.66 | 17.81 | 18.95 | 20.10         | 21.24 | 22.39 |
|         | 1.52              | 0.06 | 0.16 | 0.27         | 0.38         | 0.48         | 0.59         | 0.70         | 0.80          | 0.91  | 1.02  | 1.12  | 1.23          | 1.34          | 1.44          | 1.55  | 1.66  | 1.76  | 1.87          | 1.98  | 2.08  |
| 4       | 66                | 0.70 | 1.97 | 3.24         | 4.52         | 5.79         | 7.06         | 8.33         | 9.61          | 10.88 | 12.15 | 13.42 | 14.70         | 15.97         | 17.24         | 18.51 | 19.79 | 21.06 | 22.33         | 23.60 | 24.88 |
| . +     | 1.68<br><b>72</b> | 0.06 | 0.18 | 0.30<br>3.52 | 0.42<br>4.90 | 0.54<br>6.29 | 0.66         | 0.77         | 0.89          | 1.01  | 1.13  | 1.25  | 1.37          | 1.49          | 1.60          | 1.72  | 1.84  | 1.96  | 2.08          | 2.20  | 2.31  |
| .       | 1.83              | 0.76 | 0.20 | 0.33         | 0.46         | 0.58         | 7.67<br>0.71 | 9.05<br>0.84 | 10.43<br>0.97 | 11.82 | 13.20 | 14.58 | 15.96<br>1.48 | 17.34         | 18.73<br>1.74 | 20.11 | 21.49 | 22.87 | 24.25<br>2.26 | 25.64 | 27.02 |
|         | 78                | 0.83 | 2.34 | 3.85         | 5.36         | 6.87         | 8.37         | 9.88         | 11.39         | 1.10  | 14.41 | 15.92 | 17.43         | 1.61<br>18.94 | 20.45         | 1.87  | 2.00  | 2.13  | 26.49         | 2.38  | 2.51  |
| ח       | 1.98              | 0.03 | 0.22 | 0.36         | 0.50         | 0.64         | 0.78         | 0.92         | 1.06          | 1.20  | 1.34  | 1.48  | 1.62          | 1.76          | 1.90          | 2.04  | 2.18  | 2.32  | 2.46          | 2.60  | 2.74  |
| ا ز     | 84                | 0.90 | 2.53 | 4.17         | 5.81         | 7.44         | 9.08         | 10.72        | 12.35         | 13.99 | 15.63 | 17.26 | 18.90         | 20.54         | 22.17         | 23.81 | 25.45 | 27.08 | 28.72         | 30.36 | 31.99 |
| :       | 2.13              | 0.08 | 0.24 | 0.39         | 0.54         | 0.69         | 0.84         | 1.00         | 1.15          | 1.30  | 1.45  | 1.61  | 1.76          | 1.91          | 2.06          | 2.21  | 2.37  | 2.52  | 2.67          | 2.82  | 2.98  |
| -       | 90                | 0.96 | 2.70 | 4.45         | 6.20         | 7.94         | 9.69         | 11.44        | 13.18         | 14.93 | 16,67 | 18.42 | 20.17         | 21.91         | 23.66         | 25.41 | 27.15 | 28.90 | 30.64         | 32.39 | 34.14 |
|         | 2.29              | 0.09 | 0.25 | 0.41         | 0.58         | 0.74         | 0.90         | 1.06         | 1.23          | 1.39  | 1.55  | 1.71  | 1.88          | 2.04          | 2.20          | 2.36  | 2.53  | 2.69  | 2.85          | 3.01  | 3.17  |
|         | 96                | 1.03 | 2.90 | 4.77         | 6.65         | 8.52         | 10.39        | 12.27        | 14.14         | 16.01 | 17.89 | 19.76 | 21.64         | 23.51         | 25.38         | 27.26 | 29.13 | 31.00 | 32.88         | 34.75 | 36.62 |
|         | 2.44              | 0.10 | 0.27 | 0.44         | 0.62         | 0.79         | 0.97         | 1.14         | 1.32          | 1.49  | 1.66  | 1.84  | 2.01          | 2.19          | 2.36          | 2.53  | 2.71  | 2.88  | 3.06          | 3.23  | 3.41  |
|         | 102               | 1.54 | 3.52 | 5.50         | 7.48         | 9.47         | 11.45        | 13.43        | 15.42         | 17.40 | 19.38 | 21.37 | 23.35         | 25.33         | 27.32         | 29.30 | 31.28 | 33.27 | 35.25         | 37.23 | 39.21 |
| 1       | 2.59              | 0.14 | 0.33 | 0.51         | 0.70         | 0.88         | 1.06         | 1.25         | 1.43          | 1.62  | 1.80  | 1.99  | 2.17          | 2.36          | 2.54          | 2.72  | 2.91  | 3.09  | 3.28          | 3.46  | 3.65  |
|         | 108               | 1.16 | 3.27 | 5.38         | 7.49         | 9.60         | 11.71        | 13.82        | 15.93         | 18.04 | 20.15 | 22.26 | 24.37         | 26.48         | 28.59         | 30.70 | 32.81 | 34.92 | 37.03         | 39.14 | 41.25 |
|         | 2.74              | 0.11 | 0.30 | 0.50         | 0.70         | 0.89         | 1.09         | 1.29         | 1.48          | 1.68  | 1.87  | 2.07  | 2.27          | 2.46          | 2.66          | 2.86  | 3.05  | 3.25  | 3.44          | 3.64  | 3.84  |
|         | 114               | 1.23 | 3.46 | 5.70         | 7.94         | 10.18        | 12.41        | 14.65        | 16.89         | 19.13 | 21.36 | 23.60 | 25.84         | 28.08         | 30.32         | 32.55 | 34.79 | 37.03 | 39.27         | 41.50 | 43.74 |
| 1       | 2.90              | 0.11 | 0.32 | 0.53         | 0.74         | 0.95         | 1.15         | 1.36         | 1.57          | 1.78  | 1.99  | 2.20  | 2.40          | 2.61          | 2.82          | 3.03  | 3.24  | 3.44  | 3.65          | 3.86  | 4.07  |
|         | 120               | 1.29 | 3.63 | 5.98         | 8.33         | 10.68        | 13.02        | 15.37        | 17.72         | 20.06 | 22.41 | 24.76 | 27.11         | 29.45         | 31.80         | 34.15 | 36.50 | 38.84 | 41.19         | 43.54 | 45.88 |
| - 1     | 3.05              | 0.12 | 0.34 | 0.56         | 0.77         | 0.99         | 1.21         | 1.43         | 1.65          | 1.87  | 2.08  | 2.30  | 2.52          | 2.74          | 2.96          | 3.18  | 3.39  | 3.61  | 3.83          | 4.05  | 4.27  |

# WIND-DRIVEN RAIN PERFORMANCE

Test size is 1m x 1m (39" x 39") core area, 1.04m x 1.12m (41" x 44") nominal. Free Area of test louver is 4.20 ft² (.39m²).

29 mph (75 mm/h) wind & 3" (76) per hour rain conditions

| Core<br>Velocity <sub>1</sub><br>fpm (m/s) | Airflow cfm<br>(m³/min) | Free Area<br>Velocity <sub>2</sub><br>fpm (m/sec.) | Effectiveness<br>Ratio | Class |
|--|-------------------------|--|------------------------|-------|
| 0  | 0                       | 0  | 99.9                   | А     |
| 132 (.7)                                   | 1421                    | 383  | 99.9                   | Α     |
| 197 (1.0)                                  | 2120                    | 505  | 99.9                   | Α     |
| 285 (1.4)                                  | 3068                    | 730  | 99.9                   | Α     |
| 374 (1.9)                                  | 4031                    | 960  | 99.9                   | Α     |
| 472 (2.4)                                  | 5077                    | 1209   | 99.3                   | Α     |
| 583 (3.0)                                  | 6277                    | 1495   | 97.1                   | В     |
| 685 (3.5)                                  | 7373                    | 1755   | 96.1                   | В     |

### NOTES

- Core area is the open area of the louver face (face area less lover frames). Core Velocity is the airflow velocity through the Core Area of the louver (1m x 1m).
- 2. Free Area of test size is calculated per AMCA standard 500-L.
- 3. Wind Driven Rain Penetration Classes:

| Class | Effectiveness |
|-------|---------------|
| Α     | 1 to .99      |
| В     | 0.989 to 0.95 |
| C     | 0.949 to 0.80 |
| D     | Below 0.8     |

4. Intake Discharge Loss Class 2

Discharge Loss Coefficient is calculated by dividing a louvers' actual airflow rate vs. a theoretical airflow for the opening. It provides an indication of the louvers' airflow characteristics.

50 mph (202 mm/h) wind & 8" (203) per hour rain conditions

| Core<br>Velocity <sub>1</sub><br>fpm (m/s) | Airflow cfm<br>(m³/min) | Free Area<br>Velocity <sub>2</sub><br>fpm (m/sec.) | Effectiveness<br>Ratio | Class |
|--|-------------------------|--|------------------------|-------|
| 0  | 0                       | 0  | 99.9                   | Α     |
| 114 (.6)                                   | 1228                    | 292  | 99.8                   | Α     |
| 186 (.9)                                   | 2001                    | 476  | 99.4                   | Α     |
| 294 (1.5)                                  | 3181                    | 757  | 99.3                   | Α     |
| 398 (2.0)                                  | 4285                    | 1020   | 97.8                   | В     |
| 494 (2.5)                                  | 5315                    | 1265   | 96.2                   | В     |
| 568 (2.9)                                  | 6114                    | 1456   | 95.4                   | В     |
| 691 (3.5)                                  | 7442                    | 1772   | 90.9                   | С     |

Discharge Loss Classes:

| Class | Discharge | Loss | Coefficient |
|-------|-----------|------|-------------|
| Class | Discharge | LOSS | Coemicien   |


1 0.4 and above 2 0.3 to 0.399

3 0.2 to 0.299

4 0.199 and below

(The higher the coefficient, the less resistance to airflow.)

5. The AMCA Wind Driven Rain Test is performed in a laboratory environment and incorporates controlled wind, water and system airflow effects. In actual field installations, storms may create conditions not considered by the AMCA test. Penthouse and similar applications where wind can pass through multiple louvers in an enclosure is another condition that is not simulated by AMCA tests. These applications can create elevated water penetration rates through any louver. Because of these uncontrolled situations, it is recommended that provisions to manage water penetration through louvers be included in the building design.



- Reference separate Installation Instruction sheets for installation details. It is the responsibility of the installing contractor to properly install the louvers per the appropriate detail.
- Louvers wider than the maximum single section width will be shipped in multiple sections and will require field assembly. Field assembly is not by Ruskin.



# Schedule



Job: Home2Suites Flowood

| Model | Quantity | Tag | WIDTH | HEIGHT | SIZE          | FRAME   | BLADE<br>ACTION | OPER.SHAFT | ACT TYPE             | FAIL<br>POS. | INSTALLATION | SIDE<br>PLATE | ACCESSORIES | Slv/Tran | Comments |
|-------|----------|-----|-------|--------|---------------|---------|-----------------|------------|----------------------|--------------|--------------|---------------|-------------|----------|----------|
| CD36  | 2        | MOD | 36    | 36     | Deduct<br>1/4 | CHANNEL | OPPOSED         | EXTENDED   | ELECTRIC/120<br>VOLT | CLOSE        | OUT          | YES           | NONE        | None     |          |
| CD36  | 2        | MOD | 48    | 48     | Deduct<br>1/4 | CHANNEL | OPPOSED         | EXTENDED   | ELECTRIC/120<br>VOLT | CLOSE        | OUT          | YES           | NONE        | None     | 5        |



3900 Dr. Greaves Rd.

Kansas City, MO 64030

(816) 761-7476

FAX (816) 765-8955

# CD36 LOW LEAKAGE CONTROL DAMPER

### **APPLICATION**

Ruskin model CD36 incorporates the industries only one-piece steel frame construction, making it the engineer's preferred frame design. It promotes tighter leakage, and there are no bolts, screws or rivets that could fail over time. Frame corners are internally braced to reduce racking. V-groove blades are suitable for low and medium velocity applications. Blade edge seals are mechanically fastened to ensure years of dependable low leakage performance. Factory mounted and commissioned pneumatic and electric actuators are available options.

### STANDARD CONSTRUCTION

### FRAME

 $5"\ x\ 1"\ x\ 16$  gage (127mm x 25mm x 1.6mm) hot dipped, roll formed galvanized steel.

### BLADE

 $6\mbox{\ensuremath{^{"}}}\xspace$  x 1.6 gage (152mm x 1.6mm) hot dipped, roll formed galvanized steel.

### **AXLES**

1/2" (13mm) nominal hexagonal zinc plated steel.

### **BEARINGS**

High impact, molded synthetic, formed to hexagonal axle shape.

### **BLADE SEALS**

Mechanically fastened, fire resistant, vinyl coated polyester. Meets requirements to qualify for UL94, 5903.

### JAMB SEALS

300 series stainless steel compression type.

### LINKAGE

Shake proof Swedgelock  $\mbox{\scriptsize TM}$  plated steel assembly, concealed out of airstream.

### **PRESSURE**

Up to 5" W.C. (1.2 kPa). Refer to chart.

### VELOCITY

Up to 3,000 FPM (15.3 m/s). Refer to chart.

### **LEAKAGE**

Superior to AMCA Class 2. Refer to chart.

### **TEMPERATURE RANGE**

Standard -25°F to +185°F (-32°C to +85°C). Enhanced -45°F to +350°F (-43°C to +177°C).

With silicone blade seals and stainless bearings, see variations.

### MINIMUM SIZE


Single blade – 5" (127mm) "A" width x 5" (127mm) "B" height. Opposed blade – 5" (127mm) "A" width x 10" (254) "B" height.

### ASIS MUMIXAM

Single section - 48" (1219mm) "A" width x 72" (1829mm) "B" height. Multi-section - multiple factory assembled equal sections with unlimited overall dimensions.

### **ESTIMATED SHIPPING WEIGHT**

7 lbs. (3.2kg) per square foot.



ISO9001


### **FEATURES**

- · One-piece roll formed frame
- Swedgelock™ shake proof concealed linkage
- · Mechanically fastened blade seals

### **VARIATIONS**

Ruskin model CD36 is available with the following variations at additional cost.

- · Front, rear or double flange frame
- · Stainless axles, bearings and linkage
- · Factory mounted sleeves with round and oval transitions
- Security bars
- Factory mounted and commissioned electric and pneumatic actuators, chain pull devices, and manual locking handles
- Enamel and epoxy finishes
- Remote blade position indicator switches





### **NOTES**

- Values shown in parenthesis ( ) indicate metric units.
- Units furnished approximately 1/4" (6mm) smaller than given opening dimensions.

# LEAKAGE AND PERFORMANCE DATA



### LEAKAGE AND PERFORMANCE

All data represented in this literature are based on tests performed in accordance with AMCA test standards at Ruskin's AMCA accredited test facility. Third party verification of testing procedures and data are verified through ISO procedure audits.

| CD36                        | Leakage (CFM/Ft²)   |                  |                  |                     |  |  |  |  |
|-----------------------------|---------------------|------------------|------------------|---------------------|--|--|--|--|
| Maximum Damper<br>"A" Width | 1" wg<br>(0.25 kPa) | 4" wg<br>(1 kPa) | 8" wg<br>(2 kPa) | 10" wg<br>(2.5 kPa) |  |  |  |  |
| 48" (1219mm)                | 5.4                 | 10.7             | N/A              | N/A                 |  |  |  |  |

Leakage testing is performed in accordance with ANSI/AMCA Standard 500-D, figure 5.5. Leakage data are based on a closing torque of 5 inch pounds/ft² (0.57N.m).

As defined by AMCA, the maximum allowable leakage for class 2 rated dampers is as follows.

### Leakage Class 2

- -10cfm/ft2 @ 1 inch wg
- -20cfm/ft2 @ 4 inch wg
- -28cfm/ft2 @ 8 inch wg
- -35cfm/ft2 @ 12 inch wg


To calculate leakage at a given pressure, multiply the leakage at 1 inch wg by the square root of the given leakage.

Example: given 5 inches wg 5.4 cfm ( $\sqrt{5}$ ) = 20.07 cfm

Air performance testing is performed in accordance with ANSI/AMCA Standard 500-D, figure 5.3.

| Damper "A" Width | Maximum System Pressure |
|------------------|-------------------------|
| 48" (1219)       | 2.5" wg (.62 kPa)       |
| 36" (914)        | 3.0" wg (.75 kPa)       |
| 24" (610)        | 4.0" wg (1 kPa)         |
| 12" (305)        | 5.0" wg (1.25 kPa)      |

# PRESSURE DROP - DAMPER OPEN (24" X 24" size)



Air Velocity in **FEET** and METERS per minute through FACE AREA.

# MAXIMUM VELOCITY AND RECOMMENDATIONS


| Damper Width "A" Dimension               | Maximum Velocity |       |  |  |  |
|--|------------------|-------|--|--|--|
| in inches (mm)                           | fpm              | m/s   |  |  |  |
| Above 5" (127) through 24" (609)         | 3000             | 15.25 |  |  |  |
| Above 24" (609) through 36" (914)        | 2500             | 12.71 |  |  |  |
| Above 36" (914) through 48" (1219)       | 2000             | 10.17 |  |  |  |
| Velocity recommendation (see note below) | 1500             | 7.6   |  |  |  |


**NOTE:** For optimum sound characteristics and pressure drop performance on dampers with v-groove blades, we recommend sizing dampers for 1,500 fpm. Higher velocities are not recommended for outside air openings, due to water penetration concerns. For best pressure drop and sound performance at higher velocities, consider an airfoil blade damper, such as Ruskin model CD60.

### INSTALLATION

Ruskin model CD36 is not recommended for installation with blades running vertically unless ordered with thrust washers. For proper performance, damper must be installed square and free from racking. Actuator must be installed on linkage side. Opposed blade dampers must be operated from a power blade or shaft. Refer to installation instructions for additional information.

The CD36 is intended to be self supporting only in its largest single section size. Multiple section damper assemblies may require bracing to support the weight of the assembly and to hold against system pressure. Ruskin recommends appropriate bracing to support the damper horizontally at a minimum of every 8 feet of damper width. Vertical assemblies and higher system pressures may require more bracing.







**Typical Envelope Dimensions** 

### \*TYPICAL JACKSHAFT ASSEMBLY

Unless other wise specified, all dampers larger than the maximum single section 48" (1219mm) "A" width of 72" (1829mm) "B" height will be built in equal smaller sections and factory assembled with jackshaft as indicated in the detail to the right. In this detail, the damper is over the 48" (1219mm) width, but is less than 96" (2438mm), so it will be built two sections wide. The height is less than 72" (1829mm) so it remains one section tall. Multiple section dampers are not intended to be structural supports, or self-supporting. Additional bracing is recommended to support the damper weight and support against system pressure. Ruskin recommends appropriate bracing to support the damper horizontally at a minimum of every 96" (2438mm) of damper width. Vertical assemblies and higher pressure systems may require additional bracing.




Ruskin model CD36 is bi-directional, meaning it can be installed with the airflow in either direction. When considering mounting flange location, orientation must be defined to properly communicate the desired results. For definition purposes only, the "front" of the damper can be determined by viewing the jackshaft\*, linkage, and blade rotation. When required, jackshaft is always placed on the "rear" surface of the damper. When viewing the concealed side linkage, the "front" surface is adjacent on the right side. Also, when viewing the linkage, the top blade should rotate clockwise to open, as shown in the blade orientation graphic below. If it does not, rotate the damper 180° so the blade rotation is clockwise to open when viewing the linkage side.



### **DIMENSIONAL DATA**


Ruskin model CD36 is available with a wide variety of factory furnished, installed, and commissioned actuators. Actuators can be installed for a fraction of the cost when compared to field installation. It also makes installation faster and more reliable. Actuators vary from manufacturer to manufacturer, so it is not practical to illustrate every mounting arrangement. The four illustrations below

are intended to be used for general guidance on similar mounting arrangements. These provide typical maximum envelope dimensions for layout purposes. If space is a concern, consult your local Ruskin representative for specific details based on your unique actuator selection and installation requirements.




External side plate mounted actuators

Figure 1




Jackshaft mounted actuators. If "A" width is greater than 9" (229mm) and "B" height is more than 20" (508mm) jackshaft will be used for internally mounted actuators.

Figure 3



"A" width 9" (229mm) x "B" height 20" (508mm) minimum

Figure 2



If "B" height is less than 20" (508mm) it may be necessary to rotate the actuator 90° as illustrated.

Figure 4

# SUGGESTED SPECIFICATION

Furnish and install, at locations shown on plans, or in accordance with schedules, control dampers that meet the following minimum construction standards. Control dampers shall be produced in an ISO9001 certified factory. Frame shall be 16 ga. (1.6mm) galvanized steel structural hat channel with tabbed corners for reinforcement. The blades shall be 6" (152mm) single skin, 16 gage (1.6mm) galvanized steel with three longitudinal grooves to reduce blade deflection. Bearings shall be corrosion resistant, molded synthetic sleeve type turning in an extruded hole in the damper frame. Axles shall be hexagonal positively locked into the damper blade. Linkage shall be concealed out of airstream, within the damper frame to

reduce pressure drop and noise. Blade edge seals shall be PVC coated polyester fabric suitable for -25°F to +185°F (-32°C to +85°C) mechanically locked into the blade edge. Adhesive or clip-on type seals are unacceptable. Jamb seals shall be stainless steel compression type to prevent leakage between blade end and damper frame. Blade end overlapping frame is unacceptable. Multiple section dampers must have factory installed jackshafts unless clearly eliminated by the engineer. Submittal must include leakage, pressure drop, maximum velocity and maximum pressure data based on AMCA Publication 500D. Dampers shall be in all respects equivalent to **Ruskin Model CD36**.

