HARDWARE SCHEDULE

Onity Front Desk System
Front Desk, Guest Cards,2 Day Training

Set #1: Guestroom Entry Door
- 1.5 PR Hinges
- 1 Advance Card Lock – Wing Lever
- 1 Door Closer – w/ 90° Stop
- 1 Perimeter Gasketing
- 1 Vinyl Threshold
- 1 Door Bottom – Notched
- 1 Door Sweep
- 1 Privacy Latch
- 1 One Way Viewer ((2) @ Accessible Rooms)

Smoking Guestroom Entry Doors (substitute the following)
- 1 Door Bottom – Unnotched

Set #2: Bathroom Pocket Doors
- 1 Pocket Door Kit
- 1 Privacy Lock
- 1 Finger Pull

Accessible Bathroom Pocket Doors
- 1 Pocket Door Kit
- 1 Sliding Dr Pull w/Latch

Set #3: Connecting Doors
- 2 PR Spring Hinge
- 1 PR Hinges
- 2 Connecting Latch
- 2 Conn. DR Deadbolt
- 2 Perimeter Gasketing
- 1 Vinyl Threshold
- 2 Door Bottom – Unnotched
- 2 Door Sweeps
- 2 Door Guard w/ Edge
- 2 Wall Stop

Set #4: Bedroom Door
- 1.5 PR Hinges
- 1 Privacy Set
- 1 Wall Stop

Set #5: Bathroom Swing Door
- 1.5 PR Hinges
- 1 Privacy Set
- 1 Roller Bumper

Set #6: Sliding Glass Entry Door
- 1 Remote Reader
- 1 Intercom/Buzzer
- 1 Security Camera
- Balance Of Hardware part of Door Unit

Set #7: Aluminum Exercise Room
- 1 Advance Card Lock – Wing Lever
- 1 Continuous Hinge
- 1 Door Closer

Set #8: Exterior Aluminum Vestibule Swinging Doors
- 1 Remote Reader
- 1 Intercom/Buzzer
- 1 Continuous Hinges
- 1 Panic Devices
- 1 Push/Pulls
- 1 Door Closers
- 1 Threshold
- 1 Door Sweep
- 1 Weatherstrip

Set #9: NOT USED

Set #10: Door to Roof
- 1.5 PR Hinges
- 1 Store Room Lock
- 1 Door Closer
- 1 Weatherstrip
- 1 Threshold
- 1 Door Sweep
- 1 Rain Drip
- 1 Wall Stop

Set #11: Hollow Metal Elevator Equipment Door
- 1.5 PR Hinges
- 1 Store Room Lock
- 1 Door Closer
- 1 Weatherstrip
- 1 Threshold
- 1 Door Sweep
- 1 Rain Drip

Set #12: Exterior Aluminum Egress Door
- 1 Rim Panic Interface
- 1 Continuous Hinges
- 1 Panic Devices
- 1 Push/Pulls
- 1 Door Closers
- 1 Threshold
- 1 Door Sweeps
- 1 Weatherstrip

Set #13:
- 3 PR Hinges
- 1 Store Room Lock
- 2 Flush Bolt
- 2 Door Closer
- 1 Weatherstrip

Set #14:
- 1.5 PR Hinges
- 1 Store Room Lock
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #15:
- 1.5 PR Hinges
- 1 Rim Exit Device
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #16:
- 1.5 PR Hinges
- 1 Rim Panic Interface
- 1 Rim Exit Device
- 1 Door Closer
- 1 Weatherstrip
- 1 Threshold
- 1 Door Sweep
- 1 Rain Drip Cap

Set #17:
- 1.5 PR Hinges
- 1 Advance Cardlock – Wing Lever
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #18:
- 1.5 PR Hinges
- 1 Office Lock
- 1 Wall Stop

Set #19:
- 2 PR Hinges
- 1 Advance Cardlock – Wing Lever
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #20:
- 1.5 PR Hinges
- 1 Advance Cardlock – Wing Lever
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #21:
- 1.5 PR Hinges
- 1 Privacy Set
- 1 Weatherstrip
- 1 Wall Stop
- 2 Kick Plate

Set #22:
- 1.5 PR Hinges
- 1 Rim Exit Device
- 1 Door Closer
- 1 Weatherstrip
- 1 Magnetic Hold Open

Set #23:
- 4 PR Swing Clr Hinges
- 1 Latchset
- 2 Wd Auto Flush Bolt
- 1 Coordinator
- 2 Door Closer
- 1 Weatherstrip
- 1 Magnetic Hold Open

Set #24:
- 2 PR Hvy Wt Hinges
- 1 Advance Cardlock – Wing Lever
- 1 Door Closer
- 1 Weatherstrip
- 1 Wall Stop

Set #25:
- 2 PR Hinges
- 1 Latchset
- 1 Door Closer
- 1 Weatherstrip
- 1 Magnetic Hold Open

Set #26:
- 1.5 PR Hinges
- 1 Store Room Lock
- 1 Wall Stop

Set #27:
- 1.5 PR Hinges
- 1 Advance Cardlock – Wing Lever w/ Weather Pack
- 1 Door Closer
- 1 Weatherstrip
- 1 Threshold
- 1 Door Sweep
- 1 Rain Drip

GENERAL DOOR NOTES

1. ALL DOOR HARDWARE SHALL BE US 32D FINISH (U.N.O.)
2. ALL DOOR CYLINDERS TO BE IC CORE FORMAT TO MATCH PROPERTY STANDARDS.
3. REFER TO SHEET A610 FOR DOOR HEAD & JAMB INFO.
4. REFER TO SHEET A609 FOR WALL TYPES – CROSS REFERENCE AGAINST DOOR FRAME THROAT THICKNESS
5. ALL DOORS SHALL BE PRE-FINISHED (SHOP OR FACTORY)
6. TOPS, BOTTOMS & SIDES OF ALL DOORS SHALL BE PAINTED OR STAINED TO MATCH DOOR.
7. PROVIDE CONSTRUCTION CYLINDERS DURING CONSTRUCTION. FOR DOORS REQ'D TO BE LOCKED REPLACE CONSTRUCTION CYLINDERS PRIOR TO HOTEL OPENING. COORDINATE W/ GENERAL CONTRACTOR.
8. ALL DOORS TO BE MASTER KEYED. COORDINATE KEYING W/ OWNER.
9. ALL LOCKSETS & CYLINDERS ARE SUPPLIED W/ FINAL CORES. PERMANENT KEYING BY DOOR SUBCONTRACTOR.
10. ALL 'EXIT' DOORS MUST BE OPERABLE FROM THE INSIDE W/OUT THE USE OF A KEY, SPECIAL KNOWLEDGE, OR EFFORT.
11. ALL INTERIOR DOOR GLAZING & SIDELITES SHALL BE CLEAR TEMPERED GLASS (U.N.O.)
12. GLAZING AT EXTERIOR DOORS & SIDELITES SHALL BE INSULATED TEMPERED LITES.-- REFER TO ELEVATIONS
13. ALL DOOR HARDWARE SHALL COMPLY W/ ACCESSIBILITY REQ'S FOR ACCESSIBILITY. – FEDERAL, STATE & LOCAL ACCESSIBILITY CODE(S).
14. ALL FULL/HALF VISION DOORS SHALL BE A MEDIUM STILE (U.N.O.)
15. ALL RATED DOORS SHALL BE PROVIDED W/ MIN. REQ.'D DOOR HARDWARE REGARDLESS IF NOT SHOWN ON SCHEDULE. IF DIRECTION INDICATED OR NOTED IS SPECIFICALLY IN CONTRADICTION TO WHAT IS REQ'D. IN RATED DOORS, CONTACT ARCHITECT.
16. WHERE UNDERCUT NOT SPECIFIED, STANDARD UNDERCUT OF 3/4" FOR HM & WOOD DOORS.
17. 1 1/2" PAIR BUTT HINGES PER DOOR LEAF UP TO 7'-0". SOLID CORE WOOD OR HM DOORS FROM 7'-0" TO 10'-0" PROVIDE 2 PAIR BUTT HINGES PER DOOR LEAF. DOORS 10'-1" TO 14'-0" IN HEIGHT, PROVIDE 2 1/2 PAIR HINGES PER DOOR LEAF.
18. PROVIDE (3) SILENCERS IN SINGLE LEAF DOORS, (2) SILENCERS IN DOUBLE LEAF DOORS UNLESS PAIR OF DOORS HAS MIDDLE MULLION THEN PROVIDE A TOTAL (6) SILENCERS
19. LOCKSET SHALL OPERATE WHERE TURNING KEY UNLATCHES DOOR WHEN PUSHBUTTON IS ENGAGED & TURNED, KEY OPERATION WILL BE REQ'D @ ALL TIMES. RELEASING PUSHBUTTON UNLOCKS DOOR.
20. REFER TO INTERIOR ELEVATIONS FOR DOOR FINISHES. DOORS SPECIFIED W/ A MILLWORK FINISH SHALL BE FINISHED BY MILLWORK CONTRACTOR TO MATCH MILLWORK IN THAT ROOM/AREA
21. PROVIDE REMOTE CARD READERS @ ALL EXTERIOR DOORS, INCLUDING MAIN ENTRY, & @ EXERCISE ROOM, INDOOR POOL, GUEST LAUNDRY & @ LINEN STORAGE ROOMS.
22. ALL EXTERIOR HOLLOW METAL DOORS SHALL BE GALVANIZED & INSULATED.
23. ALL EXTERIOR DOORS SHALL BE PROVIDED W/ AN ALUMN. DRIP EDGE ANCHORED TO UNDERSIDE OF WALL CONSTRUCTION (DOORS AS PART OF AN ALUMN. STOREFRONT SYSTEM W/ A TRANSOM LITE DO NOT REQUIRE DRIP EDGE – NOR DO DOORS THAT ARE PROTECTED UNDER CANOPIES.
24. ALL EXTERIOR DOORS SHALL HAVE THE TOP OF THE DOOR SLAB CONSTRUCTED IN SUCH A WAY TO SHED & THEREFORE PREVENT WATER FROM COLLECTING/SITTING W/IN THE TOP OF THE DOOR SLAB. JOINTS SHALL BE MINIMIZED @ THE TOP OF DOOR SLAB, ANY CONSTRUCTION JOINTS SHALL BE FULLY WEATHER TIGHT.
25. GLAZING @ EXTERIOR DOORS & SIDELITES SHALL BE INSULATED TEMPERED LIGHTS.-- REFER TO ELEVATIONS & WINDOW SCHEDULE(S) FOR GLASS COLOR & SPECS.
26. SIGNAGE SHALL BE INSTALLED ON THE WALL ADJACENT TO THE LATCH SIDE OF DOORS. CENTERLINE OF SIGN SHALL BE 60"A.F.F. TO THE CENTERLINE OF THE SIGN AS INDICATED.
27. REFER TO HOME 2 SUITES BY HILTON STANDARDS MANUAL FOR ADDITIONAL INF'O REGARDING DOOR & DOOR HARDWARE REQ'S.
28. ALL DOOR HARDWARE SETS LISTED ARE RECOMMENDED ITEMS. REFER TO THE STANDARDS MANUAL FOR REQ'S.
29. ALL DOORS MUST HAVE A 32" MIN. CLEAR WIDTH OPENING WHEN DOOR IS FULLY OPEN.
30. THRESHOLDS @ ACCESSIBLE DOORS TO MEET ALL APPROPRIATE ACCESSIBILITY REQS. ACCESSIBLE DOORS INCLUDE ALL PUBLIC ACCESS SPACES, ALL PUBLIC EXTERIOR DOORS, ALL EGRESS DOORS, & EMPLOYEE DOORS THAT ARE INDICATED W/ A CLEAR FLOOR AREA.
31. EXTERIOR DOORS MUST HAVE WEATHER-STRIPPING W/ THE APPROPRIATE TYPE OF THRESHOLD.
32. OUT-SWINGING EXTERIOR METAL DOORS MUST HAVE CLOSED TOPS.
33. ALL ROOFTOP EXITS (DOORS & HATCHES) MUST BE EQUIPPED W/ A PANIC BAR OR OTHER RELEASING DEVICE, LATCHING HARDWARE, & ALARM THAT IS MONITORED IN THE SECURITY DISPATCH OFFICE OR PBX. THESE DOORS MUST HAVE A SIGN ON THE INSIDE FACE INDICATING THE DOOR IS ALARMED & TO BE USED IN EMERGENCY SITUATIONS ONLY, IF ACCESSIBLE TO THE PUBLIC.

ABBREVIATIONS*

14	14 GAUGE HOLLOW METAL
16	16 GAUGE HOLLOW METAL
18	18 GAUGE HOLLOW METAL
ALUM	ALUMINUM
ANO	ANODIZED
COMM	COMMUNICATING
DBL	DOUBLE
ET	ETCHED
FV	FIELD VERIFY
GALV	GALVANIZED
GL	GLASS/GLAZING
HC	HOLLOW CORE
HM	HOLLOW METAL
HVY WT	HEAVY WEIGHT
INT	INTERIOR DESIGN DRAWINGS
K	KAWNEER FINISH
LH	LEFT HAND
LHA	LEFT HAND – ACTIVE LEAF
LHR	LEFT HAND REVERSE BEVEL
LHRA	LEFT HAND REVERSE – ACTIVE LEAF
LVL	LEVEL
MF	4" MASONRY HEADER FRAME
OHCC	OVERHEAD CONCEALED CLOSER
PR	PAIR
PT	PAINT
PGB	PAINT GRADE BIRCH
PSNB	PLAIN SLICED NATURAL BIRCH – PREFINISHED CUSTOM COLOR
PSWB	PLAIN SLICED SELECT WHITE BIRCH – PREFINISHED CUSTOM COLOR
PSWM	PLAIN SLICED WHITE MAPLE – PREFINISHED CUSTOM COLOR
RTP	REFER TO PLANS
RH	RIGHT HAND
RHA	RIGHT HAND – ACTIVE LEAF
RHR	RIGHT HAND REVERSE BEVEL
RHRA	RIGHT HAND REVERSE – ACTIVE LEAF
SC	SOLID CORE
SGL	SINGLE
SM	SURFACE MOUNTED
SSLD	SOLID STILE LOUVERED DOOR
SST	STAINLESS STEEL
STRFT	STOREFRONT (ALUMN.)
STL	STEEL
ST	STAIN
ST+PT	STAIN PUBLIC SIDE, PAINT GUESTROOM OR "BACK OF HOUSE SIDE"
TMF	TIMELY METAL FRAME
VIF	VERIFY IN FIELD
W	WELDED
WD	WOOD

REFER ALSO TO SHEET G002 TYPICAL * ABBREVIATIONS

Richard Molenaar
ARCHITECT



PROJECT NAME:
HOME 2 SUITES BY HILTON

W Mane Street West Monroe, Lousiana

SHEET TITLE:
Door Schedule & Door Details

PROJECT NO. 13010
LATEST REVISION:
DRAWN BY: acj
CHECKED BY: rm
SHEET NUMBER: A610.1
DATE: Sept 5, 2014